TN 295
.U4

No. 9035



THE LIBRARY OF CONGRESS

IC 9035

Bureau of Mines Information Circular/1985

LIBRARY OF CONGRESS
OCT 22 1985
COPY
EXCHANGE & GIFT DIVISION

Principal Deposits of Strategic and Critical Minerals in Nevada

By N. T. Lowe, Russell G. Raney, and John R. Norberg

UNITED STATES DEPARTMENT OF THE INTERIOR

1910 1985 75 BUREAU OF MINES 75TH ANNIVERSARY

Information Circular 9035

Principal Deposits of Strategic and Critical Minerals in Nevada

By N. T. Lowe, Russell G. Raney, and John R. Norberg

UNITED STATES DEPARTMENT OF THE INTERIOR
Donald Paul Hodel, Secretary

BUREAU OF MINES
Robert C. Horton, Director

TN295
.U4
no.9035

As the Nation's principal conservation agency, the Department of the Interior has responsibility for most of our nationally owned public lands and natural resources. This includes fostering the wisest use of our land and water resources, protecting our fish and wildlife, preserving the environmental and cultural values of our national parks and historical places, and providing for the enjoyment of life through outdoor recreation. The Department assesses our energy and mineral resources and works to assure that their development is in the best interests of all our people. The Department also has a major responsibility for American Indian reservation communities and for people who live in Island Territories under U.S. administration.

Library of Congress Cataloging in Publication Data:

Lowe, N. T. (Nathan T.)

Principal deposits of strategic and critical minerals in Nevada.

(Information circular / United States Department of the Interior, Bureau of Mines ; 9035)

Supt. of Docs. no.: I 28.27:9035.

1. Ore-deposits—Nevada. 2. Strategic materials—Nevada. I. Raney, Russell G. II. Norberg, John R. III. Title. IV. Series: Information circular (United States. Bureau of Mines) ; 9035.

TN295.U4 [TN24.N3] 622s [553.4'09793] 85-600061

For sale by the Superintendent of Documents, U.S. Government Printing Office
Washington, D.C. 20402

CONTENTS

	Page
Abstract	1
Introduction	2
Acknowledgments	2
Organization of report	2
Commodity and deposit selection	3
Summary of mining activity in Nevada	6
Infrastructural and institutional factors affecting mining activities in Nevada	7
Utilities	7
Electricity	7
Natural gas	7
Water	10
Transportation	12
Rail	12
Road	15
Regulation and taxation	19
Mining regulations	19
Taxation	19
Mineral processing facilities	20
Milling facilities	20
Smelting and refining	30
Review of selected mineral commodities in Nevada	32
Aluminum	32
Antimony	34
Barite	36
Beryllium	38
Copper	40
Fluorspar	42
Gold	42
Iron ore	46
Lead and zinc	48
Lithium	50
Magnesium	52
Manganese	54
Mercury	56
Molybdenum	58
Silver	60
Tungsten	62
Abstracts of selected deposits in Nevada	64
Alligator Ridge	66
Ann	67
Ann Mason	68
Antimony King	69
Argenta	70
Atlanta	71
Aurora	72
B & B	73
B & C Springs	74
Bald Mountain	75
Basic, Inc.	76
Battle Mountain Copper Basin	77
Battle Mountain Copper Canyon	78
Bear	79
Bell Mountain	80
Big Ledge	81
Bisoni	82
Bloody Canyon	83
Blue Star	84
Bootstrap	85
Borealis	86
Boulder City	87
Bray-Beulah	88
Buckhorn	89
Buckingham	90
Buena Vista	91
Bullion-Monarch	92
C-M Alunite	93
Calico Hills	94
Candelaria	95
Carlin	96
Carson River	97
Caselton	98
Crowell	99
Dayton	100
Dee	101
Dodge-Ford	102
Dry Canyon	103
East Northumberland	104
Easy Miner	105
Emerson	106
Enfield Bell	107
Fannie Ryan	108
Fencemaker	109
Fish Creek	110
Garnet-Tennessee Mountain	111
Getchell	112
Gibellini	113
Gold Quarry	114
Goldfield	115
Goldstrike	116
Gooseberry	117
Greystone	118
Gunmetal	119
Hard Luck-Pradier	120
Heavy Spar	121
Hollywood	122
Horse Canyon	123
Indian Springs	124
Jungle	125
Kay	126
Lakes	127
Linka	128
Maggie Creek	129
Mammoth	130
Manhattan	131
McArthur	132
McDermitt	133
McGill Tailings	134
Minnesota	135
Modarelli	136
Montana Mountains	137
Mount Hope	138
Mount Wheeler	139
Mountain Springs	140
Nevada Moly	141
Nevada Scheelite	142
Northumberland	143
Nyco	144
Overton	145
P & S	146
Pan American	147
Phelps-Stokes	148
Pinson	149
Piute	150
Preble	151

	Page
Prince	152
Pumpkin Hollow	153
Queen Lode	154
Rain	155
Rainbow	156
Relief Canyon	157
Ridge 7129	158
Robinson district	159
Rochester	160
Rossi	161
Round Mountain	162
Ruby Hill	163
Santa Fe	164
Silver Peak	165
Sixteen-to-One	166
Snoose	167
Springer	168
Sterling	169
Stormy Creek	170
Sutherland	171
Taylor	172
Three Kids	173
Tonkin Springs	174
Tonopah	175
Tonapah Divide	176
Tonopah Hasbrouck	177
Victoria	178
Virgin River	179
Ward	180
White Caps	181
White Pine	182
Windfall	183
Yerington	184
References	185
Appendix A.—List of symbols and abbreviations	202
Appendix B.—Common conversion factors	202

ILLUSTRATIONS

1. Location of selected principal deposits in Nevada 4
2. Major electrical transmission lines, principal substations, and in-state generating facilities in Nevada 8
3. Major certificated electricity service areas in Nevada 9
4. Natural gas distribution system in Nevada 11
5. Hydrographic regions and designated ground water recharge areas of Nevada 13
6. Rail network of Nevada 14
7. General highway map of Nevada 16
8. Highway distances between principal Nevada communities 17
9. Highway accessibility for transporting nonreducible loads above legal weight limits 18
10. Selected beneficiation facilities in Nevada 21
11. Regional secondary processing facilities significant to Nevada 30
12. Aluminum in Nevada 33
13. Antimony in Nevada 35
14. Barite in Nevada 37
15. Beryllium in Nevada 39
16. Copper in Nevada 41
17. Fluorspar in Nevada 43
18. Gold in Nevada 45
19. Iron in Nevada 47
20. Lead-zinc in Nevada 49
21. Lithium in Nevada 51
22. Magnesium in Nevada 53
23. Manganese in Nevada 55
24. Mercury in Nevada 57
25. Molybdenum in Nevada 59
26. Silver in Nevada 61
27. Tungsten in Nevada 63
28. Location of principal deposits with deposit abstracts 65

TABLES

1. Selected principal deposit index 5
2. Distribution of principal deposits of selected commodities in Nevada, by county 6
3. Representative industrial electrical power rates in Nevada 10
4. Nevada water summary 12
5. Rail carriers and railage 15
6. Permits required in Nevada before initiation of mining or milling 20
7. Numerical index of selected beneficiation facilities in Nevada 22
8. Selected beneficiation facilities in Nevada 23
9. Deposit abstract index 64

UNIT OF MEASURE ABBREVIATIONS USED IN THIS REPORT

cm	centimeter	m^3/h	cubic meter per hour
g	gram	mi^2	square mile
g/t	gram per metric ton	oz	ounce
gal/min	gallon per minute	ppm	parts per million
gal/ton	gallon per short ton	t	metric ton
ha	hectare	t/a	metric ton per year
kg	kilogram	t/d	metric ton per day
kg/t	kilogram per metric ton	t/h	metric ton per hour
km	kilometer	t/month	metric ton per month
km^2	square kilometer	t/wk	metric ton per week
kV	kilovolt	ton	short ton
kW	kilowatt	ton/h	short ton per hour
kW·h	kilowatt hour	ton/yr	short ton per year
L/s	liter per second	tr oz	troy ounce
L/t	liter per metric ton	tr oz/ton	troy ounce per short ton
lb	pound	wt %	weight percent
MW	megawatt	yd^3	cubic yard
m	meter	yd^3/a	cubic yard per year
m^2	square meter	yd^3/d	cubic yard per day
m^3	cubic meter	yd^3/h	cubic yard per hour
m^3/d	cubic meter per day	yr	year

PRINCIPAL DEPOSITS OF STRATEGIC AND CRITICAL MINERALS IN NEVADA

By N. T. Lowe,[1] Russell G. Raney,[2] and John R. Norberg[3]

ABSTRACT

This Bureau of Mines publication presents salient deposit information in abstract form on 119 principal mineral deposits in the State of Nevada. Commodity coverage addresses 17 critical and strategic commodities that appear to have commercial production potential in the State. The core of the deposits described is taken from those properties evaluated under the Bureau of Mines Minerals Availability Program (MAP); additional deposits are included to provide a more complete coverage. Institutional and infrastructural factors affecting mineral development are also discussed.

[1]Physical scientist.
[2]Geologist.
[3]Supervisory physical scientist.
Western Field Operations Center, Bureau of Mines, Spokane, WA.

INTRODUCTION

About a decade ago, the Bureau of Mines embarked upon an ambitious program to systematically assess mineral supplies available to the U.S. economy. The Minerals Availability Program (MAP), formally established in 1974 (*727*),[4] provides current appraisals of nonfuel mineral supplies for consideration in the development of U.S. minerals policies. Results of these appraisals are published on a commodity basis in a series of availability reports that describe the supply of a commodity from domestic or foreign sources in terms of tonnage-price relationships.

The keystones of MAP appraisals are deposit-specific evaluations conducted by geologists and engineers of the Bureau's Field Operations Centers and by contractors. The deposit evaluations examine in detail the geologic, engineering, and economic factors that determine the viability of individual deposits. Deposit data are obtained from many sources, including published and unpublished Bureau reports, records, and files; U.S. Geological Survey (USGS) Bulletins, Professional Papers, and other reports; technical and professional journals; State and other Federal agency publications; proprietary company reports; data generated during field examinations; and information obtained from knowledgeable individuals.

The Bureau's purpose in publishing this prototype report is to present, in a single volume, nonproprietary data on 119 selected principal deposits of strategic and critical minerals in the State of Nevada. The easy-to-read format provides locational, geological, and operational data for selected deposits along with discussions of institutional and infrastructural factors affecting mineral development in the State.

Much of the deposit-specific data were derived from MAP deposit evaluations that have been conducted over the past 10 yr. Additional deposit data, as well as information on transportation, water, electricity, natural gas, and taxes were gathered from recent newspapers and journals and from interviews with company and State officials. Data on mineral production and mining history were obtained from Bureau and Nevada Bureau of Mines publications. It is anticipated that the information contained in this publication will be of benefit to geologists, mining engineers, prospectors, mining companies, suppliers of mining and milling equipment, and others directly involved in the State's mineral industry. It is also anticipated that the data will be equally as valuable to city, county, and State planners, transportation and utilities commissions, local tax advisory boards, and other public and private organizations that develop policies affecting mining and mineral development in Nevada.

ACKNOWLEDGMENTS

The authors wish to thank the State of Nevada, Division of Environmental Protection and Nevada Division of Mine Inspection, for their assistance and information. In addition, the authors wish to thank the Nevada Department of Transportation for graciously allowing the use of State highway base maps in this publication.

Special gratitude is extended to the entire staff of the Nevada Bureau of Mines and Geology. Particular thanks is given to J. H. Schilling, director; K. Papke, assistant director; H. F. Bonham, Jr., geologist; and J. Tingley, mining geologist, for their assistance in selecting the deposits included in this report, as well as providing supplemental deposit data.

ORGANIZATION OF REPORT

This publication is organized into two principal sections: an introductory statewide section followed by a site-specific deposit section.

The introductory section presents background information on the minerals industry of Nevada, a description of some existing infrastructure-institutional factors that affect commercial development of Nevada's mineral deposits, and a commodity review.

The infrastructure subsection contains brief discussions and maps of the transportation (highway and railroad) and utility (electricity, natural gas, and water) networks in the State. It also contains general information on milling or beneficiation facilities, and permitting and taxation procedures and policies with respect to mineral development in Nevada.

The commodity review consists of narrative, tabular, and map data that are intended to give a statewide overview of principal commodities associated with the deposits described. In addition to a brief narrative, each review contains data abstracted from the Bureau's Minerals Industry Location System (MILS). Production data were obtained from the Bureau's Minerals Yearbooks and Mineral Commodity Summaries, and from other published or publicly available sources (*728-729*). The reviews also include a listing of selected principal deposits in the State. (Most of the principal deposits are described in greater detail in the deposit abstract section.) The reserve-resource estimates are from published sources and, where necessary, have been converted to the International System of Units (SI) equivalents for ease of comparison. The column headed "Size" reflects the authors' professional judgment of the total resource contained in the deposit. The terms "small," "medium," and "large" are based primarily on the size categories published by the USGS (*236*); definitions of the terms are provided for each commodity. The associated loca-

[4]Italic numbers in parentheses refer to items in the list of references preceding the appendixes.

tion map shows the principal deposits along with other occurrences of the commodity.

The largest section of the publication is the deposit abstract section. It is composed of a series of single-page summaries of information pertaining to 119 selected mineral properties in Nevada. The summaries or abstracts are arranged alphabetically by the property's primary name. They are intended to report deposit information available through 1984; undoubtedly, the status, ownership, and some other data may have changed during the period between manuscript completion and report publication.

Each abstract is composed of the following six main subject areas:

1. Deposit name and commodity.
2. Location and ownership.
3. Geology.
4. Development.
5. Published reserves and/or resources.
6. References.

Within each subject area there are several individual data elements. Not all data elements, however, are reported for each deposit; proprietary data have been omitted and some information has yet to be determined or is not presently available. SI measurements are used throughout the deposit abstracts except for published reserves and/or resources. Reserve-resource data are reported in terms and units of the cited publication. (It is incumbent upon the reader to evaluate the reserve-resource data in the light of his or her own knowledge, experience, and assessment of the source's credibility.) In contrast, published reserve-resource data in the commodity reviews have been converted by the authors into SI measurements for comparison purposes. The reference section includes bibliographic references for the deposit, the USGS 1:250,000 quadrangle and largest scale map on which the deposit is located, and the Bureau's file reference or sequence number. The sequence number is a 10-digit number that is unique to the deposit and allows rapid retrieval of relevant data from the MAP data base. Two other file references, the Mine Safety and Health Administration (MSHA) number (Mid number), which is assigned by MSHA to active properties, and the USGS Mineral Resources Data System (MRDS), are also included. The MRDS is the former USGS Computerized Resources Information Bank (CRIB).

An extensive, but not exhaustive, reference section follows the deposit abstracts. The intent of the reference section is to provide the reader with additional sources of information about the deposits described in the main body of the report. Although an individual reference may not specifically mention the deposit, the reference contains geological, mining, metallurgical, economic, or other data pertinent to the deposit.

COMMODITY AND DEPOSIT SELECTION

This publication is in a sense a directory of principal strategic and critical mineral deposits in the State of Nevada. Deposit and commodity coverage mainly reflects the Bureau's work conducted under MAP. The MAP is concerned with a continuing assessment of the geologic, engineering, and economic availability of mineral supplies for the U.S. economy. Although the Bureau's ultimate objective is to incorporate all nonfuel mineral commodities into MAP, current MAP studies cover only the following strategic or critical commodities:

Aluminum	Graphite	Potash
Antimony	*Iron*	Rare Earths
Asbestos	*Lead*	*Silver*
Barite	*Lithium*	Sulfur
Beryllium	*Magnesium*	Tin
Chromium	*Manganese*	Titanium
Cobalt	*Mercury*	Thorium
Columbium-Tantalum	*Molybdenum*	*Tungsten*
Copper	Nickel	*Zinc*
Fluorspar	Phosphate	Zirconium-Hafnium
Gold	Platinum	

All of these commodities, with exception of hafnium, reportedly occur in Nevada. Based on current knowledge, however, only those commodities in italics appear to have potential commercial production opportunities; this publication focuses on deposits whose principal commodity is one of the 17 commodities so indicated.

Under MAP, the Bureau has evaluated nearly 100 deposits in Nevada. Most were found to have identified reserves or resources; it is these deposits that form the core of the deposit abstract section in this report. Descriptions of other properties that appear to have commercial potential and which have yet to be evaluated under MAP, are also included to provide a more complete commodity coverage.

Final deposit selection was made after consultation with individuals and agencies familiar with the Nevada mining industry. In addition to hosting one of the commodities listed (as a principal commodity), deposit selection was based on one or more of the following criteria:

1. The deposit has been evaluated under MAP.
2. Information on substantial reserves or resources has been published for the deposit.
3. The deposit is a producing or past producing mine with known production potential.
4. The deposit is a nonproducing property with a known production potential based on proprietary and/or public exploration and economic data.
5. Sufficient nonproprietary geological and operational data exist to permit completion of a deposit abstract.

Figure 1 and table 1 show the locations and names of the 167 principal deposits selected for this report; deposit abstracts have been prepared for 119 of the principal deposits.

Table 2 shows the distribution (by commodity) of principal deposits and properties with deposit abstracts for each county.



Figure 1.—Location of selected principal deposits in Nevada.

Table 1. — Selected principal deposit index

(Refer to figure 1)

Map No.	Deposit name	(1)	Map No.	Deposit name	(1)	Deposit name	(1)	Map No.	Deposit name	(1)	Map No.
1..	Indian Springs[2]	W	84.	Robinson district[2]	Cu	Alligator Ridge[2]	Au	75	Indian Springs[2]	W	1
2..	Jungle[2]	$BaSO_4$	85.	Ward[2]	Pb-Zn	Ann[2]	$BaSO_4$	101	Ivanhoe	Au	27
3..	Easy Miner[2]	$BaSO_4$	86.	Taylor[2]	Ag	Ann Mason[2]	Cu	115	Jungle[2]	$BaSO_4$	2
4..	Wells	W	87.	Mount Wheeler[2]	Be	Antimony King[2]	Sb	92	Kay[2]	$BaSO_4$	99
5..	Snoose[2]	$BaSO_4$	88.	Altanta[2]	Au	Argenta[2]	$BaSO_4$	55	Lakes[2]	$BaSO_4$	14
6..	Big Ledge[2]	$BaSO_4$	89.	White Pine[2]	CaF_2	Argentena	Pb-Zn	165	Lewis	Au	38
7..	Stormy Creek[2]	$BaSO_4$	90.	Linka[2]	W	Atlanta[2]	Au	88	Linka[2]	W	90
8..	Garnet-Tennessee Mountein[2].	W	91.	Dry Canyon	Au	Aurora[2]	Au	131	Lucerne	Au	110
			92.	Antimony King[2]	Sb	B & B[2]	Hg	139	Maggie Creek[2]	Au	18
9..	Mesona	Au	93.	Dry Canyon[2]	Sb	B & C Springs[2]	Mo	127	Mammoth[2]	CaF_2	152
10.	Enfield Bell[2]	Au	94.	Brey-Beulah[2]	Sb	Bald Mountain[2]	Au	74	Manhattan[2]	Au	105
11.	Gance Creek	Au	95.	Hard Luck-Pradier[2]	Sb	Bald Mountain	$BaSO_4$	70	McArthur[2]	Cu	113
12.	Q-Bar	$BaSO_4$	96.	Reeds Canyon	$BaSO_4$	Basic, Inc.[2]	MgO	124	McDermitt[2]	Hg	28
13.	Dexter	Au	97.	Victorine-Kingston	Au	Battle Mountain Copper Basin[2].	Cu	56	McGill Tailings[2]	Cu	83
14.	Lakes[2]	$BaSO_4$	98.	P & S[2]	$BaSO_4$				Mesona	Au	9
15.	Fish Creek[2]	$BaSO_4$	99.	Key[2]	$BaSO_4$	Battle Mountein Copper Canyon[2].	Au	58	Miller	$BaSO_4$	59
16.	Heavy Spar[2]	$BaSO_4$	100	Northumberland[2]	Au				Minnesota[2]	Fe	112
17.	Gold Querry[2]	Au	101	Ann[2]	$BaSO_4$	Bear[2]	Cu	117	Modarelli[2]	Fe	66
18.	Maggie Creek[2]	Au	102	East Northumberland[2].	$BaSO_4$	Bell Mountain[2]	Au	120	Mohawk	Ag	145
19.	Carlin[2]	Au				Big Ledge[2]	$BaSO_4$	6	Montana Mountains[2]	Li	29
20.	Bullion Monarch[2]	Au	103	Round Mountain[2]	Au	Bisoni[2]	CaF_2	79	Monte Cristo	W	82
21.	Blue Ster[2]	Au	104	White Caps[2]	Sb	Bloody Canyon[2]	Sb	41	Mount Hope[2]	Mo	73
22.	Goldstrike[2]	Au	105	Manhattan[2]	Au	Blue Star[2]	Au	21	Mount Wheeler[2]	Be	87
23.	Bootstrap[2]	Au	106	Nevada Moly[2]	Mo	Bootstrap[2]	Au	23	Mountain Springs[2]	$BaSO_4$	64
24.	Dee[2]	Au	107	Gooseberry[2]	Ag	Borealis[2]	Au	130	Mountain View	Pb-Zn	76
25.	Queen Lode[2]	$BaSO_4$	108	Dayton[2]	Fe	Boulder City[2]	Mn	166	Nevada Moly[2]	Mo	106
26.	Rossi[2]	$BaSO_4$	109	Gold Hill	Au	Boyd	Al	157	Nevada Scheelite[2]	W	122
27.	Ivanhoe	Au	110	Lucerne	Au	Bray-Beulah[2]	Sb	94	New Potosi	Sb	138
28.	McDermitt[2]	Hg	111	Carson River[2]	Hg	Buckhorn[2]	Au	67	Northumberland[2]	Au	100
29.	Montena Mounteins[2]	Li	112	Minnesota[2]	Fe	Buckingham[2]	Mo	57	Nyco[2]	CaF_2	150
30.	Getchell[2]	Au	113	McArthur[2]	Cu	Buckskin	Au	114	Overton[2]	MgO	159
31.	Tonopah[2]	W	114	Buckskin	Au	Buena Vista[2]	Fe	48	P & S[2]	$BaSO_4$	98
32.	Riley Extension	W	115	Ann Mason[2]	Cu	Bullion Monarch[2]	Au	20	Pan American[2]	Pb-Zn	155
33.	Riley	W	116	Yerington[2]	Cu	C-M Alunite[2]	Al	158	Paraside Peak	Au	128
34.	Granite Creek	W	117	Bear[2]	Cu	Calico Hills[2]	Fe	119	Phelps-Stokes[2]	Fe	123
35.	Pinson[2]	Au	118	Pumpkin Hollow[2]	Fe	Candelaria[2]	Ag	137	Pilot Mountain district.	Hg	135
36.	Preble[2]	Au	119	Calico Hills[2]	Fe	Carlin[2]	Au	19			
37.	Hog Ranch	Au	120	Bell Mountain[2]	Au	Carson River[2]	Hg	111	Pine Nut	Mo	136
38.	Lewis	Au	121	Rewhide	Au	Caselton[2]	Pb-Zn	153	Pinson[2]	Au	35
39.	Springer[2]	W	122	Neveda Scheelite[2]	W	Chicago Lode	CaF_2	126	Piute[2]	Fe	49
40.	Florida Canyon	Au	123	Phelps-Stokes[2]	Fe	Cortez	Au	69	Pleasant View	$BaSO_4$	60
41.	Bloody Canyon[2]	Sb	124	Basic, Inc.[2]	MgO	Crowell[2]	CaF_2	147	Potosi	Pb-Zn	163
42.	Rochester[2]	Ag	125	Union Canyon	CeF_2	Dayton[2]	Fe	108	Preble[2]	Au	36
43.	Sutherland[2]	Sb	126	Chicago Lode	CaF_2	Dee[2]	Au	24	Prince[2]	Pb-Zn	154
44.	Relief Canyon[2]	Au	127	B & C Springs[2]	Mo	Desert Scheelite	W	134	Pumpkin Hollow[2]	Fe	118
45.	Hollywood[2]	Sb	128	Peradise Peek	Au	Dexter	Au	13	Q-Ber	$BaSO_4$	12
46.	Fencemeker[2]	Sb	129	Hawthorne	Al	Dodge-Ford[2]	Fe	47	Queen Lode[2]	$BeSO_4$	25
47.	Dodge-Ford[2]	Fe	130	Boreelis[2]	Au	Drumm	Sb	51	Rein[2]	Au	54
48.	Buene Viste[2]	Fe	131	Aurore[2]	Au	Dry Cenyon	Au	91	Rainbow[2]	CaF_2	149
49.	Piute[2]	Fe	132	Sante Fe[2]	Au	Dry Canyon[2]	Sb	93	Rawhide	Au	121
50.	Hoyt	Sb	133	Gunmetal[2]	W	East Northumberland[2].	$BaSO_4$	102	Reeds Canyon	$BaSO_4$	98
51.	Drumm	Sb	134	Desert Scheelite	W				Relief Canyon[2]	Au	44
52.	IHX	Sb	135	Pilot Mountain district.	Hg	Easy Miner[2]	$BaSO_4$	3	Ridge 7129[2]	Zn	81
53.	Victorie[2]	Cu				Eldorado Cenyon	Au	167	Riley	W	33
54.	Rein[2]	Au	136	Pine Nut	Mo	Emerson[2]	W	156	Riley Extension	W	32
55.	Argenta[2]	$BeSO_4$	137	Cendelarie[2]	Ag	Enfield Bell[2]	Au	10	Robinson district[2]	Cu	84
56.	Bettle Mountein Copper Basin[2].	Cu	138	New Potosi	Sb	Fennie Ryan[2]	Mn	161	Rochester[2]	Ag	42
			139	B & B[2]	Hg	Fencemaker[2]	Sb	46	Rossi[2]	$BeSO_4$	26
57.	Buckinghem[2]	Mo	140	Tonopah Hasbrouck[2]	Au	Fire Creek	Au	62	Round Mountain[2]	Au	103
58.	Bettle Mountein Copper Cenyon[2].	Au	141	Tonopah Divide[2]	Au	Fish Creek[2]	$BeSO_4$	15	Ruby Hill[2]	Pb-Zn	77
			142	Goldfield[2]	Au	Florida Canyon	Au	40	Sente Fe[2]	Au	132
59.	Miller	$BaSO_4$	143	Goldfield district	Al	Gance Creek	Au	11	Silver Peak[2]	Li	144
80.	Pleasant View	$BaSO_4$	144	Silver Peak[2]	Li	Garnet-Tennessee Mountein[2].	W	8	Sixteen-to-One[2]	Ag	146
81.	Sleven Cenyon	$BaSO_4$	145	Mohewk	Ag				Sleven Canyon	$BeSO_4$	61
82.	Fire Creek	Au	146	Sixteen-to-One[2]	Ag	Getchell[2]	Au	30	Snoose[2]	$BaSO_4$	5
63.	Hilltop	Au	147	Crowell[2]	CaF_2	Gibellini[2]	Mn	80	Springer[2]	W	39
84.	Mountein Springs[2]	$BaSO_4$	148	Sterling[2]	Au	Gold Ber	Au	72	Sterling[2]	Au	146
65.	Greystone[2]	$BeSO_4$	149	Reinbow[2]	CaF_2	Gold Hill	Au	109	Stormy Creek[2]	$BeSO_4$	7
68.	Moderelli[2]	Fe	150	Nyco[2]	CaF_2	Gold Querry[2]	Au	17	Sutherlend[2]	Sb	43
67.	Buckhorn[2]	Au	151	Horseshoe	CeF_2	Goldfield[2]	Au	142	Taylor[2]	Ag	86
68.	Horse Cenyon[2]	Au	152	Memmoth[2]	CeF_2	Goldfield district	Al	143	Three Kids[2]	Mn	162
89.	Cortez	Au	153	Ceselton[2]	Pb-Zn	Goldstrike[2]	Au	22	Tonkin Springs[2]	Au	71
70.	Bald Mountain	$BeSO_4$	154	Prince[2]	Pb-Zn	Gooseberry[2]	Ag	107	Tonopeh[2]	W	31
71.	Tonkin Springs[2]	Au	155	Pen Americen[2]	Pb-Zn	Granite Creek	W	34	Tonopah Divide[2]	Au	141
72.	Gold Ber	Au	156	Emerson[2]	W	Greystone[2]	$BeSO_4$	65	Tonopeh Hasbrouck[2]	Au	140
73.	Mount Hope[2]	Mo	157	Boyd	Al	Gunmetel[2]	W	133	Union Canyon	CaF_2	125
74.	Bald Mountein[2]	Au	158	C-M Alunite[2]	Al	Herd Luck-Predier[2]	Sb	95	Victorie[2]	Cu	53
75.	Alligetor Ridge[2]	Au	159	Overton[2]	MgO	Hawthorne	Al	129	Victorine-Kingston	Au	97
78.	Mountein View	Pb-Zn	160	Virgin River[2]	Mn	Heevy Spar[2]	$BeSO_4$	16	Virgin River[2]	Mn	160
77.	Ruby Hill[2]	Pb-Zn	161	Fennie Ryan[2]	Mn	Hilltop	Au	63	Ward[2]	Pb-Zn	85
78.	Windfell[2]	Au	162	Three Kids[2]	Mn	Hog Ranch	Au	37	Wells	W	4
79.	Bisoni[2]	CeF_2	163	Potosi	Pb-Zn	Hollywood[2]	Sb	45	White Ceps[2]	Sb	104
80.	Gibellini[2]	Mn	164	Yellow Pine	Pb-Zn	Horse Cenyon[2]	Au	68	White Pine[2]	CaF_2	89
81.	Ridge 7129[2]	Zn	165	Argentene	Pb-Zn	Horseshoe	CeF_2	151	Windfell[2]	Au	78
82.	Monte Cristo	W	168	Boulder City[2]	Mn	Hoyt	Sb	50	Yellow Pine	Pb-Zn	164
83.	McGill Tellings[2]	Cu	167	Eldoredo Canyon	Au	IHX	Sb	52	Yerington[2]	Cu	118

[1]Primery commodity. [2]Deposit abstract in report.

Table 2. — Distribution of principal deposits of selected commodities in Nevada, by county

County	Aluminum		Antimony		Barite		Beryllium		Copper		Fluorspar		Gold		Iron ore		Lead-zinc	
	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs
Carson City																		
Churchill ..			3										1	1	1	1		
Clark													1				3	
Douglas...													1		1	1		
Elko					11	10			1	1			8	4				
Esmeralda	1												3	3				
Eureka ...											1	1	12	10	1	1	3	2
Humboldt .													4	3				
Lander ...			4	4	8	3			1	1			5	1				
Lincoln ...	2	1											1	1			3	3
Lyon									4	4			1		2	2		
Mineral ...	1		1										4	3	1	1		
Nye			1	1	4	4					8	5	5	4	1	1		
Pershing ..			4	4									2	1	2	2		
Storey													1					
Washoe...													1					
White Pine							1	1	2	2			2	2			1	1
Total ...	4	1	13	9	23	17	1	1	8	8	9	6	52	33	9	9	10	6

	Lithium		Magnesium		Manganese		Mercury		Molybdenum		Silver		Tungsten		Total	
	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Dep	Abs	Deposit	Abstract
Carson City							1	1							1	1
Churchill ..															5	2
Clark			1	1	4	4									9	5
Douglas...															2	1
Elko													3	2	23	17
Esmeralda	1	1					1	1			2	1			8	6
Eureka ...					1	1			1	1					19	16
Humboldt .	1	1					1	1					4	1	10	6
Lander ...									1	1			1	1	20	11
Lincoln ...													1	1	7	6
Lyon															7	6
Mineral ...							1		1		1	1	3	2	13	7
Nye			1	1					2	2					22	18
Pershing ..											1	1	1	1	10	9
Storey											1	1			2	1
Washoe...															1	
White Pine											1	1	1		8	7
Total ...	2	2	2	2	5	5	4	3	5	4	6	5	14	8	167	119

NOTE: — No entry in a column indicates that no principal deposits were identified or no abstract was prepared.

SUMMARY OF MINING ACTIVITIES IN NEVADA (*30, 382, 728*)

Mining has long occupied an important place in the history and economy of Nevada. Through television and movies, millions of Americans are aware, albeit vaguely, of the fabulous wealth created from mining of the State's gold and silver deposits during the late 19th and early 20th century. Some people may also be aware that Nevada achieved statehood in 1864 in part because of the Union's need of precious metals to finance the Civil War. Few people outside the mining community, however, are aware that mining continues as a major contributor to the State's economy. Although only ranked 13th nationally in the value of nonfuel mineral production, Nevada led the nation in 1982 in the output of gold, barite, mercury, and magnesite. In addition, it was second in mine production of diatomite and lithium minerals, and third in output of fluorspar, molybdenum, and tungsten concentrates.

The first mining in Nevada was conducted by Indians in search of turquoise and salt. Franciscan monks and their Mexican converts worked gold placers, silver lodes, and turquoise deposits in Clark County prior to the 1840's. Evidence indicates that Mexicans also mined in the San Antone mining district in about 1854, and French trappers from Canada journeyed as far south as Nye County, perhaps in search of gold or silver, prior to the 1860's. The late 1850's, however, is generally accepted as the beginning of Nevada's mining industry with the discovery of the Potosi Mine in the Goodsprings district, Clark County (1855 or 1857), and the Comstock Lode in Storey County (1859). These discoveries stimulated numerous other discoveries throughout the State, and both the economy and the population increased rapidly.

Over the next two decades, output from the State's mines, particularly those of the Comstock Lode, grew and reached a peak in about 1878. In the 1880's, mineral production began a precipitous decline that continued into the 20th century. Recovery began in the early 1900's with the discovery and subsequent production of silver and gold from ore bodies in the Tonopah, Goldfield, Rochester, and other mining districts. About the same time, significant copper production from the Ely and Yerington districts, and zinc production from the Goodsprings district began. The value of mineral production rose to a peak during World War I, but after the war, metal prices fell and output once again declined.

During the 1930's, in response to increased gold and silver prices and increased demand for base metals, output again increased from Nevada's mines. In spite of periodic setbacks, production generally continued to expand through World War II and into the postwar period. Output reached a peak in 1956 when constant dollar value of mineral production for the State was nearly $202[5] million. In 1957, output slumped 30% when copper prices fell, lead and zinc demand declined, and the Federal Government curtailed the tungsten purchasing program. Since bottoming in 1958 when constant dollar value of mineral production was slightly over $103[5] million, the constant dollar value of production of nonfuel minerals has grown to nearly $254[5] million in 1982.

Although Nevada periodically was among the leading States in domestic production of tungsten, manganese, gold, barite, and mercury, it was the mining, milling, and smelting of copper ores that dominated the State's mineral industry from the mid-1930's to mid-1970's. During a two-decade period, from 1955 to 1974, annual copper production accounted for over 50% of the State's total value of nonfuel mineral output. The only exception during these 20 yr occurred in 1967 when a protracted industry-wide strike resulted in a substantial reduction in copper production. In spite of the strike, the value of copper ore mined in 1967 amounted to nearly $39 million or about 43% of the State's total mineral production.

Nevada's copper output peaked in 1970 when the ore mined yielded nearly 97,000 t of copper valued at over $123 million or about two-thirds of the State's total mineral production. Mine output slowly decreased through the early and mid-1970's; in 1978, it plummeted when the three leading companies ceased operations citing poor market conditions and environmental restrictions as causes. Copper output has increased modestly since the 1979 low point; however, production data are withheld from publication at the request of the producers to safeguard proprietary company data.

Nevada is currently experiencing a modern day "gold rush," and gold has replaced copper as the most important commodity mined in the State. In 1983, for the fourth consecutive year, Nevada led the Nation in primary gold production in which mines yielded more than 47% of the gold produced domestically.

The resurgence of gold mining stems from two unrelated factors. First was the discovery in the early 1960's of low-grade, near-surface, disseminated, micrometer-sized gold resources in northeastern Eureka County. The discovery was followed by development of and subsequent production from the Carlin Mine in 1965 and the Cortez Mine in 1969. Second was the dramatic increase in domestic gold prices caused by the establishment of the two-tier pricing system in March 1968, which created an open market price for gold that could fluctuate with supply and demand, and by the removal of restrictions on private ownership of gold in December 1974.

As a result of these two actions, the price of gold rose from $1.13/g ($35/tr oz) in 1967 to over $19.29/g ($600/tr oz) in 1980, and provided the economic incentive for domestic producers to explore and develop deposits. As a consequence, Nevada has seen a large increase in gold exploration activities over the past decade, which has resulted in the development of many new mines, either currently operating or projected to come on-stream in the next few years. The outlook is for Nevada's mines to yield more than a million ounces annually by the mid-1980's if the present trend continues.

INFRASTRUCTURAL AND INSTITUTIONAL FACTORS AFFECTING MINING ACTIVITIES IN NEVADA

UTILITIES

Electricity

Nevada is served by a mix of investor-owned and publicly owned electric utility systems. Figure 2 displays the distribution of major electrical transmission lines, principal substations, and in-state generating facilities. Figure 3 illustrates the certificated service areas as designated by the Nevada Public Service Commission for the State's larger distribution systems. Several smaller systems occur throughout the State but are not shown on figure 3.

According to the Public Service Commission, utilities having a certificated service area have exclusive rights to market electricity in the area. The utilities also have an obligation to provide power to all new consumers. Service in the uncertificated areas is somewhat competitive with any utility having the right to market electricity subject to granting of a certificate by the Public Service Commission.

As of December 1983, all principal utilities had indicated electrical supplies were generally adequate for new or expanded mining and mineral processing facilities. However, large consumers should expect up to a 2-yr lead time for planning, permitting, and construction of new power lines and ancillary facilities. In addition, mining consumers would be required to pay the total installation cost of facilities serving their operations prior to the beginning of construction. In late 1982, the cost of a 10-MW substation was estimated at about $450,000, any three-phase line at approximately $19,000/km ($30,000/mi), and a 138-kV transmission line at $50,000/km ($80,000/mi). Although recovery of construction capital is generally incorporated into rate schedules, some isolated mining operations have installed diesel-powered plants for generating electricity rather than incur the large capital expenditure required for construction of transmission facilities.

Table 3 presents representative industrial power rates for the principal utilities in Nevada.

Natural Gas (*689*)

Natural gas is supplied to Nevada by two main transmission lines. One line enters the State from the north

[5]1972 constant dollar, gross national product basis.



Figure 2.—Major electrical transmission lines, principal substations, and in-state generating facilities in Nevada.



Figure 3.—Major certificated electricity service areas in Nevada.

Table 3. — Representative industrial electrical power rates in Nevada, December 1983

Utility	Customer monthly meter charge	Demand charge per kW/ month	Energy charge per kW•h used
C. P. National	$5.30	NAp	$0.05132
Harney Electric Cooperative, Inc.	150.00	$5.00	.039
Idaho Power Co.[1]	NAp	2.50	.1557
Lincoln County Power District 1	86.40	1.35	.0099
Mt. Wheeler Power Company	2.60	2.75	[2].0537 [3].0453
Nevada Power Co.	3.50	2.90	.0441
Overton Power District 5	NAp	1.10	[4].030 [5].024
Raft River Rural Electric Cooperative	NAp	4.75	.025 .024
Sierra Pacific Power Co.	NAp	[6]5.18 [7]4.48	.05217
Valley Electric Association, Inc.[8]	NAp	8.176	.028
Wells Rural Electric Co	50.00	4.00	.035

NAp Not applicable.
[1]Idaho Power Co. has made an application to the State of Nevada requesting a 57% increase in the energy charge.
[2]1st 50,000 kW•h.
[3]Over 50,000 kW•h.
[4]1st 100 kW•h.
[5]Over 100 kW•h.
[6]1st 1,000 kW; 1,000-kW minimum.
[7]Over 1,000 kW.
[8]Only single-phase power available.

and after crossing the Idaho-Nevada State line in Elko County, runs directly to the Reno-Sparks area. The line has main laterals serving gas to Winnemucca, Battle Mountain, and Elko; to Fernley, Fallon, and Gabbs; to the Fort Churchill area; to Yerington; and to the Carson City and Minden areas. The second transmission line supplies gas from the southwest States. It enters the southernmost tip of the State and terminates in the Las Vegas area after passing north through Searchlight and Henderson. Short laterals extend to the Davis Dam, Blue Diamond gypsum mine and plant (a short distance west of Las Vegas), and Glendale areas. Figure 4 shows the natural gas transmission network in Nevada.

The Southwest Gas Corp. (Southwest) is the intrastate supplier of gas and owns all main transmission and lateral lines. Southwest furnishes gas to the Sierra Pacific Power (SPP) and C. P. National (CPN) public utility companies for distribution. Sierra Pacific resells the gas in its service territory that essentially consists of the Reno, Sparks, and Verdi municipalities (*106*). C. P. National distributes gas at retail in the city of Henderson, located south of Las Vegas. Southwest's Northern and Southern Divisions distribute gas to all other communities served by natural gas in the State. Cities and towns served by the Northern Division include Elko, Carlin, Battle Mountain, Winnemucca, Lovelock, Fernley, Fallon, Wadsworth, Dayton, Silver Springs, Garnerville, Silver City, Minden, Incline Village, and Stateline. The Southern Division retail sales include customers in the Las Vegas, North Las Vegas, and Boulder City areas.

Southwest's extensive Nevada pipeline network was built as a result of potential revenues to be gained from the use of natural gas for firing steam electric generators and in mining and metal refining operations (*106*). In response to a rapid rise in gas rates, a major defection of large-volume industrial and powerplant customers occurred between 1980 and 1982. Those customers who could, switched from gas to residual oil for their fuel needs. Due primarily to this decline of industrial customers within the Southwest system, natural gas supplies are, and will be, readily available in the foreseeable future for existing and new industrial customers.

Water (*384, 459, 682, 684*)

Nevada is the most arid State in the Union averaging slightly less than 23 cm of precipitation annually. Precipitation will vary from about 7.5 cm in the most arid valley to 100 to 150 cm in certain mountainous areas. About 84% of Nevada's land area lies within the Great Basin section of the Basin and Range province. The Great Basin area is characterized by drainage flows into enclosed basins rather than the sea. Water supplying these intermontane basins is principally from storm runoff and snowmelt occurring mostly during the spring and early summer months. Except for times of high flow when ephemeral lakes or playas may be formed, most mountain streams terminate prior to reaching the basin floors. The annual evaporation rate is high within the State, ranging from about 1 m in the northeastern part of the State to as high as 2 m in the southernmost part. Nevada has few large streams or rivers. Unlike those in other States, these streams decrease in size and increase in dissolved mineral content as they flow. Nevada has several large lakes, but these are generally peripheral to the central portion of the State's land mass.

Nevada mining operations rely heavily on ground water as a source of water. The water supply is usually developed by a well, often several, drilled into deep saturated sediments filling the intermontane basins. Though often containing immense quantities of water built up and stored over centuries, the average annual water recharge is relatively small. If water usage is not kept at or below the rate of recharge, shortages will result. Prolonged ground water consumption greater than annual recharge would result in long-term problems for all users. It has been estimated that, even in the largest of Nevada's basins, the annual recharge does not greatly exceed 61.7 million m^3, and in perhaps half the valleys, recharge is less than 18.5 million. Table 4 presents a summary of Nevada water resources (*682*).

There are other factors besides the limited supply that affect the supply and availability of water in Nevada for development. These include water quality, low yield, temperature, ground water movement, and water rights. In some basins or portions thereof, water may be highly mineralized or contain substantial amounts of undesirable dissolved salts. Generally, water resources for mining are developed on the edges of basins where water is usually of higher quality compared with that contained in the central portions of the basin. Some basins known to have moderate-to-large yields will have areas of low yield, which results in wells with high drawdown rates. Though usually not a great problem for mine and mill consumption, above normal water temperatures occur in many areas of the State.

Problems also arise in developing water resources in basins that are closed topographically but are not closed hydraulically. As a result of water moving from one basin to another beneath topographic divides, water development and consumption in one basin can have broad unexpected effects in adjacent basins. Problems with water availability due to infringement of water rights occur throughout the State. The problems are exacerbated by the largely unknown and little understood hydraulic systems, par-



Figure 4.—Natural gas distribution system in Nevada.

Table 4. — Nevada water summary (*682*)

	10^9 m³	10^6 acre ft
Estimated annual average precipitation	67	54
Surface water:		
Estimated runoff from mountains	3.9	3.2
Estimated inflow crossing State line (excluding Colorado River)	1.6	1.3
Colorado River	12	9.7
Estimated outflow crossing State line (excluding Colorado River)[1]	.9	.7
Colorado River	12	9.4
Surface water storage capacity (excluding State's portion of Mead, Mohave, Tahoe, and Topaz)	31	25
Lake Mead	36.6	29.7
Lake Mohave	2.25	1.82
Lake Tahoe	151	122
Topaz Lake	.0733	.0594
Ground water (budget for valley-fill reservoirs):[2]		
Estimated inflow	2	2
Estimated outflow	2	2
Recharge from precipitation	2.7	2.2
Perennial yield of valley-fill reservoirs	2.1	1.7
Stored in upper 100 ft of saturated valley fill	310	250
Estimated transitional storage reserve	100	84
Estimated outflow crossing State line	.19	.15
Estimated inflow crossing State line	.004	.003

[1]Includes 1970 flow to Lake Mead from Las Vegas Wash.
[2]Water underground in a given valley.

ticularly those outside of the larger municipality and agricultural areas. Difficulties specifically occur as a result of not fully understanding the interaction between surface waters and ground water. The surface waters have long been appropriated, and as ground water is continually developed and utilized, surface water sources, with their attached legal prior use rights, may be adversely impacted.

In an arid State such as Nevada where water supplies are scarce and valuable, it has been necessary for the State government to strictly control and regulate its use. The State office that exercises authority over water use is the Division of Water Resources (DWR) of the State Department of Conservation and Natural Resources. The State Engineer is the executive head of DWR and administers the appropriation of public waters. The Division of Water Resources operates under a complex set of laws that have been developed over the past 100 yr of Nevada water usage.

For water planning and management purposes, the State of Nevada has been divided into 14 major hydrographic regions (fig. 5) of which all but two lie within the Great Basin. In turn, the hydrographic regions are further subdivided into 255 hydrographic areas. Nevada State law authorizes the State Engineer to designate ground water basins, to establish preferred uses of water within the basins, and to limit withdrawal in these areas.

As State policy, withdrawal of ground water is generally limited to that naturally recharged to the ground water basin. Additionally, Nevada Revised Statute (NRS) 533.035 states that "beneficial use shall be the basis, measure, and the limit of the right to the use of water." These guidelines result in the State Engineer assigning "designated" status to hydrographic areas where ground water resources are being depleted. By the end of 1983 there were 86 hydrographic areas throughout the State that have been so designated. In the interest of public welfare, NRS 534.120 authorizes and directs the State Engineer to declare preferred uses within these basins. Preferred uses are limited to domestic, municipal, quasimunicipal, mining, industrial, irrigation, and stock-watering uses. After preferred uses have been established for a designated basin, the State Engineer is required to appropriate the scarce water supplies in the best interest of the public when acting on water permit applications. In 1983, the State Engineer's office stated that domestic and municipal uses had the highest preferred order of use; mining had the next highest priority, above irrigation. The reason given for mining's high priority is its relatively short consumptive lifespan and importance in securing water for mine development in areas where water demand approaches and exceeds the available supply.

To gain water rights for mining and milling use, a company must submit an application for a permit to appropriate to the State Engineer. By State statue, the State Engineer is required to approve an application if there is unappropriated water at the requested source of supply and where the applicant's use does not tend to impair the value of existing rights or otherwise be detrimental to the pubic interest. An approved application—a permit—grants the applicant the right to appropriate a designated amount of water, from a particular source, for a defined purpose, and for use at a defined location.

Major mine development has encountered water availability problems in the past and no doubt will face increasing difficulties in the future as it competes with other users for scarce supplies. To date, mining has been accommodated for its water needs; however, the State is required to protect the existing rights of water users and to promote the general welfare of the State. As a result, some mine developments have been required to obtain water from relatively distant locations.

TRANSPORTATION

The Nevada highway and rail transportation systems were developed under the influences of supply and demand. State highways initially were developed along frontier trails. Once much more extensive, railroads in the State were built to carry Nevada ores from mines to distant smelters. In many cases they were replaced by highways in response to social pressures for road connections between towns. Many rail lines have been abandoned.

Rail (*686, 732*)

Nevada is served by two major railroads with transcontinental connections, the Southern Pacific and the Union Pacific. The Union Pacific more than doubled its rail length within the State after merging with the Western Pacific Railroad Co. in 1983. Nevada is also served by two intrastate railroads: the Nevada Northern and the U.S. Gypsum. The Nevada Northern is a short-line carrier that suspended operations in December 1983. The U.S. Gypsum is a private line with less than 10 km of track.

Nevada's rail system is comprised of 2,421 km of rail lines consisting of 2,002 km of mainline and 419 km of branchline. Figure 6 shows Nevada's rail system. Table 5 summarizes the State rail system by carrier.

Nevada Northern Railway Co.—The Nevada Northern is a wholly owned subsidiary of the Kennecott Copper Corp. The line runs in a general north-south direction and traverses portions of Elko and White Pine Counties. At Cobre (Shafter), the Nevada Northern connects with the



Figure 5.—Hydrographic regions and designated ground water recharge areas of Nevada.



Figure 6.—Rail network of Nevada. (Base map, courtesy Nevada Department of Transportation.)

Table 5. — Rail carriers and railage, kilometers

Carrier	Mainline	Branchline	Total	pct
Nevada Northern Railway Co.	238.2	18.8	257.0	10.6
Southern Pacific Transportation Co.	723.5	234.2	957.7	39.6
Union Pacific Railroad Co.	1,030.5	165.9	1,196.4	49.4
U.S. Gypsum	9.7	0	9.7	.4
Total	2,001.9	418.9	2,420.8	100.0

mainline of the Southern Pacific; further south it connects with the Union Pacific (formerly Western Pacific) track. The mainline extends south to Kennecott Copper Corp. inactive copper mines in the Robinson mining district. Two branchlines of the Nevada Northern connect the mainline to Kennecott's concentrator and smelter at McGill. After cessation of copper mining at the Ruth in 1976, the rail line has experienced limited use. The rail line was not abandoned but has suspended operations. Kennecott filed for abandonment in 1984. Notice of suspensions of operations are filed with the State for 6-month periods at a time.

Southern Pacific Transportation Co.—The Southern Pacific Transportation Co. is the largest of the Southern Pacific Co. subsidiaries. The company has broad financial interests including transportation, communications, and land management and development. Southern Pacific's involvement in transportation includes rail, truck, piggyback, and pipeline systems.

The Southern Pacific rail system links markets in 12 States in the west and southwest, and handles transcontinental shipments through the rail centers of New Orleans, Tucumcari (NM), Ogden, St. Louis, and Memphis. International rail shipments within Southern Pacific's system move through the U.S. Gulf and Pacific coasts and along the Mexican border.

In Nevada, the Southern Pacific offers direct mainline service to major markets in Oregon, California, Utah, Arizona, and New Mexico. Additionally, through-service is offered to points in the Pacific Northwest, Midwest, and Eastern United States. Extending east-west across northern Nevada, the Southern Pacific operates between Ogden, UT, and Roseville, CA. Connections in the Southern Pacific's Nevada rail system are made with the Union Pacific Railroad Co. (former Western Pacific) at Winnemucca and the Nevada Northern Railway Co. at Cobre (*686*).

The Southern Pacific has two branchlines in Nevada, both of which leave the mainline at Hazen, about 70 km east of Reno. One branch, the Mina, runs in a southerly direction from Hazen for about 210 km to Mina. The other branch, the Fallon, runs easterly about 25 km to Fallon.

Union Pacific Railroad Co.—The Union Pacific Railroad Co. transports diverse products and is a part of intermodal traffic in the States of California, Colorado, Idaho, Iowa, Kansas, Missouri, Montana, Nebraska, Nevada, Oregon, Utah, Washington, and Wyoming. After the 1983 merger with the Western Pacific Railroad Co., the Union Pacific added about 723 km of track (688 km of mainline) in northern Nevada to its existing 473 km northeast-southwest track system (including 342 km of mainline) in southern Nevada.

The Union Pacific rail line runs west from Salt Lake City, enters northern Nevada, and parallels the Southern Pacific's track in a cooperative paired track arrangement between a point near Wells to Winnemucca. Connections with the Nevada Northern and the Southern Pacific are at Shafter and Winnemucca, respectively. One branchline operated in the company's northern Nevada system runs 53 km (35 km of Nevada railage) from a connection point with the mainline at Reno Junction in northeastern California to the northern Reno area.

In southern Nevada, the Union Pacific passes through Las Vegas, and has about 343 km of mainline track, and about 130 km of branchline. The mainline connects major cities and towns of southern Nevada with direct lines southwest to Los Angeles and northeast to the Salt Lake City, Provo, and Ogden areas. From this hub area, direct lines exist west to San Francisco; northwest to Portland, Tacoma, and Seattle; and east where many connections exist for rail haulage to Gulf Coast ports.

Union Pacific's four branchlines in southern Nevada are the Pioche, Prince, Mead Lake, and Boulder City. Several major spurs connect the branchlines to industrial areas and military installations. The Pioche Branch, about 52 km in length, connects the Union Pacific mainline at Caliente and terminates to the north near Pioche. The Prince Branch connects with the Pioche Branch and extends 14 km west to the Caselton and Prince Mines in the Pioche mining district. The Mead Lake and Boulder City branches connect the mainline with the Nevada towns of Overton, Henderson, and Boulder City.

U.S. Gypsum.—The U.S. Gypsum Co. operates a 10-km-long private railroad from its Empire plant in Washoe County to a connection point with the Union Pacific Railroad at Gerlach, NV. Company practice in 1982 was to ship outbound finished products using five to eight cars. Two or three cars were used to haul inbound raw materials (*686*).

Road

Nevada's highway and road system is key to the mining industry's successful development of the State's mineral wealth. The system serves the seventh largest State in the Union, containing about 288,200 km² (110,500 mi²) of land. The States stretches about 780 km (485 miles) north-south and about 505 km (315 miles) east-west. Federal and State highways serve interstate and intrastate movements, respectively. The county road system serves intracounty movement not served by the State system.

Nevada is traversed east to west by interstate highways I–80 and I–15. Interstate 80 traverses northern Nevada directly connecting its cities and communities including Elko, Battle Mountain, Winnemucca, and Reno to Sacramento and San Francisco to the west, and Salt Lake City to the east. Interstate 15 passes through Las Vegas providing direct connections to Los Angeles and the Salt Lake City area. Interstate highways comprise about 875 km of the State's approximately 88,100 km (1980) of roads, highways, and streets (*687*). State and county rural highways and roads make up about 77,700 km. Figures 7 and 8 show the State's road and highway system and the approximate haul distances between major points. Figure 9 shows the relative accessibility of intrastate routes when planning for transport of heavy "overweight" mine or mill equipment loads.

Generally, intrastate movement of mine products is by truck. Commonly, movement of ores and concentrates over the State road and highway system is by contract carrier. Long-distance interstate movement of mine or mill products, characterized by large bulk and low general value, is most often by rail after products are trucked to railheads. High unit value products such as mercury and gold may be trucked for long distances. However, gold doré-bullion is



Figure 7.—General highway map of Nevada. (Courtesy Nevada Department of Transportation.)



Figure 8.—Highway distances between principal Nevada communities.



Figure 9.—Highway accessibility for transporting nonreducible loads above legal weight limits.
(Base map, courtesy Nevada Department of Transportation.)

often transported to refineries by air from the State's major gold mines.

Because transportation can be a significant element in overall resource exploitation, mine operators attempt to keep their mine-to-mill or mine-to-market transportation costs as low as possible. Efforts have been made to persuade the State to increase the legal maximum weight limitations on State and county roads, or to grant special permits or waivers for continuous haulage of overweight loads. Because of potentially increased damage to road surfaces, State policy has not yielded in this area. However, the State does grant permits for single or one-way haulage of nonreducible overweight loads, such as might be encountered when delivering heavy mine and mill equipment to a minesite. In Nevada, approval to haul such loads is difficult to get during the spring months when the frost is thawing, and during periods when the subgrade lacks stability because of high moisture content.

REGULATION AND TAXATION

Mining is critically important to Nevada. Mining and mineral exploration are particularly vital to the economies of numerous small towns and cities, some of which are almost completely dependent upon the mining industry. The influence on the economies of the State's large cities is more indirect. The mining industry contributes substantially to the State's economy through jobs, taxes, freight revenues, and the support of satellite industries. Nevada mining regulations and taxation are generally favorable to the mineral industry (*107*) as the State recognizes the importance of a prosperous and stable mineral industry.

Mining Regulations

Most regulation governing development of Nevada mineral resources occurs at the State level: "Air quality control may be regulated at the county or municipal levels; solid waste management may be regulated at the county level; and zoning and special uses are regulated at the municipal level" (*731*).

A major portion of Nevada mining law deals with claim location, millsites, tunnel rights, claim disposition, partnerships, and licensing of equipment operators. The most restrictive State laws relate to mining safety and health, and air and water quality control. The State has adopted all mandatory Federal health and safety standards as published by MSHA, and the Occupational Safety and Health Administration (OSHA) of the U.S. Department of Labor. The State Inspector of Mines, Division of Mine Inspection, State of Nevada Department of Industrial Relations is responsible for insuring industry compliance with mine safety regulations.

By State statute all water supply sources within the State, whether surface or underground, belong to the public, and their usage is regulated by the Division of Water Resources. Federal and State air and water quality laws are administered by the Nevada Division of Environmental Protection. The State air and water quality laws are generally no more stringent than Federal laws.

Nevada has no State clearinghouse or one-stop permit agency that serves to consolidate the permitting process within the State. Table 6 outlines State and Federal permits (and agency contacts) required during planning, development, and construction. The table is based on Nevada Bureau of Mines and Geology Special Publication L–6, *State and Federal Permits Required in Nevada Before Mining or Milling Can Begin* (rev. 1981), available from Nevada Bureau of Mines and Geology, Reno, NV 89557. The publication contains data compiled by the Nevada Department of Minerals (formerly State Division of Mineral Resources) on when permits are required, maximum and minimum times to obtain permits, permit costs, requirements for public notice, and other information required by the granting agency. Communication with the Nevada Department of Minerals (400 West King Street, Suite 106, Carson City, NV 89710, (702) 855–5050), is recommended for information regarding changes or additions to regulations and permitting procedures related to mining.

Similar information is available and explained in greater detail in *Permit Requirements for Development of Energy and Other Selected Natural Resources for the State of Nevada*, 1981, prepared for Four Corners Regional Commission and the U.S. Geological Survey (*731*). This document, available for several western States, is obtainable from U.S. Geological Survey, Environmental Affairs Office, 760 National Center, Reston, VA 22092.

Taxation (*18*)

Principal taxes paid by Nevada mining operations are taxes on net proceeds, property taxes on mine and mill equipment and improvements, and sales tax paid when purchasing equipment and supplies. Other taxes are levied on patented mine claims, and on oil-gas-geothermal leases.

The net-proceeds-of-mines tax is imposed on net earnings resulting from the sale of the product of the mining operation. The Nevada Department of Taxation is directed by State statute to determine the net proceeds of a mining operation from detailed financial data the mining company is required to submit. The net proceeds, which are subject to taxation, are based on gross yield or value of the product less allowable deductions for operating expenses. These deductions include, but are not limited to, actual costs for the following:

1. Extracting ore from the mines.
2. Transporting the mine product to the place of reduction, refining, or sale.
3. Reduction, refining, and sale.
4. Marketing and delivering the product and the conversion of the product into money.
5. Maintenance and repair of equipment and facilities.
6. Fire insurance.
7. Depreciation of the original capitalized cost of machinery, facilities, etc.
8. Mine development work.
9. Royalties.

The tax rate imposed upon the net proceeds earned from mining is equal to the ad valorem (property tax) rate set by the county assessor for other property within the same respective taxing jurisdiction.

Mining companies are also subject to a property tax assessed on mine and mill improvements and equipment. Property appraisal is conducted by the State Department of Taxation and is subject to the local jurisdiction tax rate set by the county assessor. Nevada's statutes limit the rate of the ad valorem property tax to a maximum of $3.64 for each $100 assessed valuation. Assessed value is set at 35% of the statutorily defined taxable value of the property. In turn, taxable value is based on the cost appraisal approach where value is determined by establishing the replacement

Table 6.—Permits required in Nevada before initiation of mining or milling (*200*)

Requirement	Granting agency or agency to contact
State:	
Permit to construct campsite	Nevada Division of Health, Bureau of Consumer Health Protection Services 505 East King St., Carson City, NV 89710 (702) 885–4750
Endangered wildlife	Nevada Department of Wildlife P.O. Box 10678 1100 Valley Road, Reno, NV 89520 (702) 784–6214
Endangered plants	Nevada Division of Forestry, Dept. of Conservation and Natural Resources 201 South Fall St., Carson City, NV 89710 (702) 885–4350
Air quality permit to construct	Nevada Division of Environmental Protection 201 South Fall St., Carson City, NV 89710 (702) 885–4670
Nevada water pollution control permit	Do.
Authorization for disposal of solid wastes	Do.
Air quality permit to operate	Do.
Hazardous waste	Do.
Permit to appropriate the public waters	Nevada Division of Water Resources 201 South Fall St., Carson City, NV 89710 (702) 885–4380
Permit to construct tailings dam	Do.
Opening and closing mines	State Inspector of Mines 1380 S. Curry St., Carson City, NV 89710 (702) 885–5243
Historic preservation	Nevada Division of Historic Preservation and Archaeology 201 South Fall St., Carson City, NV 89710 (702) 885–5138
Federal:	
Use of BLM-administered land	Bureau of Land Management—State Office Division of Mineral Resources 300 Booth St., P.O. Box 1200, Reno, NV 89520 (702) 784–5676
Use of BLM-administered land under wilderness review	Do.
Temporary use of BLM-administered land	Do.
Prevention of significant deterioration	Environmental Protection Agency Division of New Source Section, Air Management 215 Fremont St., San Francisco, CA 94105 (415) 974–8110
Right of way for transmission corridor	Bureau of Land Management Branch of Appraisal 300 Booth St., P.O. Box 1200, Reno, NV 89520 (702) 784–5474
Road access (ROW)	Do.
Purchase, transport, or storage of explosives	Bureau of Alcohol, Tobacco, and Firearms 350 South Center St., Reno, NV 89501 (702) 784–5251
Flora and fauna	U.S. Forest Service 1200 Franklin Way, Sparks, NV 89431 (702) 784–5331
Notification of commencement of operation	Mine Safety and Health Administration 3680 Grant Drive, Reno, NV 89509 (702) 784–5892
Patenting mining claims	Bureau of Land Management 300 Booth St., P.O. Box 1200, Reno, NV 89520 (702) 784–5751
City and County: General plan, building permit, special-use permit, zoning change, business license.	Contact respective city or county government affected by a proposed operation for information on what permits may be required.

costs, minus straight-line depreciation. The average Nevada ad valorem taxation per $100 of assessed value, as of August 1983, was $2.12. Current State statute limits annual growth in ad valorem revenue derived from old property in the aggregate to 4.5% without a vote of the people.

The third principal tax affecting mining companies is the sales and use tax. In 1981, the sales tax was increased statewide from 3.5% to 5.75%. Only Washoe County has a higher rate of 6%, imposed in November 1982.

For a comparative study of mine tax impact in Nevada and six western States, see reference 107.

MINERAL PROCESSING FACILITIES

Milling Facilities

Nevada beneficiation facilities are shown in figure 10 and listed in tables 7 and 8. Although the State has significant processing facilities for such commodities as diatomite, gypsum, limestone, salt, and colemanite, the facilities shown and listed are limited to those that process any of the 17 commodities designated in the introduction of this report. The State hosts primary beneficiation facilities for

the processing of ores of antimony, barium, copper, gold, silver, lead-zinc, magnesium, mercury, molybdenum, tungsten, and lithium brines.

Much of the data given in figure 10 and tables 7 and 8 are from the directories of active Nevada mine operations compiled and published annually by the Division of Mine Inspection, Department of Industrial Relations, State of Nevada (*683, 685, 688*). Mill capacity and type of operation data were derived from journals, newspapers, and personal communication with the owners and operators. The figure and tables are not intended to be comprehensive; rather, the data are intended to show the 1983–84 status of strategic mineral process development within the State.

Over the past several years there has existed an excess of in-state milling capacity for copper, tungsten, and lead-zinc. This continuing trend through 1983 and into 1984 was caused, at least in part, by low commodity prices and related foreign competition. In 1983, the outward signs of a similar demise appeared for barite with many mines and/or mills producing at much reduced levels and some operations closing. Fluctuating market conditions tend to have a major impact on in-state lithium (lithium carbonate as the product), mercury, and molybdenum production because each of these commodities are produced by a single, "large" operation. Mill production from Nevada's lithium and mercury properties has been relatively stable in recent years; however, molybdenum (concentrate) production has fluctuated and at the end of 1983, following an 8-month shutdown, output remained less than capacity.

Activity in the State's precious metal industry has been robust in the past several years. Several milling facilities have operated at rates exceeding design capacity. Mill conversions from other commodity products to gold production have occurred. Expansion of existing gold processing facilities to greater capacities and the use of multiple processes are common. The precious metal industry, gold especially, is by far the largest segment of Nevada's current mining industry. Of the 389 large and small Nevada mining operations active in 1983, gold and silver operations comprised about 57%.

Smelting and Refining

Nevada hosts one smelting and one processing facility that have been available for custom processing of copper and tungsten concentrates. The Kennecott smelter at McGill processed copper concentrates prior to its closure in June 1983. Kennametal, Inc., Nevada Division, is solely dependent on custom tungsten concentrates for its operation located a short distance north of Fallon.

The Kennecott smelter, colocated with the company's 19,500 t/d (21,500 ton/d) flotation concentrator, has the capacity to produce 45,000 t/a (50,000 ton/yr) of blister copper. It has operated on an intermittent basis after the company's nearby Ruth Mine closed in 1978. Since then, the smelter has survived on stockpiled copper concentrates, and on custom concentrates processed for other copper companies or from Kennecott's other operations. The smelter closed because of the inability to obtain adequate concentrates. Kennecott plans to continue maintenance of the facilities in the event domestic copper industry conditions improve.

The Kennametal processing plant buys tungsten concentrates on the world market. As of early 1984, domestic concentrates were not being offered, and the plant's supply sources were from foreign suppliers only. The company purchased concentrates meeting normal tungsten specifications with 60% WO_3. Minimum amount accepted per shipment is 450 t (500 ton). Sulfur content above 1.5% is penalized (*734*).

Smelting facilities are common to Nevada's numerous gold operations. The facilities are captive and seldom consider smelting outside concentrates. Dore product is sent generally to east and west coast companies for refining.

Figure 11 shows and lists principal smelting and refining processing facilities in the immediate area significant to Nevada. The figure does not include the Battle Mountain area barite grinding facilities (fig. 10). Facilities listed in the figure either currently buy, or have in the past, bought custom concentrates. The figure lists a much smaller number of copper, lead, and zinc smelting-refining facilities than would have been included 15 yr ago. The closing of smelting and refinery facilities has added significantly to the distances companies, especially the smaller operations, must ship their concentrates for treatment (*734*). Even Nevada's largest operations, such as Anaconda Company's Nevada Moly Mine,[6] may have to ship concentrates great distances for smelting. As an example, the molybdenum concentrates from the molybdenum-copper mine have been shipped to roasting facilities in Iowa, Pennsylvania, Canada, and Europe.

[6]Nevada Moly Mine indefinitely suspended operations in January 1985 because of poor market conditions.

Table 7.—Numerical index of selected beneficiation facilities in Nevada

(Refer to figure 10)

Map No.	Name	Commodity[1]
1..	McDermitt	Hg
2..	Oxbow Tungsten	W
3..	Dry Creek	$BaSO_4$
4..	Stormy Creek	$BaSO_4$
5..	Wells	W
6..	Enfield Bell (Jerritt Canyon).	Au
7..	Dexter	Au
8..	Esmeralda	Au
9..	Getchell	Au
10.	Pinson	Au
11.	Rossi	$BaSO_4$
12.	Dee	Au
13.	Bootstrap	Au
14.	Goldstrike	Au
15.	Bullion Monarch (Universal Gas of Montana).	Au
16.	Carlin	Au
17.	Eisenmann	$BaSO_4$
18.	Patsy Ann	$BaSO_4$
19.	Gold Quarry	Au
20.	Maggie Creek	Au
21.	Nevada Barth	Fe
22.	Dunphy	$BaSO_4$
23.	Argenta	$BaSO_4$
24.	Dresser	$BaSO_4$
25.	Battle Mountain Grinding (IMCO).	$BaSO_4$
26.	Battle Mountain Copper Basin.	Cu
27.	Battle Mountain Copper Canyon Precipitation plant.	Cu
28.	Battle Mountain Copper Canyon.	Au
29.	Independence	Ag
30.	Bateman Canyon	$BaSO_4$
31.	Fire Creek	Au
32.	Major Barite	Au
33.	Grey Eagle	Au
34.	Buckhorn	Au
35.	Cortez leach	Au
36.	Cortez	Au
37.	Greystone	$BaSO_4$
38.	Mountain Springs (IMCO)	$BaSO_4$
39.	Mountain Springs (FMC)	$BaSO_4$
40.	Jupiter	Au
41.	Fortune Cookie	Au
42.	Springer	W
43.	Lewis	Au
44.	Global	Au
45.	Imlay Canyon	Au
46.	Nevada Packard	Ag
47.	Oreana	Ag
48.	F. M. Wright	Au
49.	Relief Canyon	Au
50.	Gold Hill	Au
51.	Bernice Canyon	Sb
52.	Tungsten Mountain	W
53.	New Pass	Au
54.	Allen	$BaSO_4$
55.	Austin Resources	Ag
56.	Bullion Monarch (Monarch Mining).	Ag
57.	Bauer	Ag
58.	Precious Metals (Brazos, Imperial-Klondike).	Au
59.	Victorine (Sumich)	Au
60.	Silver Center-Wonder	Au
61.	Anchor Cox Canyon	Au
62.	Kennametal	W
63.	Fallon	$BaSO_4$
64.	John Young (Wheeler)	W
65.	Fisk	W
66.	Nevada Pacific	Au
67.	Gooseberry	Ag
68.	American Flat	Au
69.	Haywood-Santiago	Au
70.	Bennetts	Au
71.	Donovan	Au
72.	DeLaMare	Au
73.	Buckskin	Au
74.	Veta Grande	Au
75.	Bell Mountain	Au
76.	Nevada Scheelite	W
77.	Paymaster	Au
78.	Ione Placer	Au
79.	Luning	MgO
80.	Nevada Works	MgO
81.	Paradise Peak	Au
82.	Santa Fe	Au
83.	Kinkead	$BaSO_4$
84.	Borealis	Au
85.	Aurora	Au
86.	Ashby	Au
87.	New Boston	Au
88.	Red Rock	Au
89.	Aden	Au
90.	Potosi	Au
91.	Candelaria	Ag
92.	Argentum	Au
93.	G & S	Au
94.	Northumberland	Au
95.	East Northumberland	$BaSO_4$
96.	Round Mountain	Au
97.	Manhattan (Arizona Hillside Mining Co).	Au
98.	Manhattan (Tenneco)	Au
99.	Nevada Moly	Mo
100	Tonopah West (Miller's)	Au
101	Boss	Au
102	Jumbo	$BaSO_4$
103	Tonopah Divide	Au
104	Silver Peak	Li
105	Sixteen-to-One	Ag
106	Goldfield Tailings (Blackhawk).	Au
107	Goldfield (Trafalgar)	Au
108	Goldfield (Southern Pacific, Noranda, P.G. & U).	Au
109	Spicer Mining Co., Inc.	Au
110	Montgomery Shoshone	Au
111	Sterling	Au
112	Victoria	Cu
113	Bald Mountain	Au
114	Alligator Ridge	Au
115	Windfall	Au
116	McGill Smelter	Cu
117	McGill Concentrator	Cu
118	Sunshine Puritan	Cu
119	Ward	Pb-Zn
120	Taylor	Ag
121	Atlanta	Au
122	Research Silver (Silver Horn).	Au
123	Pioche	Au
124	Caselton	Pb-Zn
125	Emerson	W
126	Mockingbird	Au
127	Continental	Au
128	Oro De Mojave	Cu
129	Jetco	Au

[1]Principal commodity.



Figure 10.—Selected beneficiation facilities in Nevada.

	NAME	COMPANY	TYPE	STATUS
1	Trail plant, B.C.	COMINCO, Ltd.	A	a
2	Tacoma plant	ASARCO, Inc.	A	a
3	Bunker Hill	Bunker Ltd. Part.	AB	b
4	Kellogg plant	Sunshine Mining Co.	B	c
5	East Helena plant	ASARCO, Inc.	A	a[1]
6	Salt Lake City plant	Johnson-Matthey	B	c
7	Geneva plant, Provo	U.S. Steel Corp.	A	a
8	Mc Gill	Kennecott	A	b
9	Fallon plant	Kennametal	C	a
10	Pine Creek plant	Union Carbide	C	b
11	Los Angeles plant	Engelhard	B	a
12	Miami plant	Inspiration Consolidation	A B	a
13	Hayden plant	ASARCO, Inc.	A	a
14	Douglas plant	Phelps Dodge	A	a
15	El Paso plant	ASARCO, Inc.	A	a
16	Amarillo plant	ASARCO, Inc.	B	a
17	Corpus Christi plant	ASARCO, Inc.	B	b,a

Type: A, smelter; B, refinery; C, chemical
Status: a, active; b, idle; c, under construction or expansion

[1]Closure planned in spring 1985

Figure 11.—Regional secondary processing facilities significant to Nevada.

Table 8.—Selected beneficiation facilities in Nevada

Name and operator	County	Status	Map No.[1]	Method	Capacity[2]	Type	Comments
				ANTIMONY			
Bernice Canyon; Howard Turley.	Churchill . . .	Idle	51	Mill, screen . . .	1.8 t/h	A	Capacity is ball mill capacity. Owner hopes to operate the mill in 1985 with possible addition of flotation circuit. The mine was operational in 1984. Ore contains Au, Ag.
				BARITE			
Allen; Tom Norris Mining Co.	Lander	Active . . .	54	Mill, gravity (jig).	36 t/h	A	Produces about 18 t/h product. Equipment comprised of 1 roll crusher and 1 jig.
Argenta; Milchem, Inc.	. . . . do	. . . do . . .	23	Mill, gravity, grind.	136 t/h crush, 16.4 t/h grind.	A, B	Reportedly operating at 55% to 60% of capacity; has accepted custom in the past.
Bateman Canyon; Milchem, Inc.	. . . . do	Idle	30	Mill, gravity (jig).	54 t/h	A, B	Custom work accepted in past and will consider custom in future.
Battle Mountain Grinding; Imco Services, Inc.	. . . . do	Active . . .	25	Mill, grind, classification.	360 t/d, 27 t/h . . .	A, B	127,000-t/a capacity. 3 grinding mills, 9-t/h capacity each.
Dresser (Battle Mountain); Dresser Minerals.	. . . . do	. . . do . . .	24	Mill, crush, grind.	32 t/h, total grind.	A, B	Grinding plant; 3 roller mills. Reported operating at about 60% capacity in early 1983. Would consider taking custom ore if spare capacity exists.
Dry Creek; Chromalloy Mining and Minerals (owner), leased by Circle A Construction.	Elko	. . . do . . .	3	Mill, gravity (jig).	180 to 230 t/h . . .	A	Capacity is jaw crusher.
Dunphy; N. L. Industries, Baroid Division.	Eureka	. . . do . . .	22	Mill, gravity, flotation, grind.	110 t/h	A, B	Have done and would consider custom grinding, not flotation; 73-t/h railcar loading capacity.
East Northumberland; All Minerals, Inc.	Nye	. . . do . . .	95	Mill, gravity . . .	1,365 t/d, 90 t/h	A, B	Portable crusher; peak load for crushing circuit is 136 t/h.
Eisenmann; Eisenmann Chemical Co.	Eureka	. . . do . . .	17	Mill, crush, jig.	272,000 t/a	A, B	Possesses 2 jigs; has done custom crushing and would consider custom jigging. In 1984, mill feed was stockpiled ore from its Lakes Mine.
Fallon; Standard Slag Co.	Churchill . . .	. . . do . . .	63	Mill, flotation . .	7.3 t/h product . . .	A, B	Formerly a fluorspar mill, bought to feed P & S barite mine ore.
Greystone; Dresser Minerals.	Lander	. . . do . . .	37	Mill, gravity (jig).	110 t/h estimated product.	A	Mill is portable; capable of producing 907,000-t/a product.
Jumbo; GEO Drilling Fluids, Inc.	Nye	. . . do . . .	102	Mill, crush, screen.	272 t/h	A	Active in 1983; status unknown in 1984.
Kinkead; Kinkead Mining and Construction.	Mineral	. . . do . . .	83	. . . . . do	23 t/h	A	Mill has flotation capability; intermittent operation. Jig capacity—14 t/h. Normally operates at 90 t/d.
Mountain Springs (FMC); FMC Corp.	Lander	. . . do . . .	39	Mill, crush, screen.	63,000 t/a	A	Primary crusher design capacity is about 181 t/h.
Mountain Springs (IMCO); Imco Services, Inc.	. . . . do	. . . do . . .	38	Mill, jig, table, flotation.	400,000 t/a. 127,000 t/a ground product.	A	
Patsy Ann; Unichem Minerals, Inc.	Eureka	Idle	18	Gravity (jig) . . .	30 to 34 t/h	A	2 jigs. New equipment operated about 2 months in 1983; no crusher. Product capacity is 10.9 t/jig; jigs processed Coyote Mine ore.
Rossi; Tom Norris, Inc. (contractor).	Elko	Active . . .	11	Mill, gravity . . .	108 t/h	A	Minesite portable 2-stage crushing with 2 jigs; produces about 907 t product over 14 h/d. Product goes to Dunphy plant.
Stormy Creek; Old Soldier Minerals.	. . . . do	. . . do . . .	4	Mill, screen, gravity (jig).	272 t/h crush, 109 t/h jig.	A, B	Operated partial year of 1983; idle in 1984. Will consider custom milling.

See explanatory notes at end of table.

Table 8.—Selected beneficiation facilities in Nevada—Continued

Name and operator	County	Status	Map No.[1]	Method	Capacity[2]	Type	Comments
				COPPER			
Battle Mountain Copper Basin (Electrolytic Plant); Duval Corp.	Lander	Active	26	Solvent extraction, electrowinning.	5,170 t/a	A	Capacity is annual cathode capacity. Closed indefinitely in December 1984.
Battle Mountain Copper Canyon Precipitation Plant; Duval Corp.	do	do	27	Leach-precipitation.	1,562-t/a product (at peak).	A	Capacity in terms of year's output. Plant treats leach solutions from Copper Canyon Mine dumps. 1984 estimated production is at levels of 50% to 70% of peak production capacity.
McGill Concentrator; Kennecott Minerals Co.	White Pine	Idle	117	Mill, flotation	19,500 t/d	A, B	Located adjacent to McGill smelter.
McGill Smelter; Kennecott Minerals Co.	do	Idle, standby.	116	Smelter	45,000-t/a product.	B	Product is blister Cu. Processed Kennecott's Robinson district concentrate through 1978.
Oro De Mojave; Quadra Mining & Development.	Clark	Active	128	Mill, flotation, jigging, CCD-Merrill-Crowe precipitation.	73 t/h	A	Production began in 1984. Also recovers Pb, Ag, and Au.
Sunshine Puritan; Kennecott Minerals Co.	White Pine	Idle	118	Leach-precipitation.	<200-t/month product.	A	Production from unit greatly reduced when mining at the Ruth open pit copper mine ceased in 1978. Very small amount of production to February 1983.
Victoria; Hecla Mining Co.	Elko	do	112	Mill, flotation	907 t/d	A	Intermittent operation.
				GOLD AND/OR SILVER			
Aden; Hugh C. Ingle	Mineral	Idle	89	Mill, gravity, flotation.	<15 t/d	A, B	Has done custom in the past.
Alligator Ridge; Amselco Minerals, Inc.	White Pine	Active	114	Mill, heap leach,cyanidation.	2, 700 t/d	A	Recovers Au with byproduct Ag and Hg.
American Flat; United Mining Co. of Nevada, Inc.	Storey	do	68	Mill, cyanidation.	907 t/d	A, B	Operating at capacity in 1984.
Anchor Cox Canyon; Anchor Mine, Inc.	Churchill	do	61	Vat leach, cyanidation.	72 t over 3- to 4-d period.	A	No crushing facilities by December 1984, though operators reportedly are in search of a crusher.
Argentum: Combined Metals & Recovery Systems.	Esmeralda	do	92	Mill, cyanidation (flotation).	360 t/d	A, B	Capacity is crushing ability for flotation circuit. On standby in 1984. Will buy ore.
Ashby; Hugh C. Ingle, Jr.	Mineral	do	86	Mill, heap leach, cyanidation.	<10 t/d	A	Capacity is estimated.
Atlanta; Standard Slag Co.	Lincoln	do	121	Mill, cyanidation.	520 t/d	A, B	Has taken custom in past.
Aurora; Centennial Exploration Corp.	Mineral	do	85	Mill, heap leach, cyanidation.	900 t/d	A	Cone crusher capacity 91 t/h; jaw crusher capacity 136 t/h.
Austin Resources; Austin Resources Corp.	Lander	Idle	55	Mill, flotation	68 t/d	A	Mill is intact and has processed Ag ore only.
Bald Mountain; Placer U.S.	White Pine	Active	113	Mill, heap leach, cyanidation.	57 L/s (900 gal/min).	A	Recovers primarily Au. Full production will be reached about January 1985. Capacity is for carbon reccovery plant.
Battle Mountain Copper Canyon; Duval Corp.	Lander	Active, development.	28	Mill, cyanidation, gravity.	3,200 to 3,600 t/d.	A	Expansion to unknown capacity planned for 1983 completion. Crusher rated capacity 726 t/h.
Bauer; Bauer Metals, Inc.	do	Active	57	Mill, agglomeration, heap leach, cyanidation.	907 t/d	A	Operation leaches tailings. Primarily extracts Ag, byproduct Au. Commenced production in 1983; full production in 1984.
Bell Mountain; Bell Mountain Mining Co.	Churchill	Development.	75	Mill, cyanidation (tank).	650 t/d	A	Capacity is 1982 preliminary.

See explanatory notes at end of table.

Table 8.—Selected beneficiation facilities in Nevada—Continued

Name and operator	County	Status	Map No.[1]	Method	Capacity[2]	Type	Comments
GOLD AND/OR SILVER—Continued							
Bennetts; John Bennett (owner).	Lyon	Idle	70	Mill, cyanidation.	32 t/d	B	Type questionable. Reportedly inactive since about 1942. Major components still present.
Bootstrap; Carlin Gold Mining Co.	Elko	Active	13	Heap leach, cyanidation.	200,000 t/a	A	Recovers Au only. Dump leach. On-site plant consists of a 4-stage carbon column circuit. The gold-loaded carbon is stripped, acid washed, and regenerated at the Carlin mill.
Borealis; Tenneco Minerals Co.	Mineral	do	84	Mill, heap leach, crush, screen.	2,270 t/d	A	Recovers Hg also. Crushing circuit capacity 272 t/h; Hg retort feed 0.9 t/8-h d; smelting furnace feed 0.9 t/8-h d.
Boss; Falcon Mining and Exploration Co.	Esmeralda	Active, development.	101	Mill, heap leach, cyanidation.	180 t/h	A, B	Production anticipated to commence fall 1984. Crusher moved from Tonopah Divide Mine. Will consider buying compatible ore.
Buckhorn; Cominco American, Inc.	Eureka	Active	34	Mill, heap leach, cyanidation.	260 t/h crush	A	Heaps to be built at 2,270 t/d ore, or 680,000 t/a.
Buckskin; Pacific Silver Corp.	Douglas	Development.	73	Mill	270 t/d	A	
Bullion Monarch; Monarch Mining.	Lander	Active	56	Mill, flotation	450 to 540 t/d	A, B	Recovers Ag. Will buy high-grade compatible to circuit; minimum lot 450 t. 1-t/h (24-h/d) smelter near completion.
Bullion Monarch; Universal Gas of Montana.	Eureka	do	15	Mill, cyanidation.	360 t/d	A	Normal feed rate about 180 t/d.
Candelaria; NERCO Metals.	Mineral	do	91	Crush, screen, heap leach, cyanidation.	7,300 t/d	A	Primarily produces Ag.
Carlin; Carlin Gold Mining Co.	Eureka	do	16	Mill, cyanidation.	2,450 t/d	A	Recovers Hg also. Capacity is combined 2,000 t/d oxide and 450 t/d carbonaceous ore capacities.
Continental; Continental Co.	Clark	Inactive	127	Heap leach, cyanidation.	See comments	A	Became inactive in 1984. Has two 4,500-t leach ponds. Zn precipitation.
Cortez Leach; Cortez Gold Mines.	Lander	Active	35	Heap leach, cyanidation.	57 L/s (900 gal/min).	A	Capacity is carbon-in-pulp plant.
Cortez; Cortez Gold Mines.	do	do	36	Mill, carbon-in-leach tanks and carbon columns, cyanidation.	1,800 t/d, >180 t/h.	A	Processes ore from Horse Canyon Mine. Capacity is planned feed rate (660,000 t/a).
Dee; Dee Gold Mining Co.	Elko	do	12	Mill, cyanidation.	820 t/d, 286 t/h.	A	Operation began in fall 1984.
DeLaMare; R. W. DeLaMare (owner).	Lyon	Idle	72	do	45 t/d	B	Type questionable. Reportedly inactive since about 1942. Major components still present.
Dexter; Pecos Resources.	Elko	Active, development.	7	Heap leach, cyanidation, Merrill-Crowe precious metal plant recovery.	16 L/s (250 gal/min).	A	Test heap leaching began in 1984. Capacity is Merrill-Crowe plant purchased from Tuscaroa Associates.
Donovan; Mike Donovan (owner).	Lyon	Idle	71	Mill, cyanidation.	45 t/d	B	Type questionable. Reportedly inactive since 1879. Major components still present.
Enfield Bell (Jerritt Canyon); Freeport Gold Co.	Elko	Active	6	do	3,040 t/d	A	Original capacity was 2,750 t/d in 1981.
Esmeralda; Merrill A. Nelson (owner).	do	Idle	8	Mill, crush, grind, gravity (table).	23 t/d	A	Last period of mill operation was for a short period in 1981.

See explanatory notes at end of table.

Table 8.—Selected beneficiation facilities in Nevada—Continued

Name and operator	County	Status	Map No.[1]	Method	Capacity[2]	Type	Comments
GOLD AND/OR SILVER—Continued							
F. M. Wright; F. M. Wright Mining Co.	Pershing...	Active ...	48	Mill, flotation, gravity.	45 t/d	B	Has run as captive mill. Presently processes precious metals. Has processed base metal sulfides and tungsten.
Fire Creek; Mines Resources, Inc.	Lander	...do...	31	Heap leach, cyanidation, carbon column recovery.	30,400 t per 60-d period batch process.	A	
Fortune Cookie; Proquip, Inc.	Pershing...	Active, production, development.	41	Placer, gravity.	1,500 to 2,300 m³/shift (2,000 to 3,000 yd³/shift). See comments.	A	Feasibility and expansion to 4,600 to 7,600 m³ (6,000 to 10,000 yd³) on a 1-shift basis planned for 1985.
G & S; Robert E. Wilson.	Nye.....	Active ...	93	Mill, gravity ...	18 t/d	A, B	Capacity estimated. Past product was tungsten.
Getchell; Watterson Mining, Contractor.	Humboldt ..	Development, feasibility.	9	Mill, cyanidation.	91 t/d	A	1983 activity was test leaching.
Global; Global Natural Resources, Inc.	Pershing...	Active ...	44	Placer washing plant, trommel screen and sluice boxes.	60 m³/h (80 yd³/h)	A	
Gold Hill; Fisk and Robertson Mining.	Churchill...	...do...	50	Mill, vat leach, cyanidation, activated carbon.	1,360 t/month....	A	
Gold Quarry; Carlin Gold Mining Co.	Eureka	Development.	19	Heap leach; mill agitated leach, carbon-in-pulp.	6,120 t/d.....	A	Will recover byproduct Hg. Mill to come on-stream in late 1985, processing about 2.3 million t/a ore.
Goldfield; Trafalgar Mines partnership.	Esmeralda .	Active ...	107	Agglomeration, heap leach, cyanidation.	See comments...	A	Operation reportedly shut down in 1984 with equipment still on-site. Plan was to reprocess 91 million t mill tailings. Reportedly, only 27,000 to 36,000 t material placed on heap.
Goldfield (Southern Pacific, Noranda, P.G. & U. joint venture); Blackhawk Mines Corp. (operator).	....do....	Development.	108	..... do	1,090 t/d.....	A	Information in December 1984 indicated the development plan may have been abandoned.
Goldfield Tailings; Blackhawk Mines Corp.	....do....	Active ...	106	..... do	23,000 t/a.....	A	
Goldstrike; Western States Minerals Corp.	Eureka	...do...	14	Cyanide heap leach of mine-run ore.	1,500,000 m³ (2,000,000 yd³/a) material handled.	A, B	Does no custom but may consider it if ore is compatible. Annual tonnage ore and waste estimated 3.6 million t.
Gooseberry; Asamera Minerals (U.S.), Inc.	Storey.....	...do...	67	Mill, cyanidation.	320 t/d	A	Principal commodity is Ag. Full production reached in fall 1984.
Grey Eagle; Grey Eagle Mining Co.	Lander	...do...	33	Mill, crush, gravity.	45 t/d	A	
Haywood-Santiago; NEVEX Gold Co., Inc.	Lyon	Development.	69	Mill, heap leach, cyanidation.	15.8 L/s pregnant solution.	A, B	Will consider buying ore after 1 yr of production. Production anticipated to commence in November 1984. Full production anticipated to commence in first quarter 1985.
Imlay Canyon; Bill Dale.	Pershing...	Active ...	45	Placer washing plant; trommel screen and sluice boxes.	15- to 19-m³/h (20- to 25-yd³/h) test capacity.	A	Recovers Au, W, and Hg. Placer operation. Capacity will be increased in 1985 from stated test capacity.

See explanatory notes at end of table.

Table 8.—Selected beneficiation facilities in Nevada—Continued

Name and operator	County	Status	Map No.[1]	Method	Capacity[2]	Type	Comments
GOLD AND/OR SILVER—Continued							
Independence; United Mining and Milling.	Lander	Active ...	29	Mill, cyanide vat leach.	45 t/d	A, B	Principal commodity is Ag, by-product Au. Will consider custom. Mill burned and rebuilt in 1983. Operating less than capacity in 1984.
Ione Placer; Marshall Earth Resources, Inc.	Nye.....	...do...	78	Mill, screen, gravity.	270 t/h	A	Ore comes from their Ione Placer and Sky Claims.
Jetco; Jetco Enterprises, Inc.	Clark.....	...do...	129	Mill, tank leach	NA	A, B	May take custom. Has 25- by 91-cm (10- by 36-in) jaw crusher and 1.2- by 1.5-m (4- by 5-ft) ball mill.
Jupiter; Circle A Construction.	Pershing...	...do...	40	Mill, char-in-pulp, cyanidation.	1.4 t/h.....	A	
Lewis; Standard Slag Co.	Humboldt ..	...do...	43	Mill, heap leach	3,200 t/d.....	A	Production began in August 1984.
Maggie Creek; Carlin Gold Mining Co.	Eureka	...do...	20	Heap leach, cyanidation.	2,300 t/d.....	A	Milling grade is trucked and processed at Carlin mill.
Major Barite; Major Barite Co.	Lander	...do...	32	Mill, gravity ...	90 t/h	A, B	Formerly called the Bradshaw (processed barite).
Manhattan; Arizona Hillside Mining Co.	Nye.....	Active, standby.	97	Heap leach, cyanidation.	NA	A	Mine capacity is about 2,720 t/d. No crushing facilities.
Manhattan; Tenneco Minerals Co.	....do....	...do...	98	Mill, gravity, flotation, cyanidation.	2,700 t/d crush, 1,360 t/d flotation.	A	Plant startup in January 1984.
Mockingbird; P.G. Harrison and James Harris.	Clark.....	...do...	126	Mill, gravity ...	2 t/d	A	Has accepted custom but does not at present; intermittently active.
Montgomery Shoshone; Bullfrog Mining Enterprises.	Nye.....	...do...	110	Mill, screen, crush, vat leach.	450 t/d crush	A, B	Possesses two 680-t vats; intermittently active.
Nevada Pacific; Nevada Pacific Mining Co.	Washoe ...	Development.	66	Gravity, jigs, tables.	1,500 m^3/d (2,000 yd^3/d).	A	Construction in progress in December 1984 on mine and mill to process a 1.5 million m^3 (6 million yd^3) eluvial gold deposit.
Nevada Packard; Nevada Packard (joint venture).	Pershing...	Active ...	46	Heap leach, cyanidation, Zn dust precipitation.	200 gal/min	A	Recovers primarily Ag. 140-t/h capacity crusher. Sold in 1984. Production ceased in July 1984. Possesses 3 Shriver clarifier presses and 2 precipitation presses.
New Boston; New Boston Mining Co.	Mineral	...do...	87	Mill, screen, heap leach.	150 t/h	A, B	Cyanidation.
New Pass; Donald Jung.	Lander	Idle	53	Mill, heap leach, cyanidation.	36 t/d	A	Capacity is approximate.
Northumberland; Cyprus Mines Corp.	Nye.....	Active ...	94	..... do	4,500 t/d.....	A	
Oreana; Coronado Oil & Minerals Co.	Pershing...	...do...	47	Mill, flotation, gravity.	90 t/d (has never operated over 45 t/d).	A, B	Has processed Au, Sb, W. Minor production early 1983; none in 1984. Production anticipated commencing again in first quarter 1985.
Paradise Peak; FMC Corp.	Nye.....	Active, development.	81	Mill, cyanidation, agitation, leaching.	907,000 t/a.....	A	Proposed capacity is estimated. Hg will be produced as by-product. Production planned to commence in 1986.
Paymaster; Jesse R. Wilson.	....do....	Active ...	77	Mill, tank cyanide leach, carbon recovery.	90 t/d	A	Capacity is tank capacity. Ag recovery very minor.
Pinson; Pinson Mining Co.	Humboldt ..	...do...	10	Mill, carbon-in-pulp, cyanidation.	1,360 t/d.....	A	Recovers byproduct Hg. In 1984, about 25% of ore mined was heap leached.

See explanatory notes at end of table.

Table 8.—Selected beneficiation facilities in Nevada—Continued

Name and operator	County	Status	Map No.[1]	Method	Capacity[2]	Type	Comments
GOLD AND/OR SILVER—Continued							
Pioche; Hollingshead Mining Contracting.	Lincoln	Active ...	123	Mill, flotation, gravity.	23 t/d	A, B	Some custom work has been done.
Potosi; S & R Mining & Milling.	Mineral	...do...	90	Crush, screen, heap leach, cyanidation.	230 t/d	A	Portable crusher.
Precious Metals (Brazos, Imperial-Klondike); Precious Metals, Inc. of Texas.	Lander	Inactive..	58	Mill, flotation ..	180 t/d	A	Anticipated restart of production in early 1984. Reportedly bought in late 1984 by Spirit Oil Co., Billings, MT.
Red Rock; Tseng Mining Co.	Mineral	Active ...	88	Mill, pond leach, screen.	90 t/hr	B	Leases Ladd Enterprise mill. Has unused flotation capability. Ladd has about 180-t/h crushing capacity.
Relief Canyon; Lacana Mining, Inc.	Pershing...	...do...	49	Mill, heap leach, cyanidation.	4,500 t/d, 907,000 t/a.	A	300-t/h design crushing capacity. Average annual product to be 680 kg (22,000 tr oz) Au.
Research Silver (Silver Horn); Silver Horn Research Mill Corp.	Lincoln	...do...	122	Mill, flotation, cyanidation.	320 t/d	A, B	
Round Mountain; Smoky Valley Mining Co.	Nye.....	...do...	96	Mill, heap leach, cyanidation.	9,000 t/d.....	A	Construction of a 36,000-t/d-capacity mill is being considered in 1984 for possible operation in 1987.
Santa Fe; Lacana Mining Corp.	Mineral	Development.	82	..... do	See comments...	A	Production planned by December 1985 at minimum ore throughput of 590,000 t/a.
Silver Center-Wonder; Belmont Resources.	Churchill...	Active ...	60	..... do	5,400 t/wk, 136 t/h.	A	Processes Wonder Mine tailings and Silver Center Mine new ore. Capacity is March 1984 process rate.
Sixteen-to-One; Sunshine Mining Co.	Esmeralda .	...do...	105	Mill, tank leach	635 t/d	A, B	Has bought compatible ore. Crushing capacity about 130 t/h. Principal commodity is Ag.
Spicer Mining Co., Inc.; Nevada Mines & Minerals, Spicer Mining Co., Inc.	Nye.....	...do...	109	Mill, agglomeration, heap leach.	70- to 90-t/d pilot crushing.	A, B	Active in 1984. Also performs custom assay. Processes captive ore from Mayflower Mine. Agglomeration capacity 230 t/d; test mill 23 t/d; carbon stripping 340 kg/batch.
Sterling; Saga Exploration Co.	....do....	...do...	111	Mill, heap leach, cyanidation.	82 t/h	A	Projected daily crushing rate is 270 t.
Taylor; Silver King Mines, Inc.	White Pine .	...do...	120	Mill, cyanidation.	1,800 t/d, 91 t/h..	A, B	Recovers primarily Ag. Has accepted custom. Normal operating rate is 1,090 t/d.
Tonopah Divide; Ebco Enterprises.	Esmeralda .	...do...	103	Mill, crush, screen, heap.	910 t/d, 180 t/h ..	A	Production expected to cease fall 1984. Crusher will be moved to company's Boss Mine.
Tonopah West (Miller's); TW-MNR Assoc.	....do....	...do...	100	Mill, tank leach	1,090 t/d.....	A	Recovers principally Ag with minor Au. Reprocesses old tailings in Tonopah district. Operations were suspended in July 1984 for an indefinite period.
Veta Grande; 20th Century Energy Corp.	Douglas ...	...do...	74	Mill, gravity, flotation.	180 t/d, 36 t/h ...	A, B	Intermittent operation.
Victorine (Sumich); New Beginnings Resources.	Lander	Active, development.	59	Mill, jig, flotation, cyanide regrind, electrowinning (Ag), smelting.	320 t/d	A, B	Capacity is current crusher capacity; design capacity is 450 t/d. Production to begin in mid-December 1984. Company will consider custom.
Windfall; Windfall Venture.	Eureka	Active ...	115	Cyanidation, heap leach.	1,100 t/d.....	A	Inactive most of 1983.

See explanatory notes at end of table.

Table 8.—Selected beneficiation facilities in Nevada—Continued

Name and operator	County	Status	Map No.[1]	Method	Capacity[2]	Type	Comments
				IRON			
Nevada Barth; Nevada Barth Corp.	Eureka	Active ...	21	Mill, crush, screen.	200 to 300 t/h ...	A	Feed is from stockpiles. Normal operating rate is 455 t/d.
				LEAD—ZINC			
Caselton; Combined Metals Reduction Co.	Lincoln	Idle	124	Flotation	1,270 t/d	A, B	Idle since about 1978. Plans in 1984 are to reopen by 1986. Will be looking for ore to purchase.
Ward; Silver Kings Mines, Inc.	....do....	Development, design.	119	Mill, flotation ..	1,100 t/d		Construction planned to begin in 1985 with completion in late 1986. Will recover Ag and Cu also. Design will allow for increase in capacity to 1,800 to 2,700 t/d.
				LITHIUM			
Silver Peak; Foote Mineral.	Esmeralda .	Active ...	104	Solar evaporation, chemical, refinery.	7,260 t/a	A	Capacity in terms of production. Product is lithium carbonate (Li_2CO_3).
				MAGNESIUM (MAGNESITE—MgO)			
Luning; C-E Basic	Nye	Active ...	79	Mill, screen ...	NA		
Nevada Works; C-E Basic.	....do....	...do...	80	Mill, calcine, flotation.	2,000 t/d	A	Capacity is estimated.
				MERCURY			
McDermitt; McDermitt Mine Joint Venture.	Humboldt ..	Active ...	1	Mill, flotation, distillation.	2,200 t/d flotation; 0.45-t/h furnace.	A	Product is elemental Hg.
				MOLYBDENUM			
Nevada Moly; Anaconda Minerals Co.	Nye	Active ...	99	Mill, flotation, tank leach.	20,000 t/d	A	Also recovers Cu. Product is MoS_2.
				TUNGSTEN			
Emerson; Union Carbide Corp.	Lincoln	Idle	125	Mill, flotation ..	907 t/d	A	Mill intact and on standby.
Fisk; Gee Mines	Churchill...	Active ...	65	Mill, gravity ...	0.9 t/h	A	Mill leased to Gee Mines, which ran Ag ore through it in 1984. Originally built to process tungsten ore.
John Young (Wheeler); John Young (owner).	....do....	...do...	64	Mill, gravity, amalgamation.	0.45 t/h	A, B	Also recovers Au. Idle in 1984. Has accepted custom and will consider custom in the future.
Kennametal; Kennametal, Inc.	....do....	...do...	62	Chemical	Proprietary data ..	B	A secondary processing plant, refinery.
Nevada Scheelite; Natural Resources Development, Inc.	Mineral	Idle	76	Gravity	113 t/d, 36 t/h ...	A	36-t/h jaw crusher capacity. In 1984, mill being dismantled and equipment sold.
Oxbow Tungsten; P.A.B. Oil Mining Co.	Elko	...do...	2	Mill, gravity, flotation.	181 t/d	A	Last known operating year was 1978. Mill reportedly not intact. Possesses flotation cells and tables. Crushing equipment removed.
Springer; Utah International, Inc.	Pershing...	...do...	42	Flotation	1,800 t/d	A	Normal crushing rate is about 900 t/d. Final product is ammonium paratungstate.
Tungsten Mountain; Opportunity Village (owner).	Churchill...	Active ...	52	Mill, table, flotation.	1.8 t/h	A	Mill originally set up for tungsten recovery. Contains 5 tables and 2 flotation cells. In 1984, Pt, with minor Au and Ag, recovery was attempted.
Wells; Nevada Milling Inc.	Elko	Idle	5	Gravity, flotation.	91 t/h	A	Rehabilitated in December 1983; operating in 1984.

A Captive.
B Custom or accepts custom.
NA Not available.

[1]Refer to figure 10.
[2]Approximate feed unless otherwise noted in comments.

NOTE.—An entry of "mill" in method indicates crushing ability.

REVIEW OF SELECTED MINERAL COMMODITIES IN NEVADA

ALUMINUM

Aluminum, the third most abundant element in the Earth's crust, is second only to iron in terms of value of nonfuel mineral products in world commerce. The United States, the world's largest producer of aluminum metal, has accounted for about 30% of the world smelter output over the past 5 yr. At the present time, the only commercially viable smelter feed for the production of aluminum metal is alumina (Al_2O_3) obained from bauxite ores. The United States imports over 90% of the aluminum raw material (both bauxite and alumina) it uses; however, it is technically feasible to produce aluminum from domestic nonbauxite materials such as high-alumina clays, alunite, anorthosite, dawsonite in spent oil shale, and coal waste. Several deposits of nonbauxitic aluminous materials occur in Nevada—several hundred million metric tons of alunitized rock (<30% alunite) has been identified in the southern part of the State and significant deposits of kyanite-related minerals occur in Douglas, Mineral, and Pershing Counties (*239*). Future development of these resources depends on their ability to economically compete with foreign bauxite deposits and other domestic nonbauxitic sources of supply.

Bureau of Mines Mineral Industry Location System (MILS) Data—Aluminum in Nevada

Total properties	68
Producers[1]	0
Known principal deposits	4
Deposit abstracts in directory	1

[1]Producers of materials for aluminum only.

Reported Bauxite Production—United States and Nevada, 1978–83 (*728–729*)

Year	United States[1]		Nevada	
	10^3 t	Value, 10^3	10^3 t	Value, 10^3
1978	1,669	$23,185	NRP	NRP
1979	1,821	24,875	NRP	NRP
1980	1,559	22,353	NRP	NRP
1981	1,510	26,489	NRP	NRP
1982	732	12,334	NRP	NRP
1983	679	11,309	NRP	NRP

NRP No reported production.

[1]From 1978 to 1982, between 74% and 82% of domestically mined bauxite was used in the production of alumina. In 1983, no domestically mined bauxite was used in the production of aluminum metal.

Principal Known Aluminum Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10^3 t	wt %	Year	Reference
Boyd	Lincoln	Past producer[3]	Alunite	Small	43	[4]29.3	1978	239
					289	[4]21.5		
C-M Alunite[5]	do	Prospect	do	Medium	([6])	([6])	NAp	NAp
Goldfield district:								
CTR leases	Esmeralda	Explored	do	do	100	[4]22	1978	239
MTZ lease	do	do	do	do	60,000	[4]20	1978	239
Hawthorne	Mineral	Past producer	Andalusite, corundum	do	13,608-27,216	[7]27	1967	277

NAp not applicable.

[1]Based on estimate of metric tons of contained Al_2O_3: Large, >100 million; medium, 1 million to 100 million; small, <1 million.

[2]Rounded.

[3]Lens of alunite mined for fertilizer.

[4]Wt % alunite.

[5]Deposit abstract in directory.

[6]No published data have been located.

[7]Wt % Al_2O_3.



Figure 12.—Aluminum in Nevada.

ANTIMONY

Antimony, a brittle, silver-white metal, is consumed in minor amounts when compared with other base metals. Apparent U.S. annual antimony consumption averaged slightly more than 32,000 t from 1978 through 1983. In 1983, about 50% of consumption need was satisfied by recycling of old scrap, principally plates from lead-acid batteries. The remainder was supplied by domestic mines and imports of antimony metal, compounds, and ores. From 1978 to 1982 reported U.S. mine production averaged about 580 t, or less than 2% of domestic consumption.

Bureau of Mines Mineral Industry Location System (MILS) Data—Antimony in Nevada

Total properties	239
Producers[1]	44
Known principal deposits	13
Deposit abstracts in directory	9

[1]Includes past producers.

Antimony has been sporadically recovered from Nevada mines since the 1860's. The principal periods of production were during World War I and World War II, when increased demand and reduced imports caused antimony prices to increase. The last recorded production of antimony in Nevada was in 1974.

Reported Antimony Production[1]—United States and Nevada, 1978–83 (*728–729*)

Year	United States		Nevada	
	10^3 t	Value, 10^3	10^3 t	Value, 10^3
1978	724	W	NRP	NRP
1979	655	W	NRP	NRP
1980	311	W	NRP	NRP
1981	586	W	NRP	NRP
1982	456	W	NRP	NRP
1983	760	W	NRP	NRP

NRP No reported production.
W Withheld to avoid disclosing company proprietary data.
[1]Antimony content of domestic ores and concentrates.

Principal Known Antimony Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					10^3 t	wt %	Year	Reference
Antimony King[2]	Lander	Past producer	Sb	Small	[3]	[3]	NAp	NAp
Bloody Canyon[2]	Pershing	do	Sb, Ag	do	[3]	[3]	NAp	NAp
Bray-Beulah[2]	Lander	do	Sb, Ag	do	[3]	[3]	NAp	NAp
Drumm	Churchill	do	Sb	Unknown	[3]	[3]	NAp	NAp
Dry Canyon[2]	Lander	do	Sb, Ag	Small	[3]	[3]	NAp	NAp
Fencemaker[2]	Pershing	do	Sb	Medium	[3]	[3]	NAp	NAp
Hard Luck-Pradier[2]	Lander	do	Sb, Ag	Small	[3]	[3]	NAp	NAp
Hollywood[2]	Pershing	do	Sb, Ag	do	[3]	[3]	NAp	NAp
Hoyt	Churchill	do	Sb, Ag	Unknown	[3]	[3]	NAp	NAp
IHX	do	do	Sb	do	[3]	[3]	NAp	NAp
New Potosi	Mineral	do	Au, Ag, Pb, Sb	do	[3]	[3]	NAp	NAp
Sutherland[2]	Pershing	do	Sb	Small	[3]	[3]	NAp	NAp
White Caps[2]	Nye	do	Au, Sb, As, Hg	do	[3]	[3]	NAp	NAp

NAp Not applicable.
[1]Based on estimate of metric tons of contained Sb: Large, >50,000; medium, 5,000 to 50,000; small, <5,000.
[2]Deposit abstract in directory.
[3]No published data have been located.



Figure 13.—Antimony in Nevada.

BARITE

Barite (barium sulfate) is primarily used as a weighting agent in oil well drilling (over 90% of 1982 production), paint manufacturing, glassmaking, rubber, and as a source of barium chemicals. In 1981, domestic production of barite reached record levels of 2.5 million t; in 1982, production decreased to 1.67 million t; and by 1983, domestic output declined to only 26% of the 1981 level. Of the seven States reporting production in 1982, Nevada accounted for 85% of the total.

Bureau of Mines Mineral Industry Location System (MILS) Data—Barite in Nevada

Total properties	235
Producers[1]	125
Known principal deposits	23
Deposit abstracts in directory	17

[1]Includes past producers.

Reported Barite Production—United States and Nevada, 1978–83 (*728–729*)

Year	United States		Nevada	
	10^3 t	Value, 10^3	10^3 t	Value, 10^3
1978	1,969	$45,130	1,622	$30,034
1979	1,916	53,581	1,637	35,707
1980	2,037	65,957	1,740	47,800
1981	2,585	102,439	2,252	79,716
1982	1,674	69,522	1,429	52,727
1983	684	29,203	601	21,736

Principal Known Barite Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10^3 t	sp gr	Year	Reference
Ann[3]	Nye	Explored	$BaSO_4$	Medium	(4)	(4)	NAp	NAp
Argenta[3]	Lander	Producer	$BaSO_4$	...do...	(4)	(4)	NAp	NAp
Bald Mountain	.....do.....	Past producer	$BaSO_4$	Unknown	(4)	(4)	NAp	NAp
Big Ledge[3]	Elko	Explored	$BaSO_4$	Medium	(4)	(4)	NAp	NAp
East Northumberland[3]	Nye	Producer	$BaSO_4$	...do...	(4)	(4)	NAp	NAp
Easy Miner[3]	Elko	Past producer	$BaSO_4$	...do...	(4)	(4)	NAp	NAp
Fish Creek[3]	.....do.....	Explored	$BaSO_4$	Large	(4)	(4)	NAp	NAp
Greystone[3]	Lander	Producer	$BaSO_4$	Medium	(4)	(4)	NAp	NAp
Heavy Spar[3]	Elko	Past producer	$BaSO_4$	...do...	(4)	(4)	NAp	NAp
Jungle[3]	.....do.....	..... do	$BaSO_4$	...do...	(4)	(4)	NAp	NAp
Kay[3]	Nye	Explored	$BaSO_4$	...do...	(4)	(4)	NAp	NAp
Lakes[3]	Elko	Past producer	$BaSO_4$	Large	7,300	(4)	1982	304
Miller	Lander	..... do	$BaSO_4$	Unknown	(4)	(4)	NAp	NAp
Mountain Springs[3]	.....do.....	Producer	$BaSO_4$	Large	(4)	(4)	NAp	NAp
P & S[3]	Nye	..... do	$BaSO_4$	Medium	(4)	(4)	NAp	NAp
Pleasant View	Lander	Past producer	$BaSO_4$	Unknown	(4)	(4)	NAp	NAp
Q-Bar	Elko	Explored	$BaSO_4$	...do...	(4)	(4)	NAp	NAp
Queen Lode[3]	.....do.....	Past producer	$BaSO_4$	Medium	(4)	(4)	NAp	NAp
Reeds Canyon	Lander	Explored	$BaSO_4$	Unknown	(4)	(4)	NAp	NAp
Rossi[3]	Elko	Past producer	$BaSO_4$	Large	(4)	(4)	NAp	NAp
Slaven Canyon	Lander	Producer	$BaSO_4$	Unknown	(4)	(4)	NAp	NAp
Snoose[3]	Elko	Past producer	$BaSO_4$	Medium	(4)	(4)	NAp	NAp
Stormy Creek[3]	.....do.....	..... do	$BaSO_4$	...do...	(4)	(4)	NAp	NAp

NAp Not applicable.
[1]Based on estimate of metric tons of contained barite: Large, >5 million; medium 50,000 to 5 million; small, <50,000.
[2]Rounded.
[3]Deposit abstract in directory.
[4]No published data have been located.



Figure 14.—Barite in Nevada.

BERYLLIUM

Beryllium, a lightweight, hard metal with a high strength-to-weight ratio, has high electrical, thermal shock, and corrosion resistance as well as high thermal conductivity. Although high costs have limited the amount of beryllium consumed (annual domestic consumption from 1978 through 1982 averaged 234 t), it is used where its unique combination of physical characteristics are required. Its uses are varied and range from components in electronic switchgear, to brake shoes, to heat shields in aerospace equipment, to neutron moderators or reflectors in nuclear reactors. About 80% of the U.S. consumption of beryllium is in the form of copper alloys; the remainder is evenly divided between beryllium oxide and beryllium metal. Prior to the development of the Spor Mountain bertrandite deposits in Utah in the late 1960's, the United States was almost wholly dependent on imported beryl to meet domestic demand. Since that time the United States has become a major producer capable of supplying much of its beryllium requirements. Nevada has several beryllium occurrences; however, only small amounts have been mined in the past.

Bureau of Mines Mineral Industry Location System (MILS) Data—Beryllium in Nevada

Total properties	22
Producers[1]	5
Known principal deposits	1
Deposit abstracts in directory	1

[1]Includes past producers.

Reported Beryllium Production—United States and Nevada, 1978–83 (*728–729*)

Domestic production of beryllium is withheld from publication to avoid disclosing company proprietary data. No beryllium production was reported in Nevada from 1978 through 1983.

Principal Known Beryllium Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					10^3 t	wt %	Year	Reference
Mount Wheeler[2]	White Pine	Developed	Be, CaF_2, W	Large	([3])	([3])	NAp	NAp

NAp Not applicable.
[1]Based on estimate of metric tons of contained BeO: Large, >1,000; medium, 10 to 1,000; small, <10.
[2]Deposit abstract in directory.
[3]No published data have been located.



Figure 15.—Beryllium in Nevada.

COPPER

Copper, primarily used by ancient civilizations for jewelry, coinage, and weaponry, is used by modern society in thousands of applications because it possesses a versatility surpassed by few metals. More than 50% of the copper produced domestically is used in the electrical and communications industries, while another 40% is used in brass mills.

A lengthy labor strike in 1980 effectively immobilized 10 major domestic producers, which resulted in a substantial production decrease when compared with 1979 levels. In 1981, 15 mines in Nevada were producing copper ore, the bulk of which was from Duval's Copper Basin Mine; only 3 mines reported copper production in 1982. Although the United States continues to be a major copper producing nation, in 1982, for the first year since 1934 and for only the second year since 1883, the United States did not lead the world in newly mined copper. In 1982, the United States ranked second behind Chile and ahead of the U.S.S.R., Canada, Zambia, and 58 other countries.

A copper deposit was announced by Plexus Resources Corp., Salt Lake City, UT, in its 1984 annual report. The deposit, called the Lyon, is part of the Pumpkin Hollow iron-copper skarn complex in east-central Lyon County. The deep-seated Lyon deposit is reported to contain high-grade geologic reserves of 7.5 million tons of 3.1% Cu, 8.6 g/t Ag, and 0.51 g/t Au. Additionally, there is 26 million tons of 1.1% Cu peripheral to the high-grade zone. Unfortunately, the announcement of this significant copper deposit came too late for inclusion in this section's copper table and location map (fig. 16).

Bureau of Mines Mineral Industry Location System (MILS) Data—Copper in Nevada

Total properties	1,116
Producers[1]	637
Known principal deposits	8
Deposit abstracts in directory	8

[1]Includes past producers.

Reported Copper Production[1]—United States and Nevada, 1978–83 (*728–729*)

Year	United States[1]		Nevada	
	[2]10^3 t	Value, 10^3	[2]10^3 t	Value, 10^3
1978	1,358	$1,990	20	$30
1979	1,444	2,961	W	W
1980	1,181	2,667	W	W
1981	1,538	2,886	W	W
1982	1,140	1,840	W	W
1983	1,038	1,750	W	W

W Withheld to avoid disclosing company proprietary data.
[1]Contained copper.
[2]Rounded.

Principal Known Copper Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10^3 t	wt %	Year	Reference
Ann Mason[3]	Lyon	Explored	Cu, Mo	Large	449,056	0.4	1976	829
Battle Mountain Copper Basin.[3]	Lander	Standby	Cu, Ag, Au	Medium	860	1.49	1978	707
						[4].925	1978	707
						[5]13.32	1978	707
Bear[3]	Lyon	Explored	Cu, Mo, Au, Ag	Large	453,592	.4	1979	829
McArthur[3]	do	do	Cu	do	11,793	.43	1976	822
McGill Tailings[3]	White Pine	Explored	Cu, Ag, Au	Medium	36,287-	.3-	1979	413
					72,575	.4		
Robinson district[3]	do	Past producer	Cu, Mo, Au, Ag	Large	82,554	.67	1976	792
Victoria[3]	Elko	Standby	Cu, Ag, Bi	Medium	1,353	[6]2.34	1977	337
					135	[7]2.51	1977	337
Yerington[3]	Lyon	Past producer	Cu, Mo, Ag, Au	Large	115,122	.34	1982	49

[1]Based on estimate of metric tons of contained Cu: Large, >1 million; medium, 50,000 to 1 million; small, <50,000.
[2]Rounded.
[3]Deposit abstract in directory.
[4]g/t Ag.
[5]g/t Au.
[6]Proven.
[7]Probable.



Figure 16.—Copper in Nevada.

FLUORSPAR

Fluorspar is a nonmetallic aggregate containing a sufficient quantity of fluorite (CaF_2) to be of commercial value. Two producers in southern Illinois accounted for over 90% of the domestic fluorspar production in 1983; the remainder was from Nevada and Texas. The manufacture of hydrofluoric acid, used in the aluminum, fluorchemical, and uranium industries, accounted for approximately 64% of the fluorspar consumed domestically in 1983. Another 34% was used as a flux in steelmaking. Enamels, glass manufacture, coatings for welding rods, and other end uses accounted for the remainder of 1983 consumption. In 1981, 1982, and 1983, the Crowell Mine (Daisy) in Nye County was the sole producer of fluorspar in Nevada. The metallurgical grade fluorspar produced at the Crowell Mine was shipped to steel plants in California.

Bureau of Mines Mineral Industry Location System (MILS) Data—Fluorspar in Nevada

Total properties	152
Producers[1]	47
Known principal deposits	9
Deposit abstracts in directory	6

[1]Includes past producers.

Reported Fluorspar Production[1]—United States and Nevada, 1978–83 (*728–729*)

Year	United States[1]		Nevada	
	[2]10^3 t	Value, 10^3	[2]10^3 t	Value, 10^3
1978	117,415	$13,261	W	W
1979	99,154	12,162	W	W
1980	84,037	12,611	W	W
1981	104,693	18,412	W	W
1982	69,869	13,293	W	W
1983	55,000	10,000	W	W

W Withheld to avoid disclosing company proprietary data.
[1]As measured by finished shipments.
[2]Rounded.

Principal Known Fluorspar Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					10^3 t	wt %	Year	Reference
Bisoni[2]	Eureka	Explored prospect	CaF_2, Zn, Be	Large	(3)	(3)	NAp	NAp
Chicago Lode	Nye	Past producer	CaF_2	Unknown	(3)	(3)	NAp	NAp
Crowell[2]	do	Producer	CaF_2	Medium	(3)	(3)	NAp	NAp
Horseshoe	do	Past producer	CaF_2	Unknown	(3)	(3)	NAp	NAp
Mammoth[2]	do	Explored	CaF_2	Medium	(3)	(3)	NAp	NAp
Nyco[2]	do	Past producer	CaF_2	do	(3)	(3)	NAp	NAp
Rainbow[2]	do	do	CaF_2	Small	(3)	(3)	NAp	NAp
Union Canyon	do	do	CaF_2	Unknown	(3)	(3)	NAp	NAp
White Pine[2]	do	Explored prospect	CaF_2	Large	(3)	(3)	NAp	NAp

NAp Not applicable.
[1]Based on estimate of metric tons of contained CaF_2: Large, >5 million; medium, 50,000 to 5 million; small, <50,000.
[2]Deposit abstract in directory.
[3]No published data have been located.

GOLD

Gold production in Nevada increased from 26% of total U.S. production in 1978 to 47% of U.S. total in 1983. Since 1980, Nevada has been the largest gold producing State. Nevada gold production more than tripled between 1978 and 1983. Nevada 1982 gold production was 28,626 kg. Production by the end of 1984 could easily be at the annual rate of 29,000 kg. After mid-decade, Nevada could be annually producing 31,000 kg (1 million oz) gold as new properties come on stream and several existing producers complete expansion. As a comparison, total 1983 U.S. gold production was 60,900 kg.

Most Nevada gold discoveries are very recent. Announcement of new Nevada discoveries and plans for mine-mill development have been commonplace up to the present time.

One of the most recent discoveries was announced by AMAX Inc. in February 1985. Named the Sleeper, this gold and silver ore body is located about 50 km northwest of Winnemucca in Humboldt County. AMAX intends to develop and produce initially from a high-grade portion of the 3.8 million t ore body that, on the whole, averages 4.5 g/t Au and 25 g/t Ag. Production is scheduled to commence by mid-1986 at the mine rate of 450 t/d, producing about 1,700 kg Au and 1,900 kg Ag annually. Unfortunately, the announcement of this significant Nevada discovery came too late to include in the tabulation of principal known gold deposits below and on figure 18.

Bureau of Mines Mineral Industry Location System (MILS) Data—Gold in Nevada

Total properties	2,476
Producers[1]	1,726
Known principal deposits	52
Deposit abstracts in directory	33

[1]Includes past producers.

Reported Gold Production[1]—United States and Nevada, 1978–83 (*728–729*)

Year	United States		Nevada	
	10^6 kg	Value, 10^3	kg	Value, 10^3
1978	31.1	$193,324	8,125	$50,496
1979	30.0	296,550	7,779	76,905
1980	30.2	594,050	8,662	170,595
1981	42.9	633,918	16,323	241,220
1982	45.6	550,966	23,548	284,601
1983	60.9	829,929	28,626	390,226

[1]Data are rounded.



Figure 17.—Fluorspar in Nevada.

Principal Known Gold Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10^6 t	g/t Au	Year	Reference
Alligator Ridge[3]	White Pine	Active-producer	Au, Ag, Hg	Medium	3.5	3.1	1983	15
Atlanta[3]	Lincoln	do	Au, Ag	Small	.9	3.0	1980	61
						[4]55.0		
Aurora[3]	Mineral	Active-producer, testing and developing.	Au, Ag	do	1.4	4.42	1982	309, 444
						[4]10.0		
Bald Mountain[3]	White Pine	Active-testing and developing.	Au	do	2.5	3.1	1984	499
Battle Mountain Copper Canyon:[3] Fortitude.	Lander	Active-producer	Au, Ag	Medium	14.5	4.8	1983	435
						[4]18.0		
Bell Mountain[3]	Churchill	Active-developing, exploration.	Au, Ag	Small	2.5	2.02	1984	208
						[4]56		
Blue Star[3]	Eureka	Active-intermittent producer.	Au	do	1.6	4.1	1974	517
						[4]100		
Bootstrap[3]	Elko	Active-producer[5]	Au, Ag	do	<.9	1.5	1979	378
Borealis[3]	Mineral	do	Au, Ag, Hg	do	2.3-2.7	2.7 [4]2.1	1981	383
Buckhorn[3]	Eureka	do	Au, Ag	do	4.5	1.5	1983	769
						[4]20		
Buckskin	Douglas	Active-developing	Au, Cu, Ag	do	.36	([6])	1983	394
Bullion Monarch[3]	Eureka	Active-producer	Au, Ag	Small	([7])	([7])	NAp	NAp
Carlin[3]	do	do	Au, Ag, Hg	Medium	[6]4.08	[9]5.5	1983	511
Cortez	do	Active-past producer[9]	Au	Small	([7])	([7])	NAp	NAp
Dee[3]	Elko	Active-producer	Au	do	[10]2.420 [11]1.010	[10]3.94 [11].96	1983	493
Dexter:								
High-grade zone	do	Active-exploration	Au, Ag	do	1.8	1.37	1984	524, 534
						[4]65.1		
Low-grade zone	do	do	Au, Ag	do	1.7	34	1984	524, 534
						[4]2.4		
Dry Canyon (Quito)	Lander	Active-exploration	Au, Sb	Small	1.36	6.9	1984	799
Eldorado Canyon	Clark	do	Au	Unknown	([7])	([7])	NAp	NAp
Enfield Bell (Jerritt Canyon).[3]	Elko	Active-producer	Au	Medium	12.4	7.03	1984	313
Fire Creek	Lander	Active-producer	Au	Small	.32	2	1982	611
Florida Canyon	Pershing	Inactive-explored	Au	do	18	.7	1984	662
Gance Creek	Elko	Active-exploration	Au	Unknown	([7])	([7])	NAp	NAp
Getchell[3]	Humboldt	Active-past producer, exploration.	Au, Ag, W	Small	2.950	6.2	1982	61
					9	5.5		
Gold Bar	Eureka	Active-exploration	Au	do	2.5	3	1984	660
Gold Hill	Storey	Inactive	Au, Ag	do	([7])	([7])	NAp	NAp
Gold Quarry[3]	Eureka	Active-developing	Au, Hg	Large	[12]166 [13]122	[12]1.47 [13]1.65	1983	511
Goldfield[3]	Esmeralda	do	Au, Ag	Small	1.919	2.4	1984	502
Goldstrike[3]	Eureka	Active-producer	Au, Ag	do	([7])	([7])	NAp	NAp
Hilltop	Lander	Active-feasibility	Au	do	[14]9.34	[14]2.5	1984	532
Hog Ranch	Washoe	Active-exploration	Au	do	([15])	([15])	1984	611
Horse Canyon[3]	Eureka	Active-producer	Au	do	3.121	1.89	1982	564
Ivanhoe	Elko	Inactive-explored	Au	do	([16])	([16])	1984	611
Lewis	Humboldt	Active-developing	Au, Ag	do	>9.1	NA	1984	501
Lucerne	Lyon	Inactive-explored	Au	do	([7])	([7])	NAp	NAp
Maggie Creek[3]	Eureka	Active-producer	Au	do	3.3	2.7	1984	511
Manhattan[3]	Nye	do	Au, Ag	do	4.5	1.2	1983	311
Mesona	Elko	Active-exploration	Au	do	([7])	([7])	NAp	NAp
Northumberland[3]	Nye	Active-producer	Au, Ag	do	15.4	1.5	1981	61
Paradise Peak	do	Active-developing	Au, Ag	Medium	9.1	3.4	1984	611, 772
						[4]103		
Pinson[3]	Humboldt	Active-producer	Au, Ag, Hg	Small	[10]2.7 [11]2.2	[10]3.19 [11].89	1983	667
Preble[3]	do	do	Au	do	1.6	2.13	1984	770
Rain[3]	Elko	Active-exploration	Au, Ag	do	[17]7.5	2.85	1983	511
Rawhide	Mineral	do	Au, Ag	do	([18])	([18])	1984	611
Relief Canyon[3]	Pershing	Active-producer	Au, Ag	do	8	1.1	1984	658
Round Mountain[3]	Nye	do	Au, Ag	Large	177.3	1.5	1981	388
						[4].79		
Santa Fe[3]	Mineral	Active-feasibility	Au, Ag	Small	[19]10.4	1.88	1983	531, 657
						[4]20.9		
Sterling[3]	Nye	Active-producer	Au, Ag, Hg	do	.18	6.9	1983	533
Tonkin Springs:[3]								
Upper zone	Eureka	Active-exploration	Au	do	2.3	3	1983	241
Lower zone	do	do	Au	do	.45	3	1983	241
Tonopah Divide[3]	Esmeralda	Active-producer	Au, Ag	do	([7])	([7])	NAp	NAp
Tonopah Hasbrouck[3]	do	Active-exploration	Au, Ag	do	4.5	2	1982	611
						[4]51		
Victorine-Kingston	Lander	Active-producer, exploration.	Au, Ag	do	([7])	([7])	NAp	NAp
Windfall[3]	Eureka	Active-producer	Au, Ag	do	2.7	1	1975	805

NAp Not applicable. NA Not available.

[1]Based on estimate of metric tons of contained Au: Large, >90; medium, 90 to 30; small <30.

[2]Rounded.

[3]Deposit abstract in directory.

[4]Silver.

[5]Pit inactive, reserves depleted. Low-grade dump is being leached.
[6]Development ore assayed 6.9 g/t Au, 0.9% Cu, and 14 g/t Ag.
[7]No published data have been located.
[8]Quantity and grade include Carlin and Blue Star reserves.
[9]Low-grade and high-stripping-ratio resource believed remaining; dump material currently being mined.
[10]Mill grade.
[11]Leach grade.
[12]Total resource.
[13]Recoverable reserve.
[14]Contains 5.2 million t averaging 2.7 g/t amenable to open-pit mining.
[15]Contains >3,000 kg Au.
[16]Contains >15,000 kg Au.
[17]Contains 3.1 million t averaging 5.04 g/t Au.
[18]Contains >18,000 kg Au.
[19]Contains 6.3 million t oxide ore averaging 1.6 g/t Au and 15 g/t Ag, and 4.1 million t sulfide ore averaging 2.26 g/t Au and 30.9 g/t Ag.



Figure 18.—Gold in Nevada.

IRON ORE

U.S. iron ore production, down about 50% in 1982 when compared with 1981 levels, was at the lowest since 1938. The reduction was largely due to the decline in iron and steel production. In California, a major mine was permanently closed and 9 of 13 taconite operations in the Lake Superior District were closed 7 to 12 months. In Nevada, the Nevada-Barth Corp. continued to ship ore to the Geneva, UT, facility from its mine stockpile near Carlin; production reportedly ended in 1980 because of exhaustion of ore reserves. Two other mines, the Iron Mine in Churchill County and the Cooney Brothers, Pershing County, also reported shipments in 1982.

Bureau of Mines Mineral Industry Location System (MILS) Data—Iron Ore in Nevada

Total properties	216
Producers[1]	77
Known principal deposits	9
Deposit abstracts in directory	9

[1]Includes past producers.

Reported Iron Ore Production[1]—United States and Nevada, 1978–83 (*728–729*)

Year	United States		Nevada	
	$^{2}10^{3}$ t	Value, 10^{3}	$^{2}10^{3}$ t	Value, 10^{3}
1978	84,542	$2,401,387	W	W
1979	87,602	2,814,440	W	W
1980	70,711	2,544,121	W	W
1981	73,340	2,915,239	100.6	$1,490
1982	36,330	1,491,809	78.9	1,119
1983	45,006	1,944,988	W	W

W Withheld to avoid disclosing company proprietary data.
[1]As measured by shipments; includes byproduct ore.
[2]Rounded.

Principal Known Iron Ore Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					$^{2}10^{3}$ t	wt %	Year	Reference
Buena Vista[3]	Churchill	Past producer	Fe	Medium	46,000	28.5	1971	[4]454
Calico Hills[3]	Mineral	Unknown	Fe, Cu	Small	([5])	([5])	NAp	NAp
Dayton[3]	Lyon	Explored prospect.	Fe	Medium	46,000	42	1971	454
Dodge-Ford[3]	Pershing	Past producer	Fe	...do...	([5])	([5])	NAp	NAp
Minnesota[3]	Douglas	.....do.....	Fe	Small	([5])	([5])	NAp	NAp
Modarelli[3]	Eureka	.....do.....	Fe	Medium	45,000	42.7	1971	454
Phelps-Stokes[3]	Nye	.....do.....	Fe	Small	([5])	([5])	NAp	NAp
Piute[3]	Pershing	Explored prospect	Fe	Large	([5])	([5])	NAp	NAp
Pumpkin Hollow[3]	Lyon	.....do.....	Fe, Cu, Au, Ag	...do...	250,000	40 [6].3	1969	771

NAp Not applicable.
[1]Based on estimate of metric tons of contained Fe: Large, >100 million; medium, 5 million to 100 million; small, <5 million.
[2]Rounded.
[3]Deposit abstract in directory.
[4]Buena Vista published reserves-resources are for 3 separate ore bodies and include measured, indicated, and inferred estimates.
[5]No published data have been located.
[6]Wt % Cu.



Figure 19.—Iron in Nevada.

LEAD AND ZINC

Lead and zinc are two of the most widely used metals in world industry. In terms of tonnage used, lead and zinc rank fifth and fourth, respectively, after iron, aluminum, and copper. In 1982, world mine production of lead and zinc was estimated at 3.5 million and 6.2 million t, respectively, while output from U.S. mines was estimated at 513,000 t lead and 303,000 t zinc.

Although Nevada is not a major producer of either lead or zinc, both metals have been periodically recovered from Nevada mines. The last significant period of production was during the mid-1970's when the Pan American Mine in Lincoln County was operated by the Bunker Hill Co. Since 1979, however, output of lead and zinc has been small.

Bureau of Mines Mineral Industry Location System (MILS) Data—Lead and Zinc in Nevada

Total properties	1,506
Producers[1]	1,051
Known principal deposits	10
Deposit abstracts in directory	6

[1]Includes past producers.

Reported Lead and Zinc Production—United States and Nevada, 1978–83 (*722–723*)

Year	Lead		Zinc	
	10^3 t	Value, 10^3	10^3 t	Value, 10^3
UNITED STATES				
1978	[1]530	$393,516	[1]303	$206,854
1979	[1]526	609,929	[1]267	219,841
1980	[1]550	515,189	[1]317	261,671
1981	[1]446	358,821	[1]312	306,879
1982	[1]513	288,579	[1]303	257,116
1983	[1]449	214,623	[1]275	251,204
NEVADA				
1978	0.653	$485	1.371	$937
1979	.024	28	W	W
1980	.026	24	.002	2
1981	W	W	W	W
1982	W	W	0	0
1983	.014	7	0	0

W Withheld to avoid disclosing company proprietary data.
[1]Rounded.

Principal Known Lead and/or Zinc Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10^3 t	wt %	Year	Reference
Argentena	Clark	Past producer	Zn, Pb, Ag, Au, Cu, V	Small	([4])	([4])	NAp	NAp
Caselton[3]	Lincoln	do	Zn, Pb, Ag, Mn	Medium	([4])	([4])	NAp	NAp
Mountain View	Eureka	do	Zn, Pb, Ag, Cu, Au	Small	([4])	([4])	NAp	NAp
Pan American[3]	Lincoln	do	Zn, Pb, Ag, Mn	Medium	1,992	[5]1.17 [6]2.45 [7]2.07 (sic)	1982	168
Potosi	Clark	do	Zn, Ag, Pb	Small	([4])	([4])	NAp	NAp
Prince[3]	Lincoln	do	Zn, Pb, Ag, Mn	Medium	([4])	([4])	NAp	NAp
Ridge 7129[3]	Eureka	Explored	Zn, V, Mo, Se, oil shale	do	([4])	([4])	NAp	NAp
Ruby Hill[3]	do	Developed	Zn, Au, Ag, Pb	do	2,841	[5]3.7 [6]8.3 [8]5.48 [7]194	1982	168
Ward[3]	White Pine	Active-developing	Zn, Pb, Ag, Cu	do	4,500	[9]5.5 [7]103 [10]1.4	1983	637
Yellow Pine	Clark	Past producer	Zn, Pb, Ag, Cu, Au	do	([4])	([4])	NAp	NAp

NAp Not applicable.
[1]Based on estimate of metric tons of contained Pb and Zn: Large, >1 million; medium, 50,000 to 1 million; small, <50,000.
[2]Rounded.
[3]Deposit abstract in directory.
[4]No published data have been located.
[5]Wt % Pb.
[6]Wt % Zn.
[7]g/t Ag.
[8]g/t Au.
[9]Combined wt % Zn-Pb.
[10]Wt % Cu.



Figure 20.—Lead-zinc in Nevada.

LITHIUM

Lithium is the lightest weight, lowest density, and most electrochemically reactive metal known. It finds use in a variety of commercial or industrial applications. The United States is the world's largest consumer of lithium and from 1978 through 1983, apparent domestic consumption averaged 2,833 t. In 1983, the aluminum industry, the largest lithium user, accounted for about one-third of domestic consumption. Other consuming industries include ceramic and specialty glass, lubricant, air conditioning, synthetic rubber, and primary batteries.

The United States is also the world's largest producer of lithium. In addition to supplying domestic needs, U.S. producers provide about 70% of market-economy countries supply of lithium. Approximately three-fourths of U.S. output is obtained from pegmatite deposits in North Carolina. The remainder is from lithium-bearing brines in Clayton Valley, NV. Currently, there is significant exploration activity in the McDermitt Caldera area near the Nevada-Oregon border where an extensive deposit of hectorite, a lithium-bearing clay, occurs.

Bureau of Mines Mineral Industry Location System (MILS) Data—Lithium in Nevada

Total properties	2
Producers[1]	1
Known principal deposits	2
Deposit abstracts in directory	2

[1]Includes past producers.

Reported Lithium Production—United States and Nevada, 1978–83 (*722–723*)

Lithium production data for both the United States and Nevada are withheld to avoid disclosing company proprietary data.

Principal Known Lithium Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					$2 10^3$ t	wt %	Year	Reference
Montana Mountains[3]	Humboldt	Explored	Li, U	Large	(4)	(4)	NAp	NAp
Silver Peak[3]	Esmeralda	Producer	Li	...do	41	(5)	1979	638

NAp Not applicable.
[1]Based on estimate of metric tons of contained LiO_2: Large, >100,000; medium, 10,000 to 100,000; small, <10,000.
[2]Rounded.
[3]Deposit abstract in directory.
[4]No published data have been located.
[5]Li as Li_2CO_3.



Figure 21.—Lithium in Nevada.

MAGNESIUM

Magnesium, the eighth most abundant element in the Earth's crust, has two basic commercial forms: magnesium metal and magnesium compounds. Apparent U.S. annual consumption of magnesium metal averaged 111,000 t from 1978 through 1983, and for the same period, apparent annual domestic consumption of magnesium compounds averaged nearly 705,000 t (magnesium content). In 1983, about 53% of consumption of metallic magnesium was in the production of aluminum-based alloys. Other uses of the metal included magnesium castings and wrought products; reducing agents for titanium, zirconium, uranium, and beryllium metal; cathodic protection; and production of nodular cast iron. About 80% of the magnesium compounds used in the United States is in the form of magnesia (MgO) for high-temperature, basic refractory materials. The steel industry, the largest consumer of magnesia refractories, uses about 5.5 kg of MgO per metric ton of steel ingot produced. Magnesium compounds are also used in the production of a variety of other industrial and consumer goods including such diverse products as pulp and paper, sugar, rubber, chemicals, pharmaceuticals, fertilizers, textiles, glass, paint, cements, and ceramics.

In the United States, magnesium metal and magnesium compounds are recovered from seawater, well and lake brines, dolomite, brucite, and magnesite.

Prior to World War II, Nevada produced minor amounts of magnesium compounds; however, in the early 1940's production of magnesia greatly expanded principally for feed to the Government-built magnesium metal plant near Henderson, NV. All of the ore was obtained from deposits near Gabbs in Nye County. Magnesite mining for the production of refractory grade magnesia began in 1949 and has been carried out since.

Bureau of Mines Mineral Industry Location System (MILS) Data—Magnesium in Nevada

Total properties	35
Producers[1]	2
Known principal deposits	2
Deposit abstracts in directory	2

[1]Includes past producers.

Reported Magnesium Production[1]—United States and Nevada, 1978–83 (*722–723*)

Year	United States		Nevada	
	[2]10^3 t	Value, 10^3	10^3 t	Value, 10^3
1978	1,378	$221,626	W	W
1979	1,428	234,306	W	W
1980	1,297	277,506	W	W
1981	1,114	262,265	W	W
1982	915	222,287	W	W
1983	935	216,765	W	W

W Withheld to avoid disclosing company proprietary data.
[1]Magnesium compounds shipped and used.
[2]Rounded.

Principal Known Magnesium Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10^3 t	wt %	Year	Reference
Basic, Inc.[3]	Nye	Producer	MgO	Large	24,500	[4]<5	1956	749
Overton[3]	Clark	Explored	MgO	Medium	([5])	([5])	NAp	NAp

NAp Not applicable.
[1]Based on estimate of metric tons contained MgO: Large, >10 million; medium, 100,000 to 10 million; small, <100,000.
[2]Rounded.
[3]Deposit abstract in directory.
[4]Wt % CaO.
[5]No published data have been located.



Figure 22.—Magnesium in Nevada.

MANGANESE

Manganese, an extremely critical material in an industrial economy, is essential in the production of virtually all steels and pig iron. When added to the melt in small amounts (approximately 6.8 kg/t), manganese acts as a scavenger by combining with oxygen and sulfur to form easily removable slag. When added in larger amounts (10% to 14%), manganese imparts a work hardening characteristic to steel without sacrificing other desired properties. Manganese added to aluminum, magnesium, and copper increases strength, hardness, and/or corrosion resistance. Other uses of manganese include the production of dry cell batteries and chemicals.

The United States is almost totally dependent on imports to satisfy domestic manganese demand. Between 1978 and 1982, net U.S. import reliance ranged from 97% to 99% of domestic consumption. During war or other periods of artificially high prices, however, domestic mines have produced high-grade manganese ore or concentrates (>35% manganese). The Three Kids Mine in Clark County, the largest manganese producer in Nevada, is reported to have yielded more than 600,000 t of concentrates averaging about 45% manganese (*727*). Other major manganese past producers in Nevada include the Black Diablo Mine in Pershing County and the Caselton and Pioche No. 1 and 2 in Lincoln County. There has been no reported manganese production in Nevada since 1961.

Bureau of Mines Mineral Industry Location System (MILS) Data—Manganese in Nevada

Total properties	209
Producers[1]	69
Known principal deposits	5
Deposit abstracts in directory	5

[1]Includes past producers.

Reported Manganese Production[1]—United States and Nevada, 1978–83 (*722–723*)

Year	United States		Nevada	
	t	Value, 10^3	t	Value, 10^3
1978	34,723	$3,074	NRP	NRP
1979	27,998	2,902	NRP	NRP
1980	20,553	2,444	NRP	NRP
1981	22,067	2,890	NRP	NRP
1982	3,614	293	NRP	NRP
1983	3,335	216	NRP	NRP

NRP No reported production.

[1]Manganese content of manganiferous ore (5% to 35% Mn, natural) shipped. Shipments are used as a measure of manganiferous ore production. No manganese ore (35% or more Mn, natural) was reported shipped from 1978 through 1983.

Principal Known Manganese Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10^3 t	wt %	Year	Reference
Boulder City[3]	Clark	Explored	Mn	Medium	13,600	3	1949	407
Fannie Ryan[3]	do	do	Mn	Small	23	7.6	1949	407
Gibellini[3]	Eureka	do	Mn, Ni, Zn	do	([4])	([4])	NAp	NAp
Three Kids[3]	Clark	Past producer	Mn	Large	7,230	13.2	1982	351
Virgin River[3]	do	Expored	Mn	do	290	10	1949	407

[1]Based on estimate of metric tons of contained Mn: Large, >1 million; medium, 100,000 to 1 million; small, <100,000.
[2]Rounded.
[3]Deposit abstract in directory.
[4]No published data have been located.



Figure 23.—Manganese in Nevada.

MERCURY

Mercury possesses a combination of useful properties, namely, liquidity at ordinary temperatures, chemical stability, good electrical conductivity, high density and surface tension, uniform volume expansion, toxicity of its compounds for use in fungicides and other pesticides, and an ability to alloy readily. This latter property in particular, resulted in mercury having an important role in Nevada's early mining history. At one time, cinnabar was widely mined throughout the State and mercury, recovered by retorting, was used in early day gold mine operations to recover free gold and silver from placer and lode ores. This practice all but disappeared when free-milling ores were depleted and the cyanide process was developed. Today, over half of domestic mercury consumption is used in electrical apparatus. Other areas of principal use are in the electrolytic production of chlorine and caustic soda, mildew-proofing paint, and in industrial and control instruments.

Bureau of Mines Mineral Industry Location System (MILS) Data—Mercury in Nevada

Total properties	283
Producers[1]	124
Known principal deposits	4
Deposit abstracts in directory	3

[1]Includes past producers.

In recent years, Nevada has been the largest producer of primary mercury in the United States. In 1983, the State was the Nation's sole producer. Placer U.S. Inc.'s McDermitt Mine accounted for 99.8% of U.S. total mercury mine production in 1982, or 85% of total domestic mine and secondary mercury production. In 1983, Nevada supplied the nation with about 50% of the 50,000 flasks reported consumed. Although the bulk of mercury is produced from the McDermitt Mine, the Carlin, Pinson, and Borealis gold mines produce small quantities of mercury as a byproduct of gold refining. When the Paradise Peak gold mine commences production in the near future, about 90 t or 2,600 flasks of mercury is expected to be produced annually. An additional unknown quantity of mercury will be produced at the proposed Gold Quarry gold mine.

Reported Mercury Production—United States and Nevada, 1978–83 (*728–729*)

Year	United States		Nevada	
	Flasks	Value, 10^3	Flasks	Value, 10^3
1978	24,163	$3,705	24,163	$3,705
1979	29,519	8,299	29,368	8,256
1980	30,657	11,939	30,431	11,851
1981	27,904	11,549	27,819	11,514
1982	25,760	W	25,760	W
1983	25,070	W	25,070	W

W Withheld to avoid disclosing company proprietary data.

Principal Known Mercury Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10^3 t	kg/t	Year	Reference
B & B[3]	Esmeralda	Inactive-past producer	Hg, Sb	Small	(4)	(4)	NAp	NAp
Carson River[3]	Carson City	Inactive-Comstock wastes.	Hg, Au, Ag	Medium	(4)	(4)	NAp	NAp
McDermitt[3]	Humboldt	Active-producer	Hg	...do...	1,202	4.44	1982	564
Pilot Mountain district	Mineral	Inactive-past producer	Hg	Small-medium	(4)	(4)	NAp	NAp

NAp Not applicable.
[1]Based on estimate of flasks of contained Hg: Large, >500,000; medium, 500,000 to 10,000; small, <10,000.
[2]Rounded.
[3]Deposit abstract in directory.
[4]No published data have been located.



Figure 24.—Mercury in Nevada.

MOLYBDENUM

Molybdenum, a silver-white metallic element, is used as an alloying agent, refractory metal, and in lubricants, catalysts, and pigments. The United States has consistently been the world's largest producer of molybdenum, accounting for about two-thirds of the world annual output from 1976 through 1981. In 1982, however, the U.S. share of world production declined to about 41%, when domestic mines produced an estimated 38,275,000 kg of molybdenum, down from 63,458,000 kg in 1981. In 1983 U.S. mine output declined by nearly 60% and accounted for less than 25% of world molybdenum production.

Bureau of Mines Mineral Industry Location System (MILS) Data—Molybdenum in Nevada

Total properties	162
Producers[1]	2
Known principal deposits	5
Deposit abstracts in directory	4

[1]Includes past producers.

Until 1980, the molybdenum produced in Nevada was as a byproduct of cooper ore. By the end of 1981, Nevada's first primary molybdenum mine, the Anaconda Minerals Co. Nevada Moly Mine, was on-stream; however, no shipments were made. The mine operated through mid-1982, when the mill was shut down for modifications. Although milling resumed in October, the operation was again shut down in January 1983 because of the worldwide oversupply of molybdenum. In September 1983, operations resumed at 60% capacity.

Reported Molybdenum Production—United States and Nevada, 1978–83 (*728–729*)

Year	United States		Nevada	
	[1]10^3 t	Value, 10^3	[1]ton	Value, 10^3
1978	60	$807,950	45	$489
1979	55	871,068	18	242
1980	68	1,344,181	NRP	NRP
1981	63	995,541	NRP	NRP
1982	38	504,089	W	W
1983	15	167,184	W	W

NRP No reported production.
W Withheld to avoid disclosing company proprietary data.
[1]Rounded.

Principal Known Molybdenum Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					10^3 t	wt %	Year	Reference
B & C Springs[2]	Nye	Explored	Mo, Cu, Ag	Large	131,000	0.12	1983	710
Buckingham[2]	Lander	do	Mo, Ag, Cu, W	do	907,000	.06	1982	701
Mount Hope[2]	Eureka	Developing	Mo	do	408,000	[3].13-.32	1981	383
Nevada Moly[2]	Nye	Producer	Mo, Cu	do	455,000	.072 [4].068	1983	738
Pine Nut	Mineral	Explored	Mo, W	do	82,000	.06	1983	794

[1]Based on estimate of metric tons of contained Mo: Large, >200,000; medium, 5,000 to 200,000; small, <5,000.
[2]Deposit abstract in directory.
[3]Wt % MoS_2
[4]Wt % Cu.



Figure 25.—Molybdenum in Nevada.

SILVER

Both silver and gold have long been used as storehouses for wealth; however, silver possesses physical and chemical properties that also make it critical in producing many modern industrial and consumer products. Silver's unique properties include the highest electrical and thermal conductivity of all metals; the forming of photosensitive compounds; the resistance to oxidation at high temperatures while maintaining strength; and exceptional malleability and ductility. In 1982, U.S. consumers used about 4.66 million kg of silver while domestic mines yielded only slightly more than 1.25 million kg of primary metal or about 27% of apparent domestic consumption (*728*). Mines in Nevada contributed about 7.8% of the total domestic mine output and the State ranked fifth behind Idaho, Arizona, Montana, and Utah.

Nevada, the Silver State, earned its nickname early in its history when the rich ore bodies in the Comstock, Tonopah, and Eureka districts were discovered and mined. A recent revival in Nevada's silver mining industry began in 1979 in response to sharp increases in silver prices. Although industry activity slowed in 1981 and 1982, the revival had resumed momentum by 1983; the Sixteen-to-One commenced production in February 1982, and the Candelaria Mine, the Nation's largest open-pit silver mine, reopened in August 1983.

Nevada silver production is likely to increase over the next several years, especially if precious metal prices remain attractive. A major share of the increase will be from "byproduct" silver produced from Nevada's expanding gold mining industry. Several large gold mines are undergoing expansion and recent new discoveries may yield substantial silver. The Ward Mine should add a significant quantity of silver to the State's annual output when production commences after 1986.

Bureau of Mines Mineral Industry Location System (MILS) Data—Silver in Nevada

Total properties	2,479
Producers[1]	1,740
Known principal deposits	6
Deposit abstracts in directory	5

[1]Includes past producers.

Reported Silver Production—United States and Nevada, 1978–83 (*728–729*)

Year	United States		Nevada	
	[1]10^3 kg	Value, 10^3	kg	Value, 10^3
1978	1,225	$212,681	25,004	$4,341
1979	1,179	420,261	17,431	6,215
1980	1,006	666,955	29,237	19,392
1981	1,265	427,987	94,538	31,975
1982	1,252	319,902	97,735	24,981
1983	1,350	496,671	160,618	59,073

[1]Rounded.

Principal Known Silver Deposits in Nevada[1]

Deposit	County	Current status	Commodity	Size[2]	Published reserves-resources			
					[3]10^3 t	g/t	Year	Reference
Candelaria[4]	Mineral	Active-producer	Ag, Au	Medium	16,800	37.4	1983	423
Gooseberry[4]	Storey	do	Ag, Au	Small	509	349	1984	504
						[5]8.9		
Mohawk	Esmeralda	do	Ag	do	180	480	1980	762
Rochester[4]	Pershing	Active-feasibility	Ag, Au	Medium	80,100	51	1983	94
						[5].24		
Sixteen-to-One[4]	Esmeralda	Active-producer	Ag, Au	Small	1,000	190	1984	700
						[5].96		
Taylor[4]	White Pine	do	Ag, Au	Medium	6,000	110	1983	637

[1]Many of Nevada's gold deposits also contain significant silver reserves-resources and with moderate price changes could be described as silver properties; many of these gold-silver deposits are listed under "Principal Known Gold Deposits in Nevada."
[2]Based on estimate of metric tons of contained Ag: Large, >10,000; medium, 10,000 to 500; small, <500.
[3]Rounded.
[4]Deposit abstract in directory.
[5]g/t Au.



Figure 26.—Silver in Nevada.

TUNGSTEN

Tungsten, vital to the defense industry, is essential for high-speed wear-resistant applications in most plant, mine, construction, and drilling operations, and for lamp filaments and many other pure metal uses. It is an important alloying element in tool steel. Approximately 95% of domestic tungsten production, up about 31% in 1981 from 1980 levels, came from two mines in California and one each in Colorado and Nevada. The Emerson Mine, Lincoln County, NV, was that State's largest producer, accounting for over 90% of production in 1981. The Emerson, Nevada Scheelite, Springer, Red Ant No. 2, Bobby No. 4, and Wells Tungsten reportedly produced in 1981. As of July 1983, tungsten production in Nevada was at a much lower level as a result of depressed tungsten market conditions. In 1984, the principal Nevada tungsten mines remain closed.

Bureau of Mines Mineral Industry Location System (MILS) Data—Tungsten in Nevada

Total properties	597
Producers[1]	321
Known principal deposits	14
Deposit abstracts in directory	8

[1]Includes past producers.

Reported Tungsten Production[1]—United States and Nevada, 1978–83 (*728–729*)

Year	United States		Nevada	
	[2]10[3] kg	Value, 10[3]	[2]10[3] kg	Value, 10[3]
1978	3,130	$56,961	119	$1,687
1979	3,014	55,785	W	W
1980	2,738	50,575	W	W
1981	3,545	62,231	W	W
1982	1,575	22,062	W	W
1983	1,016	10,528	W	W

W Withheld to avoid disclosing company proprietary data.
[1]Production as measured by mine shipments, sales, or marketable production (including consumption by producers).
[2]Rounded.

Principal Known Tungsten Deposits in Nevada

Deposit	County	Current status	Commodity	Size[1]	Published reserves-resources			
					[2]10[3] t	wt %	Year	Reference
Desert Scheelite	Mineral	Past producer	W	Small	[3]	[3]	NAp	NAp
Emerson[4]	Lincoln	Standby	W, Mo, Zn, CaF_2, U	Large	[3]	[3]	NAp	NAp
Garnet-Tennessee Mountain.[4]	Elko	Past producer	W, Mo	Medium	359	[5]0.42	1977	526, 527
Granite Creek	Humboldt	do	W, Mo	Small	[3]	[3]	NAp	NAp
Gunmetal[4]	Mineral	do	W, Mo, Au	Large	[3]	[3]	NAp	NAp
Indian Springs[4]	Elko	Developed	W	do	12,610	[5].265	1970	147
					39,000	[5].164		
Linka[4]	Lander	Past producer	W, Mo	Small	[3]	[3]	NAp	NAp
Monte Cristo	White Pine	Explored prospect	W, Mo	Large	[3]	[3]	NAp	NAp
Nevada Scheelite[4]	Mineral	Past producer	W, Cu, Mo	do	[3]	[3]	NAp	NAp
Riley	Humboldt	do	W, Cu, Zn, Pb	Small	[3]	[3]	NAp	NAp
Riley Extension	do	do	W, Cu, Zn, Pb	do	[3]	[3]	NAp	NAp
Springer[4]	Pershing	Standby	W, Mo	Large	[3]	[3]	NAp	NAp
Tonopah[4]	Humboldt	Past producer	W, Cu, Mo	Medium	[3]	[3]	NAp	NAp
Wells	Elko	Producer	W	Small	[3]	[3]	NAp	NAp

NAp Not applicable.
[1]Based on estimate of metric tons of contained W: Large, >10,000; medium, 500 to 10,000; small, <500.
[2]Rounded.
[3]No published data have been located.
[4]Deposit abstract in directory.
[5]Wt % WO_3.



Figure 27.—Tungsten in Nevada.

ABSTRACTS OF SELECTED DEPOSITS IN NEVADA

As previously described, the heart of this publication consists of single-page, site-specific deposit abstracts for 119 selected deposits in Nevada. Figure 28 and table 9 serve as an index for the deposit abstract section.

TABLE 9.—Deposit abstract index

(Refer to figure 28)

Map No.	Deposit name	(1)	Map No.	Deposit name	(1)	Deposit name	(1)	Map No.	Deposit name	(1)	Map No.
1..	Indian Springs	W	60.	Dry Canyon	Sb	Alligator Ridge	Au	52	Indian Springs	W	1
2..	Easy Miner	$BaSO_4$	61.	Hard Luck-Pradier .	Sb	Ann	$BaSO_4$	86	Jungle	$BaSO_4$	6
3..	Snoose	$BaSO_4$	62.	Bray-Beulah	Sb	Ann Mason	Cu	68	Kay	$BaSO_4$	88
4..	Big Ledge	$BaSO_4$	63.	Gooseberry	Ag	Antimony King	Sb	59	Lakes	$BaSO_4$	11
5..	Stormy Creek	$BaSO_4$	64.	Dayton	Fe	Argenta	$BaSO_4$	39	Linka	W	58
6..	Jungle	$BaSO_4$	65.	Carson River	Hg	Atlanta	Au	106	Maggie Creek	Au	15
7..	Garnet-Tennessee Mountain.	W	66.	Minnesota	Fe	Aurora	Au	80	Mammoth	CaF_2	107
			67.	McArthur	Cu	B & B	Hg	83	Manhattan	Au	91
8..	McDermitt	Hg	68.	Ann Mason	Cu	B & C Springs	Mo	77	McArthur	Cu	67
9..	Montana Mountains	Li	69.	Yerington	Cu	Bald Mountain	Au	51	McDermitt	Hg	8
10.	Enfield Bell	Au	70.	Bear	Cu	Basic, Inc.	MgO	76	McGill Tailings	Cu	100
11.	Lakes	$BaSO_4$	71.	Pumpkin Hollow ...	Fe	Battle Mountain Copper Basin.	Cu	40	Minnesota	Fe	66
12.	Fish Creek	$BaSO_4$	72.	Calico Hills	Fe				Modarelli	Fe	45
13.	Heavy Spar	$BaSO_4$	73.	Bell Mountain	Au	Battle Mountain Copper Canyon.	Au	42	Montana Mountains	Li	9
14.	Gold Quarry	Au	74.	Nevada Scheelite ..	W				Mount Hope	Mo	49
15.	Maggie Creek	Au	75.	Phelps-Stokes	Fe	Bear	Cu	70	Mount Wheeler ...	Be	104
16.	Carlin	Au	76.	Basic, Inc.	MgO	Bell Mountain	Au	73	Mountain Springs ..	$BaSO_4$	43
17.	Bullion Monarch ...	Au	77.	B & C Springs	Mo	Big Ledge	$BaSO_4$	4	Nevada Moly	Mo	92
18.	Blue Star	Au	78.	Santa Fe	Au	Bisoni	CaF_2	55	Nevada Scheelite ..	W	74
19.	Goldstrike	Au	79.	Borealis	Au	Bloody Canyon	Sb	29	Northumberland ...	Au	85
20.	Bootstrap	Au	80.	Aurora	Au	Blue Star	Au	18	Nyco	CaF_2	108
21.	Dee	Au	81.	Gunmetal	W	Bootstrap	Au	20	Overton	MgO	115
22.	Queen Lode	$BaSO_4$	82.	Candelaria	Ag	Borealis	Au	79	P & S	$BaSO_4$	84
23.	Rossi	$BaSO_4$	83.	B & B	Hg	Boulder City	Mn	119	Pan American	Pb-Zn	112
24.	Getchell	Au	84.	P & S	$BaSO_4$	Bray-Beulah	Sb	62	Phelps-Stokes	Fe	75
25.	Tonopah	W	85.	Northumberland ...	Au	Buckhorn	Au	46	Pinson	Au	28
26.	Pinson	Au	86.	Ann	$BaSO_4$	Buckingham	Mo	41	Plute	Fe	37
27.	Preble	Au	87.	East Northumberland.	$BaSO_4$	Buena Vista	Fe	38	Preble	Au	27
28.	Springer	W				Bullion Monarch ...	Au	17	Prince	Pb-Zn	111
29.	Bloody Canyon	Sb	88.	Kay	$BaSO_4$	C-M Alunite	Al	114	Pumpkin Hollow ...	Fe	71
30.	Rochester	Ag	89.	Round Mountain ..	Au	Calico Hills	Fe	72	Queen Lode	$BaSO_4$	22
31.	Relief Canyon	Au	90.	White Caps	Sb	Candelaria	Ag	82	Rain	Au	38
32.	Sutherland	Sb	91.	Manhattan	Au	Carlin	Au	16	Rainbow	CaF_2	109
33.	Hollywood	Sb	92.	Nevada Moly	Mo	Carson River	Hg	65	Relief Canyon	Au	31
34.	Dodge-Ford	Fe	93.	Tonopah Divide ...	Au	Caselton	Pb-Zn	110	Ridge 7129	Zn	57
35.	Fencemaker	Sb	94.	Tonopah Hasbrouck	Au	Crowell	CaF_2	98	Robinson district ..	Cu	101
36.	Buena Vista	Fe	95.	Silver Peak	Li	Dayton	Fe	64	Rochester	Ag	30
37.	Plute	Fe	96.	Sixteen-to-One	Ag	Dee	Au	21	Rossi	$BaSO_4$	23
38.	Rain	Au	97.	Goldfield	Au	Dodge-Ford	Fe	34	Round Mountain ..	Au	89
39.	Argenta	$BaSO_4$	98.	Crowell	CaF_2	Dry Canyon	Sb	60	Ruby Hill	Pb-Zn	53
40.	Battle Mountain Copper Basin.	Cu	99.	Sterling	Au	East Northumberland.	$BaSO_4$	87	Santa Fe	Au	78
			100	McGill Tailings	Cu				Silver Peak	Li	95
41.	Buckingham	Mo	101	Robinson district ..	Cu	Easy Miner	$BaSO_4$	2	Sixteen-to-One	Ag	98
42.	Battle Mountain Copper Canyon.	Au	102	Ward	Pb-Zn	Emerson	W	113	Snoose	$BaSO_4$	3
			103	Taylor	Ag	Enfield Bell	Au	10	Springer	W	28
43.	Mountain Springs ..	$BaSO_4$	104	Mount Wheeler ...	Be	Fannie Ryan	Mn	117	Sterling	Au	99
44.	Greystone	$BaSO_4$	105	White Pine	CaF_2	Fencemaker	Sb	35	Stormy Creek	$BaSO_4$	5
45.	Modarelli	Fe	106	Atlanta	Au	Fish Creek	$BaSO_4$	12	Sutherland	Sb	32
46.	Buckhorn	Au	107	Mammoth	CaF_2	Garnet-Tennessee Mountain.	W	7	Taylor	Ag	103
47.	Horse Canyon	Au	108	Nyco	CaF_2				Three Kids	Mn	118
48.	Tonkin Springs	Au	109	Rainbow	CaF_2	Getchell	Au	24	Tonkin Springs	Au	48
49.	Mount Hope	Mo	110	Caselton	Pb-Zn	Gibellini	Mn	58	Tonopah	W	25
50.	Victoria	Cu	111	Prince	Pb-Zn	Gold Quarry	Au	14	Tonopah Divide ...	Au	93
51.	Bald Mountain	Au	112	Pan American	Pb-Zn	Goldfield	Au	97	Tonopah Hasbrouck	Au	94
52.	Alligator Ridge	Au	113	Emerson	W	Gold Strike	Au	19	Victoria	Cu	50
53.	Ruby Hill	Pb-Zn	114	C-M Alunite	Al	Gooseberry	Ag	63	Virgin River	Mn	118
54.	Windfall	Au	115	Overton	MgO	Greystone	$BaSO_4$	44	Ward	Pb-Zn	102
55.	Bisoni	CaF_2	116	Virgin River	Mn	Gunmetal	W	81	White Caps	Sb	90
56.	Gibellini	Mn	117	Fannie Ryan	Mn	Hard Luck-Pradier .	Sb	81	White Pine	CaF_2	105
57.	Ridge 7129	Zn	118	Three Kids	Mn	Heavy Spar	$BaSO_4$	13	Windfall	Au	54
58.	Linka	W	119	Boulder City	Mn	Hollywood	Sb	33	Yerington	Cu	69
59.	Antimony King	Sb				Horse Canyon	Au	47			

[1]Primary commodity.



Figure 28.—Location of principal deposits with deposit abstracts.

ALLIGATOR RIDGE—GOLD

Ore body names: Vantage 1, 2, and 3

Commodities: Au, Ag, Hg (Au-Ag ratio = 9:1)

LOCATION-OWNERSHIP

County	White Pine.	General location	About 50 km northeast of Eureka.
Mining district	Buck Mountain (8 km north of mine).	Meridian	Mount Diablo.
Elevation	2,250 m.	Tract	Sec. 1, T 22 N, R 57 E.
Topography	Rugged.	Latitude	39°48′24″ N.
Domain	Public, BLM-administered.	Longitude	115°31′12″ W.

Owner: Amselco Minerals, Inc., Denver, CO (subsidiary of Selection Trust Ltd., London, England), 50%; NERCO Minerals Co., Fairbanks, AK (subsidiary of Pacific Power & Light Co., Portland, OR), 50% (1984).

Operator: Amselco Minerals, Inc. (1984).

GEOLOGY[1]

Type of ore body	Disseminated; stratabound.	Host formation	Pilot Shale.
Origin	Hydrothermal.	Geologic age	Mississippian.
Shape of ore body	Irregular.	Rock relationships	Siltstone, silicified-brecciated, contains ore.
Ore controls	Bedding; faulting.		Siltstone, unaltered carbonaceous calcareous, is unaltered, unmineralized Pilot Shale.
Strike and dip of mineralized zone.	N 20° E; nearly horizontal.		Limestone is above and below host rock.
Age of mineralization	Tertiary (5 to 30 million yr).	Alteration	Jasperoid silicification, oxidation, decarbonatization.
Mineralized zone average dimensions, m:		Size	Medium.
Length	915.		
Width	305.		
Thickness	75.		
Depth	120 (deepest ore body).		

Mineral names: Gold (coarse free and submicrometer free); oxide zone—specular hematite, jarosite, stibiconite, goethite, drusy quartz, barite, calcite, gypsum, alunite, kaolinite; carbonaceous ore—stibnite, pyrite, orpiment, realgar, calcite.

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	On-site wells, 180 m deep.
Type of operation	Surface.	Road requirement	Amselco improved about 50 km of county road.
Mining method	Open pit: 680,000-t/a capacity.	Distance to power supply	50- to 60-km powerline constructed.
Year of discovery	June 1976.	Mill location	On-site.
Discovery method	Outcrop sampling.	Mill status	Active.
Initial production	May 1981.	Milling method	Agglomeration, heap cyanide leaching, carbon adsorption, electrolysis, smelting.
Past production	1,980.3 kg (63,668 tr oz) Au, 141.8 kg (4,558 tr oz) Ag (1981) (*133*).	Process rate	680,000 t/a (2,700 t/d).
	Total, 1.8 million t (2 million ton) ore with 3.91 g/t (0.114 tr oz/ton) leachable metal (1981-83) (*15*).	Product type	Dore bullion bars; 92% Au, 6% Ag.
		Distance shipped	About 700 km.
		Destination	Anaheim, CA.
Annual production rate	About 1,900 kg Au (60,000 tr oz), 440 kg Ag (14,000 tr oz).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1. Not reported in reference	14,000,000 tons	0.12 tr oz/ton Au	1981	61
2. Demonstrated	5,000,000 tons	0.12 tr oz/ton Au (average stripping ratio of 3.08:1; tons waste:tons ore).	1981	835
3. Proven	3,900,000 tons	0.092 tr oz/ton Au (stripping ratio = 3.5:1)	1983	15

REFERENCES

15, 61, 82, 83, 90, 111, 133, 163, 227, 284, 297, 298, 358, 378, 400, 412, 481, 565, 587, 681, 835.

USGS quad maps	Ely, 1:250,000. Cold Creek, 15′.
USBM sequence number	0320330470.
Mid number	2601624.

[1]The deposit, as presently defined, consists of 4 separate but adjacent mineralized areas. Ore bodies are irregular but roughly circular in plan with widths of 100 to 200 m, lengths of 200 m, and thicknesses estimated at 40 to 50 m. Pilot Shale host is approximately 60 to 90 m thick but thins and disappears to the west and south. 1984 projected mine life is mid-1988.

ANN—BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Nye.	General location	About 65 km southeast of Austin.
Mining district	Northumberland.	Meridian	Mount Diablo.
Elevation	2,500 m.	Tract	Sec. 28, T 13 N, R 46 E.
Topography	Rugged.	Latitude	38°55′40″ N.
Domain	Federal; National forest.	Longitude	116°47′45″ W.
Owner	W. B. Kohlmoos, N. S. Mallory, T. Corder (1983).		
Operator	Dresser Industries, Dallas, TX (1983).		

GEOLOGY

Type of ore body	Bedded replacement.	Host formation	Pinecone.
Origin	Sedimentary.	Geologic age	Devonian.
Shape of ore body	Irregular.	Rock relationships	Chert.
Ore controls	Bedding.		Claystone, lies over ore.
Strike and dip of mineralized zone.	N 40° E: 45° E.		Mudstone.
		Size	Medium.
Mineralized zone average dimensions, m.	Unknown.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-explored.	Distance to water supply	<3 km.
Type of operation	Possible surface.	Road requirement	<10 km.
		Distance to power supply	<10 km.
Year of discovery	1967.	Mill location	No mill.
Discovery method	Ore mineral in place.		
Initial production	No production.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

338, 357, 368, 546, 623, 624.

USGS quad maps	Tonopah, 1:250,000.
	Northumberland Pass, 7.5′.
USBM sequence number	0320230718.

ANN MASON—COPPER

Alternate names: None

Commodities: Cu, Mo

LOCATION-OWNERSHIP

County	Lyon.
Elevation	1,829 m.
Domain	BLM administered.
General location	About 58 km southeast of Carson City.
Meridian	Mount Diablo.
Tract	Sec. 13, T 13 N, R 24 E.
Latitude	38°59'03" N.
Longitude	119°14'47" W.

Owner: The Anaconda Minerals Co., Denver, CO (a wholly owned subsidiary of Atlantic Richfield Co., Denver, CO)(1984).

GEOLOGY

Type of ore body	Disseminated, porphyry copper.
Origin	Magmatic, hydrothermal.
Shape of ore body	Irregular.
Ore controls	Dikes, faulting.
Plunge and dip of mineralized zone.	West: gentle.
Age of mineralization	168 million yr.
Mineralized zone average dimensions, m:	
Length	2,360.
Thickness	+530.
Depth	90 to +240.
Mineral names	Chalcopyrite, pyrite, bornite, molybdenite, goethite, limonite, chrysocolla, hematite, quartz, K-feldspar, plagioclase, hornblende, biotite, magnetite, sphene, apatite, zircon, ilmenite, augite, chlorite, sericite.
Host formation	Yerington Batholith.
Geologic age	Jurassic.
Rock relationships	Quartz monzonite, encloses ore, gangue.
	Porphyrtic quartz monzonite, encloses ore, gangue.
	Granodiorite, encloses ore, gangue.
	Quartz monzonite porphyry dikes; highest ore grades occur near dikes.
	Tertiary volcanics; above ore on the north.
Alteration	Sodic-calcic, potassic, propylitic, sodic, sericitic.
Size	Large.

DEVELOPMENT

Current status	Inactive-explored prospect.
Type of operation	Prospect.
Year of discovery	1968.
Discovery method	Geophysical, drilling.
Initial production	No production.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	495,000,000 tons	0.40% Cu	1976	829

REFERENCES

126, 128, 453, 567, 695, 822, 829.

USGS quad maps	Walker Lake, 1:250,000. Yerington, 15'.
USBM sequence number	0320190169.

Comments: Copper mineralization is contemporaneous with and spatially related to a swarm of quartz monzonite porphyry dikes that intrude into granodiorite and quartz monzonite. Mineralized zone dimensions are for >0.2% Cu.

ANTIMONY KING—ANTIMONY

Alternate names: Last Chance, Pine, Dry Canyon, Big Creek, Stokes, Mammoth, Mountain View, Commodore, Confidence

Commodities: Sb

LOCATION-OWNERSHIP

County	Lander.
Mining district	Big Creek.
Elevation	2,682 m.
Topography	Rugged.
Domain	Mixed.
Owner	Donald Colson (1984).
Lessee	FMC Corp., Reno, NV (1984).
General location	About 12 km southwest of Austin.
Meridian	Mount Diablo.
Tract	Sec. 26, T 18 N, R 43 E.
Latitude	39°23'27" N.
Longitude	117°06'08" W.

GEOLOGY

Type of ore body	Shear zone; fracture zone.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Faulting; fracturing.
Strike and dip of mineralized zone.	N 55° W: 55° W.
Mineralized zone average dimensions, m:	
Length	200.
Width	40.
Thickness	2.
Depth	0.
Mineral names	Stibnite, pyrite.
Host formation	Valmy.
Geologic age	Ordovician.
Rock relationships	Shale, encloses ore.
	Limestone, encloses ore.
	Sandstone, near ore.
	Chert, near ore.
	Siltstone, near ore.
Size	Small.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Underground.
Year of discovery	1890.
Discovery method	Ore mineral in place.
Initial production	1907.
Last production	1970.
Past production	454 t Sb metal (*376*).
Distance to water supply	<10 km.
Road requirement	<50 km.
Distance to power supply	<50 km.
Mill location	No mill.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

376, 693.

USGS quad maps	Millett, 1:250,000.
	Austin, 15'.
USBM sequence number	0320150034.

Comments: Some production apparently combined with or reported as output from the Dry Canyon antimony mine.

ARGENTA—BARITE

Alternate names: Barium King, Milchem, Nevada Barite, Yuba-Shelton, Baryte No. 1, 3

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Lander.	General location	About 18 km east of Battle Mountain.
Mining district	Argenta.	Meridian	Mount Diablo.
Elevation	1,890 m.	Tract	Sec. 19, T 32 N, R 47 E.
Topography	Rugged.	Latitude	40°38′14″ N.
Domain	Public; private.	Longitude	116°44′20″ W.

Owner: Milchem, Inc., Battle Mountain, NV (1984).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Slaven.
Origin	Sedimentation.	Geologic age	Devonian.
Shape of ore body	Tabular.	Rock relationships	Chert, lies over ore, encloses ore.
Ore controls	Bedding; lithology.	Size	Medium.
Strike and dip of mineralized zone.	N 10° E: 20° E.		
Mineralized zone average dimensions, m:			
Length	400.		
Width	170.		
Thickness	15.		
Depth	60.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	On-site.
Type of operation	Open pit.	Road requirement	None.
		Distance to power supply	On-site.
Initial production	1935.	Mill location	65 km north of mine.
Last production	1983.	Mill status	Active.
Past production	About 5,215,000 t barite mined to January 1982 (*385*).	Milling method	Crushing, jigging, grinding.
		Product type	Jigged and ground barite.
		Distance shipped	Gulf Coast, California, Wyoming, and Canada.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

87, 283, 330, 346, 385, 392, 546, 548, 601, 688, 693.

USGS quad maps	Winnemucca, 1:250,000. Dunphy, 15′.
USBM sequence number	0320150057.
Mid number	2600635.

Comments: Existing pit operations cover about 40.5 ha. The Argenta has been divided into 6 major areas for development, of which 2 are currently being stripped and mined.

ATLANTA—GOLD

Alternate names: Atlanta Home, Atlanta Strip, Hillside, Sparrow Hawk, Pactolion Fraction, Belle

Commodities: Au, Ag, minor U

LOCATION-OWNERSHIP

County	Lincoln.
Mining district	Atlanta.
Elevation	2,073 m.
Topography	Hilly.
General location	About 80 km northeast of Pioche.
Meridian	Mount Diablo.
Tract	Sec. 24, T 7 N, R 68 E.
Latitude	38°27′57″ N.
Longitude	114°19′18″ W.
Owner-operator	Standard Slag Co., Reno, NV (1984).
Owner	Bobcat Properties, Inc., Fort Lauderdale, FL (1984).

GEOLOGY

Type of ore body	Disseminated gold in shear-breccia zone.
Origin	Hydrothermal; open space filling of breccia zone.
Shape of ore body	Tabular (planet).
Ore controls	Faulting, silicification, brecciation.
Strike and dip of mineralized zone.	N 5° E: 45° W.
Age of mineralization	Tertiary.
Mineralized zone average dimensions (breccia zone), m:	
Length	200.
Width	250.
Mineral names	Gold (microscopic), silver (microscopic), limonite, quartz, manganese oxides, jasperoid, hematite, barite, clay.
Host formation	Ely Springs Dolomite (see comments).
Geologic age	Ordovician.
Rock relationships	Dolomite, massive dolomite below ore zone. Jasperoid breccia, portions are ore. Quartz porphyry, near ore, in places contains low-grade gold.
Alteration	Silicification, intense; kaolinitic argillization; alunitization.
Size	Small.

DEVELOPMENT

Current status	Active-producer.
Type of operation	Surface.
Mining method	Open pit; multiple bench.
Year of discovery	About 1906; reactivated in 1974.
Initial production	1975 (Standard Slag).
Last production	Ongoing 1984.
Past production	May 1, 1975, to May 31, 1982: 2,500 kg (80,000 tr oz) Au, 12,000 kg (400,000 tr oz) Ag. Estimated total ore milled is 860,000 t (*680*).
Annual production rate	Estimated 400 kg (13,000 tr oz) Au and 2,000 kg (65,000 tr oz) Ag (*132*).
Distance to water supply	14 km.
Road requirement	Existing to site.
Distance to power supply	On-site, 26-km line.
Mill location	On-site.
Mill status	Active, producing.
Milling method	Cyanide leach, countercurrent decantation, Merrill-Crowe zinc precipitation, smelting.
Process rate	520 t/d (570 ton/d).
Product type	Bullion.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	1,100,000 tons	0.08 tr oz/ton Au; 1.6 tr oz/ton Ag	1980	61

REFERENCES

61, 102, 132, 207, 265, 288, 289, 393, 412, 617, 678, 680, 723, 724.

USGS quad maps	Lund, 1:250,000. Atlanta, 7.5′.
USBM sequence number	0320170169.
USGS MRDS number	M032067.
Mid number	2601143.

Comments: The Atlanta ore body carries disseminated submicroscopic gold and uranium within a breccia zone consisting of brecciated fragments of limestone (Ordovician-Ely Springs Dolomite), quartz porphyry, quartzite (Ordovician-Eureka Quartzite), volcanic rocks (possibly Tertiary-ignimbrites), jasperoid. Breccia is cemented chiefly by quartz. The ore zone has been intruded by quartz-porphyry and is bounded by 2 high-angle, west-dipping normal faults. Tertiary volcanic ignimbrites form the hanging wall; the Ely Springs Dolomite forms the footwall.

AURORA—GOLD

Patented claim names: Silver Lining Consolidated, Humboldt, Humboldt W., Astor, Alice C. Dennis
Alternate names: Humboldt East Claims, Humboldt West Claims

Commodities: Au, Ag

LOCATION-OWNERSHIP

County	Mineral.	General location	About 35 km north of Hawthorne.
Mining district	Aurora.	Meridian	Mount Diablo.
Elevation	2,290 m.	Tract	Sec. 17, T 5 N, R 28 E.
Topography	Hilly.	Latitude	38°12'23" N.
Domain	Private.	Longitude	118°53'16" W.

Owner-lessee ..... Electra North West Resources, Ltd., Vancouver, BC, Canada (1983).
Owner-lessee ..... Centennial Minerals, Ltd., Vancouver, BC, Canada (1983).
Operator ..... Centennial Exploration Corp. (1983).
(Portions of the property are leased from Hanna Mining Co. and from Houston International Minerals.)

GEOLOGY

Type of ore body	Fissure vein.	Host formation	Volcanics.
Origin	Hydrothermal.	Geologic age	Tertiary.
Shape of ore body	Tabular.	Rock relationships	Andesite, altered, encloses ore. Quartz, vein encloses ore, vein is ore.
Ore controls	Faulting.		
Strike and dip of mineralized zone.	N 40° E: 60 to 70° W.	Alteration (district)	Potassic, argillic, propylitic.
Age of mineralization	10 million yr.	Size	Small.
Pit zone average dimensions (1983 plan), m:			
Length	490.		
Width	60 to 120.		
Depth	12 to 35.		

Mineral names ..... Native gold, quartz, sulfides (sparse) (typical mineralogy of ore veins has been quartz, adularia, argentiferous tetrahedrite, pyrite, chalcopyrite, and soft blue-gray material containing gold, and native gold).

DEVELOPMENT

Current status	Active-producer; developing.	Distance to water supply	900 m, from abandoned underground workings.
Type of operation	Surface.	Road requirement	No new access road required.
Mining method	Open pit.	Distance to power supply	On-site diesel electric generation.
Year of discovery	District discovery in 1860.	Mill location	On-site.
Discovery method	Unknown.	Mill status	Active-testing.
Initial production	June 1983 (planned).	Milling method	Test cyanide heap leach, adsorption-desorption columns, electrolysis, smelting.
Past production	The first dore was planned to be poured in July 1983. Planned production for 1983 was 77,000 t containing about 300 kg gold. Anticipated recovery was 70%. Total waste production planned was 200,000 t (*309*).	Process rate	90-t jaw and cone crusher, estimate about 1,600 t/d and 196,000 t/a.
		Product type	Gold dore.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Probable and inferred	1,500,000 tons	0.129 tr oz/ton Au	1983	309
2..Not reported in reference	1,200,000 tons	0.13 tr oz/ton Au; 0.30 tr oz/ton Ag	1982	444

REFERENCES

7, 90, 228, 309, 356, 444, 598.

USGS quad maps	Walker Lake, 1:250,000. Aurora, 15'.
USBM sequence number	0320210544.
Mid number	2601790.

Comments: Ore body reflected in published reserves is reported to be open at depth and along strike.

B & B—MERCURY

Alternate names: Chrysler, Kollsman Mine

Commodities: Hg, Sb

LOCATION-OWNERSHIP

County	Esmeralda.
Mining district	Oneota (Fish Lake Valley).
Elevation	2,414 m.
Topography	Rugged.
Domain	National forest.
General location	About 91 km west of Tonopah and 27 km northwest of Dyer.
Meridian	Mount Diablo.
Tract	Sec. 1, T 1 S, R 33 E.
Latitude	37°53'17" N.
Longitude	118°15'04" W.

Owner: Robert W. Hughes (locator), Las Vegas, NV (1982).

GEOLOGY

Type of ore body	Disseminated; breccia fill.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Faulting; lithology; bedding.
Mineralized zone average dimensions, m (estimated):	
Length	600.
Width	300.
Thickness	15.
Mineral names	Cinnabar, schuetteite, chalcedony, opal, zeolites, alunite, kermesite.
Host formation	Volcanics.
Geologic age	Tertiary.
Rock relationships	Opalite blanket, encloses ore, gangue. Rhyolite tuff, lies under ore. Andesite breccia, near ore.
Alteration	Extensive silicification of rhyolite tuffs.
Size	Small.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Surface; underground.
Mining method	Open pit; drift.
Year of discovery	1925.
Discovery method	Ore mineral in place.
Initial production	1927.
Last production	1970.
Past production	See comments.
Distance to water supply	<3 km.
Road requirement	None.
Distance to power supply	<10 km.
Mill location	On-site.
Mill status	Dismantled.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

8, 29, 42, 103, 148, 276, 376.

USGS quad maps	Mariposa, 1:250,000. Benton, 15'.
USBM sequence number	0320090084.
USGS MRDS number	M055003.

Comments: Published past production data are obscure and some production credited to the B & B Mine between 1957 and 1970 was taken from other ore bodies nearby. Mercury production from the district is probably about 8,000 flasks. The remaining reserves are low grade and large tonnage.

B & C SPRINGS—MOLYBDENUM

Alternate names: B C Project, B C Well, U.V. Industries Moly Prospect

Commodities: Mo, Cu, Ag

LOCATION-OWNERSHIP

County	Nye.	General location	About 75 km northeast of Hawthorne.
Mining district	Paradise Peak.	Meridian	Mount Diablo.
Elevation	2,140 m.	Tract	Sec. 34, T 11 N, R 37 E.
Topography	Rolling.	Latitude	38°46'50" N.
Domain	Mixed.	Longitude	117°48'06" W.

Owner: Sharon Steel Corp., Miami Beach, FL (1982).

GEOLOGY

Type of ore body	Disseminated; fissure vein.	Host formation	Luning.
Origin	Hydrothermal; contact metasomatic.	Geologic age	Upper Triassic.
Shape of ore body	Irregular; tabular.	Rock relationships	Limestone, is ore, encloses ore.
Ore controls	Lithology; igneous.	Size	Large.
Strike and dip of mineralized zone.	N 15° E: 05° E.		
Mineralized zone average dimensions, m:			
Length	1,195.		
Width	465.		
Thickness	51.		
Depth	172.		

Mineral names: Molybdenite, chalcopyrite, pyrite, tetrahedrite, sphalerite, covellite, magnetite, calcite, dolomite, quartz.

DEVELOPMENT

Current status	Active-explored prospect.	Distance to water supply	On-site.
		Road requirement	<50 km.
Year of discovery	1968.	Distance to power supply	<50 km.
Discovery method	Geophysical anomaly.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	131,000,000 t	0.12% Mo	1983	710

REFERENCES

11, 29, 156, 196, 357, 368, 433, 626, 646, 710, 750, 758, 827, 828, 837.

USGS quad maps	Tonopah, 1:250,000. Paradise Peak, 7.5'.
USBM sequence number	0320230678.

BALD MOUNTAIN—GOLD

Alternate names: BF Claim Group, Top Group

Commodities: Au

LOCATION-OWNERSHIP

County	White Pine.
Mining district	Bald Mountain.
Elevation	2,440 m.
Topography	Mountainous.
Domain	BLM administered.
General location	About 130 km northwest of Ely.
Meridian	Mount Diablo.
Tract	Secs. 16, 17, 18, T 24 N, R 57 E (unsurveyed).
Latitude	39°57′55″ N.
Longitude	115°34′31″ W.

Owner-operator ..... Placer U.S., Inc., San Francisco, CA (subsidiary of Placer Development Ltd., Vancouver, BC, Canada), 75% ownership (1984).

GEOLOGY

Type of ore body	Disseminated.
Origin	Probably hydrothermal.
Shape of ore body	Unknown.
District ore controls	Faulting, lithology.
Strike and dip of district rocks.	Northwest: 10° to 20° E.

Mineralized zone development dimensions, m:

	Area 1	Area 3	Area 5	Top area
Length	600	600	600	760
Width	600	460	300	760

Mineral names ..... Unavailable

(Known district minerals include quartz, jasper, pyrite, calcite, stibnite, malachite, chrysocolla, cerussite, powellite, molybdenite.)

Host formation	Unknown.
Geologic age	Unknown.
Rock relationships	Limey shales, surface, at drill roads. Limestone, surface, at drill roads.
Size	Small.

NOTE: Past district gold production came from veinlike replacement deposits in breccia zones (some jasperoid) along northwest-, northeast-, or north-striking faults in limestone; northwest- or west-striking quartz veins in quartz monzonite porphyry, and valley placers.

DEVELOPMENT

Current status	Active-testing; exploration; development.
Type of operation	Surface.
Mining method	Conventional open pit.
Year of discovery	Exploration since 1975.
Discovery method	Geochemical; drilling.
Initial production	1983 (initial testing).
Last production	Ongoing.
Past production	For 2 months, 109 kg (3,500 tr oz) Au was produced from 60,000 t of ore during test heap leaching (1983) (*499*).
Distance to water supply	On-site; deep well.
Road requirement	Access—13 km improvement; 3 km new.
Distance to power supply	Unknown.
Mill location	On-site.
Mill status	Construction.
Milling method	Conventional cyanide heap leach—study ongoing whether carbon-adsorption or zinc precipitation for gold recovery.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Reserves indicated	1,600,000 t	3.43 g/t Au	1981	563
2..Not reported in reference[1]	200,000 tons	0.10 tr oz/ton Au	1983	495
3..Indicated and inferred	2,800,000 tons	0.09 tr oz/ton Au	1984	499

REFERENCES

58, 284, 495, 499, 563, 577, 587, 618, 785.

USGS quad maps	Ely, 1:250,000. Cold Creek Ranch, 15′.
USBM sequence number	0320330503.

Comments: In 1983, mining of 230,000 t of ore from Area 5 at the rate of 1,800 t/d began for test heap leaching. Tests were scheduled to begin in September 1983 and end in June 1984. Intensive ongoing exploration in 1983 was defining reserves in the 3 other adjacent areas. Reserves are contained in 6 deposits.

[1]This resource was described as minable reserves for test work.

BASIC, INC.—MAGNESITE

Alternate names: Gabbs

Commodities: MgO

LOCATION-OWNERSHIP

County	Nye.
Mining district	Gabbs.
Elevation	1,646 m.
Topography	Rugged.
Domain	Private; BLM administered.
Owner	C-E Basic, Gabbs, NV (1984).
General location	About 74 km northeast of Hawthorne.
Meridian	Mount Diablo.
Tract	Sec. 26, T 12 N, R 36 E.
Latitude	38°52'11" N.
Longitude	117°53'50" W.

GEOLOGY

Type of ore body	Replacement.
Origin	Metamorphism; hydrothermal.
Shape of ore body	Irregular; massive.
Ore controls	Lithology.
Mineralized zone average dimensions, m:	
Length	1,520.
Width	1,000.
Thickness	60.
Depth	0.
Mineral names	Magnesite, brucite.
Host formation	Luning.
Geologic age	Triassic.
Rock relationships	Limestone, lies under ore. Shale, lies under ore. Dolomite, replaced by ore, gangue.
Size	Large.

DEVELOPMENT

Current status	Active-producer.
Type of Operation	Surface.
Mining method	Open pit.
Year of discovery	1927.
Discovery method	Ore mineral in place.
Initial production	1941.
Last production	1984.
Past production	Confidential proprietary data.
Distance to water supply	<3 km.
Road requirement	None.
Distance to power supply	On-site.
Mill location	On-site.
Mill status	Active.
Milling method	Crushing, heavy media, flotation, calcining.
Process rate	2,000 t/d.
Product type	Refractory magnesia.
Distance shipped	46 km.
Destination	Luning, NV, for transshipment.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Measured	27,000,000 tons	Magnesite containing <5% CaO	1956	749
2.. Do	18,000,000 tons	Magnesite containing 5% to 26% CaO	1956	749
3.. Do	7,000,000 tons	Magnesite containing >26% CaO	1956	749
4..Indicated	2,000,000 tons	Magnesite containing <5% CaO	1956	749
5.. Do	100,000 tons	Magnesite containing 5% to 26% CaO	1956	749

REFERENCES

212, 273, 357, 368, 609, 688, 699, 733, 749.

USGS quad maps	Tonopah, 1:250,000. Paradise Peak, 15'.
USBM sequence number	0320230158.
Mid number	2600864.

BATTLE MOUNTAIN COPPER BASIN—COPPER

Alternate names: Copper Basin Mine-Duval Corp.

Commodities: Cu, Ag, Au

LOCATION-OWNERSHIP

County	Lander.
Mining district	Battle Mountain.
Elevation	1,615 m.
Topography	Rugged.
Domain	Private.
General location	About 10 km southwest of Battle Mountain.
Meridian	Mount Diablo.
Tract	Sec. 32, T 32 N, R 44 E.
Latitude	40°36'12" N.
Longitude	117°02'50" W.
Owner-operator	Duval Corp., Tucson, AZ (subsidiary of Pennzoil Co., Houston, TX) (1984).

GEOLOGY

Type of ore body	Disseminated; stockwork.
Origin	Hydrothermal; oxidation.
Shape of ore body	Tabular.
Ore controls	Igneous; fracturing.
Mineralized zone average dimensions, m:	
Length	1,000.
Width	600.
Thickness	30.
Depth	75.
Mineral names	Malachite, chrysocolla, cuprite.
Host formation	Igneous intrusive.
Geologic age	Upper Cretaceous.
Rock relationships	Quartz monzonite, ore in fractures, gangue. Conglomerate, gangue.
Size	Medium.

DEVELOPMENT

Current status	Active-standby.
Type of operation	Surface.
Mining method	Bench (berm).
Year of discovery	<1869.
Discovery method	Ore in place.
Initial production	1897.
Last production	Possibly 1981.
Distance to water supply	<10 km.
Road requirement	<50 km.
Distance to power supply	On-site.
Mill status	Active, standby.
Milling method	Solvent extraction; electrowinning.
Process rate	5,170-t/a (18-t/d) output capacity.
Product type	Cathode quality copper.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Measured	948,000 tons	1.49% Cu; 0.027 tr oz/ton Au; 0.39 tr oz/ton Ag.	1978	707
2..Not reported in reference	3,066,000 tons (mill).	1.75% Cu (sulfide)	1968	606
	22,657,000 tons (leach).	0.41% Cu (oxide)	1968	606

REFERENCES

144, 220, 591, 606, 641, 648, 693, 705, 707, 708, 717, 742.

USGS quad maps	Winnemucca, 1:250,000 Antler Peak, 15'.
USBM sequence number	0320150003.
USGS MRDS number	M030001.
Mid number	2600220.

BATTLE MOUNTAIN COPPER CANYON—GOLD

Alternate names: Copper Canyon Mine
Ore body names: Northeast, Tomboy, Minnie, Fortitude

Commodities: Au, Ag (Cu formerly produced from adjacent pit)

LOCATION-OWNERSHIP

County	Lander.	General location	About 20 km southwest of Battle Mountain.
Mining district	Battle Mountain		
Elevation	1,700 m.	Meridian	Mount Diablo.
Topography	Rugged.	Tract	Sec. 34, T 31 N, R 43 E.
Domain	Private; public-BLM administered.	Latitude	40°31'12" N.
		Longitude	117°07'13" W.

Owner-operator ..... Duval Corp., Tucson, AZ (subsidiary of Pennzoil Co., Houston, TX) (1984).

GEOLOGY

Type of ore body	Stockwork (Fortitude ore body).	Host formation	Battle.
Origin	Contact metasomatic, replacement.	Geologic age	Pennsylvanian.
Shape of ore body	Tabular.	Rock relationships	Unavailable.
Ore controls	Faults; fractures.	Alteration	Silicification.
Strike and dip of mineralized zone.	North: vertical.	Size	Medium.
Age of mineralization	Middle Tertiary (37 million yr).		
Mineralized zone average dimensions, m (estimated):			
Length	520.		
Width	340.		
Thickness	120.		
Depth	75.		
Mineral names	Free gold, silver, pyrrhotite, pyrite, "soluble" copper.		

DEVELOPMENT

Current status	Active-producer, development.	Distance to water supply	<3 km, wells in Reese Valley.
Type of operation	Surface.	Road requirement	Existing.
Mining method	Open pit.	Distance to power supply	Existing, 5 km.
		Mill location	On-site.
Year of discovery	1981 (announced—Fortitude).	Mill status	Active-producing, expansion.
Discovery method	Geologic inference, geochemical sampling; drilling.	Milling method	Gravity (20%)—tabled, amalgamated, retorted. Cyanide agitated tank leach (80%)—carbon-in-pulp, electrolysis, smelting.
Initial production	Dec. 1984 from Fortitude ore body.		
Annual production rate	Reported 1983 mill expansion will enable company to produce 4.7 t Au and 46.7 t Ag during 1985, when production from the Fortitude ore body comes on-stream; currently about 36,000 t/d ore produced.	Process rate	3,200 to 3,400 t/d (1982).
		Product type	Dore bullion bars, 95% to 96% Au-Ag.
		Destination	Engelhard Industries, Union City and Anaheim, CA.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
Minnie and Tomboy:				
1..Not reported in reference	3,900,000 tons	0.09 tr oz/ton Au; 0.28 tr oz/ton Ag	1981	164
Fortitude:				
1..Proven and probable	16,000,000 tons	0.15 tr oz/ton Au; 0.57 tr oz/ton Ag	1981	164
2..Not reported in reference	14,500,000	4.8 g/t Au; 18 g/t Ag	1983	435
3.. Do	15,000,000 tons	2,400,000 tr oz Au; 9,200,000 tr oz Ag	1984	400

REFERENCES

13, 33, 34, 35, 54, 55, 56, 57, 88, 89, 90, 141, 142, 143, 144, 149, 151, 164, 224, 317, 328, 378, 381, 391, 412, 434, 435, 437, 438, 465, 484, 500, 558, 588, 590, 591, 605, 606, 608, 641, 693, 706, 707, 709, 711, 712, 742, 817, 818, 820, 825, 838.

USGS quad maps	Winnemucca, 1:250,000. Antler Peak, 15'.
USBM sequence number	0320150631.
Mid number	260550.

Comments: Production began in 1967 as a copper property. Operations shifted about 1978 to adjacent gold-silver ore bodies when copper prices declined and precious metal prices climbed. The existing flotation mill was converted to precious metal recovery. Of 4 separate gold ore bodies, the Minnie and Tomboy were mined initially and are essentially depleted. The Fortitude ore body, described above, is the largest with development completed in 1984. The mill expansion to handle Fortitude ore will enable Duval to produce 4.7 t (150,000 tr oz) Au and 46.7 t (1.5 million tr oz) Ag during 1985 (*434*).

BEAR—COPPER

Alternate names: None

Commodities: Cu, Mo, Au, Ag

LOCATION-OWNERSHIP

County ..... Lyon.
Mining district ..... Mason Valley.
Elevation ..... 1,329 m.
Domain ..... Private.

General location ..... About 54 km southeast of Carson City.
Meridian ..... Mount Diablo.
Tract ..... Sec. 4, T 13 N, R 25 E.
Latitude ..... 39°00'47" N.
Longitude ..... 119°11'24" W.

Owner ..... The Anaconda Minerals Co., Denver, CO (subsidiary of Atlantic Richfield Co., Denver, CO) (1984).

GEOLOGY

Type of ore body ..... Replacement; disseminated.
Origin ..... Hydrothermal; oxidation.
Shape of ore body ..... Unknown.
Ore controls ..... Igneous; contact zone; faulting.
Mineral names ..... Chalcopyrite, pyrite, bornite, molybdenite.

Host formation ..... Porphyry dikes.
Geologic age ..... Tertiary.
Rock relationships ..... Quartz monzonite, encloses ore, gangue. Granodiorite, near ore.
Size ..... Large.

DEVELOPMENT

Current status ..... Inactive-explored prospect.
Type of operation ..... Prospect.

Year of discovery ..... 1961.
Discovery method ..... Auxiliary mineral in place.

Distance to water supply ... <10 km.
Road requirement ..... <10 km.
Distance to power supply ... <10 km.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	500,000,000 tons	0.40% Cu	1979	829

REFERENCES

453, 695, 822, 829.

USGS quad maps ..... Reno, 1:250,000. Wabuska, 15'.
USBM sequence number ..... 0320190171.

Comments: The deposit does not outcrop and is deeply buried.

BELL MOUNTAIN—GOLD

Alternate names: None

Commodities: Au, Ag

LOCATION-OWNERSHIP

County	Churchill.	General location	About 60 km southeast of Fallon.
Mining district	Fairview.	Meridian	Mount Diablo.
Elevation	1,810 m.	Tract	Sec. 10, T 15 N, R 34 E.
Topography	Hilly.	Latitude	39°10′45″ N.
Domain	Private.	Longitude	118°07′59″ W.

Owner: Nevada Silver, Inc. (subsidiary of American Pyramid Resources, Inc., Vancouver, BC, Canada), 100% (1982).

Owner-operator: Southern Pacific Land Co. (if option agreement met in 1984, will own 66.6% of the property and will become the operator) (1984).

GEOLOGY

Type of ore body	Vein; brecciated, sheared.	Host formation	Undifferentiated volcanics.
Origin	Hydrothermal.	Geologic age	Tertiary (Miocene).
Shape of ore body	Tabular.	Rock relationships	Rhyolite pyroclastics, encloses ore (vein).
Ore controls	Fracturing; faulting.		Tuff, air fall, encloses ore (vein).
Strike and dip of mineralized zone.	N 90° W; 45° S (Main Vein).		Basalt dikes, near ore.
Mineralized zone average dimensions, m:			Calcite-quartz vein, contains ore.
Length	>1,600 (reserves developed on 300 m).	Alteration	Broad silicification, chloritization, and argillization with seritization close to walls of vein; oxidation.
Width	>115 (downdip).	Size	Small.
Thickness	10 to 18.		

Mineral names: Possible electrum and argentite, native silver, cerargyrite, possible acanthite, yellow-gray chlorides, manganiferous calcite, ocherous limonite, quartz, adularia, barite, fluorspar, rhodochrosite, montmorillonite.

DEVELOPMENT

Current status	Active-development; exploration.	Distance to water supply	12 km pipeline from well at Stingaree Flat.
Type of operation	Surface.	Road requirement	12 km to U.S. Highway 50.
Mining method	Open-pit; on 5-m benches.	Distance to power supply	On-site caterpillar diesels.
Year of discovery	Unavailable.	Mill location	On-site.
Discovery method	Unvailable.	Mill status	Development.
Initial production	1927.	Milling method	Tank cyanidation (CCD); zinc precipitation, smelting.
Past production	35 t ore; 17 g/t (0.5 tr oz/ton) Au; 562 g/t (16.4 tr oz/ton) Ag.	Process rate	650 t/d (1982 preliminary).
Annual production rate	Anticipate 1.43 t Au; 37.5 t Ag (recovery from proven reserves).	Product type	Dore bullion (Ag-Au 30:1).

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven	1,000,000 t	1.5 g/t Au; 50 g/t Ag (Main Vein)	1982	40
2..Not reported in reference	1,500,000 to 2,000,000 t.	4.2 g/t Au; 100 g/t Ag (Zphinz Zone); grade based on assay of first crosscut.	1982	71
3..Proven	1,000,000 tons	0.055 tr oz/ton Au; 1.4 tr oz/ton Ag	1984	208
Probable	1,000,000 tons	0.022 tr oz/ton Au; 1.0 tr oz/ton Ag	1984	208
Possible	500,000 tons	0.14 tr oz/ton Au; 3.3 tr oz/ton Ag (Zphinz Zone)	1984	208

REFERENCES

40, 71, 84, 208, 224, 802.

USGS quad maps	Reno, 1:250,000. Bell Canyon, 7.5′.
USBM sequence number	0320010050.
Mid number	2601775.

Comments: Sulfides and sulfosalts have been completely leached from the vein. Original ore minerals were electrum and argentite. Zphinz Zone was discovered as a cross structure of Main Vein in about 1982. Large reserves of low-grade 'ore' reported as extensions of Main Vein. Recent discovery of ore in the Zphinz Zone could alter original development plans.

BIG LEDGE—BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.	General location	About 53 km northwest of Wells.
Mining district	Snake Mountains.	Meridian	Mount Diablo.
Elevation	2,440 m.	Tract	Sec. 27, T 42 N, R 61 E.
Topography	Rugged.	Latitude	41°29'57" N.
Domain	Mixed; private leases and unpatented claims on public lands administered by BLM.	Longitude	115°03'02" W.
Owner	Mary's River Ranch (1983).		
Operator	Chromalloy American Corp., St. Louis, MO (1983).		

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Valmy.
Origin	Sedimentation; hydrothermal.	Geologic age	Ordovician,
Shape of ore body	Tabular; irregular.	Rock relationships	Chert, lies along ore, encloses ore.
Ore controls	Bedding; lithology.		Shale, lies along ore, encloses ore.
Strike and dip of mineralized zone.	N 15° to 45° E: 30° to 45° NW.	Size	Medium.
Mineralized zone average dimensions, m:			
Length	380.		
Width	105.		
Thickness	30.		
Depth	0.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-explored.	Distance to water supply	Unknown.
Type of operation	Possible surface.	Road requirement	<50 km.
		Distance to power supply	<50 km.
Year of discovery	1978.	Mill location	No mill.
Discovery method	Ore mineral in place.		
Initial production	No production.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

77, 95, 123, 205, 226, 278, 546, 669, 716, 775, 778.

USGS quad maps	Wells, 1:250,000.
	Black Butte NE, 7.5'.
USBM sequence number	0320070904.

BISONI—FLUORINE

Alternate names: Bisoni Fluorite, Fish Creek

Commodities: CaF_2, Zn, Be

LOCATION-OWNERSHIP

County	Eureka.	General location	About 15 km southwest of Eureka.
Mining district	Fish Creek.	Meridian	Mount Diablo.
Elevation	2,316 m.	Tract	Sec. 23, T 18 N, R 52 E.
Topography	Hilly.	Latitude	39°25'12" N.
Domain	BLM administered.	Longitude	116°05'17" W.

Owner: Maynard and Lester Bisoni (1984).

GEOLOGY

Type of ore body	Disseminated; replacement; fissure vein.	Host formation	Antelope Valley Limestone.
Origin	Hydrothermal.	Geologic age	Middle Ordovician.
Shape of ore body	Tabular; massive.	Rock relationships	Limestone, ore in fractures.
Ore controls	Lithology; bedding.		Limestone, encloses ore.
Strike and dip of mineralized zone.	N 45° W: 5° S.	Size	Large.
Mineralized zone average dimensions, m:			
Length	1,200.		
Width	790.		
Thickness	98.		
Depth	34.		

Mineral names: Fluorite, quartz, calcite, limonite, sphalerite, beryl, hematite, muscovite, scheelite, molybdenite, sericite.

DEVELOPMENT

Current status	Inactive-explored prospect.	Distance to water supply	<10 km.
		Road requirement	<50 km.
Year of discovery	1960.	Distance to power supply	<50 km.
Discovery method	Ore mineral in place.		

Initial production: No production.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

275, 281, 545, 593.

USGS quad maps	Millet, 1:250,000.
	Bellevue Peak, 15'.
USBM sequence number	0320110195.

BLOODY CANYON—ANTIMONY

Alternate names: Red Star, Hutton

Commodities: Sb, Ag

LOCATION-OWNERSHIP

County	Pershing.	General location	About 15 km south of Imlay.
Mining district	Star.	Meridian	Mount Diablo.
Elevation	1,975 m.	Tract	Sec. 35, T 31 N, R 34 E.
Topography	Rugged.	Latitude	40°31'02" N.
Domain	Mixed.	Longitude	118°08'08" W.

Owner: Hybert L. Neal (1960).
Operator: Metro-dyne International, Inc., Oreana, NV (1970).

GEOLOGY

Type of ore body	Fissure vein.	Host formation	Koipato.
Origin	Hydrothermal.	Geologic age	Triassic.
Shape of ore body	Tabular.	Rock relationships	Rhyolite, encloses ore.
Ore controls	Faulting; fracturing.		Limestone, near ore.
Strike and dip of mineralized zone:		Size	Small.
West Vein	N 10° W: 80° to 85° E.		
East Vein	N 10° to 25° E: 80° to 85° E.		
Mineralized vein average dimensions, m:			
Length	100.		
Width	60.		
Thickness	1.		
Depth	0.		
Mineral names	Stibnite, pyrite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	On-site.
Type of operation	Underground.	Road requirement	None.
		Distance to power supply	<50 km.
Year of discovery	1868.		
Discovery method	Ore mineral in place.		
Initial production	1907.		
Last production	1942.		
Past production	100 t metal (*376*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

74, 329, 376.

USGS quad maps	Lovelock, 1:250,000.
	Imlay, 15'.
USBM sequence number	0320270294.
USGS MRDS number	M060338.

Comments: The Bloody Canyon is reported to be second only to the Sutherland Mine in antimony production; principal periods of production were in 1907 and 1917–21.

BLUE STAR—GOLD

Alternate names: Number 8, South Pit, East Pit, North Pit

Commodities: Au, turquoise

LOCATION-OWNERSHIP

County	Eureka.	General location	About 43 km northwest of Carlin.
Mining district	Lynn.	Meridian	Mount Diablo.
Elevation	1,830 m.	Tract	Sec. 4, T 35 N, R 50 E.
Topography	Hilly.	Latitude	40°56'35" N.
Domain	Private.	Longitude	116°21'38" W.

Owner-operator ..... Carlin Gold Mining Co., Carlin, NV (subsidiary of Newmont Mining Corp., New York, NY) (1984).

GEOLOGY

Type of ore body	Disseminated.
Origin	Hydrothermal.
Shape of ore body	Irregular in plan.
Ore controls	Faulting; fracturing; lithology.
Strike and dip of mineralized zone.	Northwest: unknown.
Age of mineralization	Miocene (37.5 million yr).
Mineralized zone average dimensions, m:	
Length	365.
Width	200.
Thickness	90.
Mineral names	Quartz, clays, sericite, kaolinite, calcite, barite, pyrite, realgar, orpiment, stibnite, cinnabar, native gold, turquoise, chrysocolla, malachite, euchroite, montmorillonite, sphalerite.
Host formation	Vinini (in upper plate of Roberts Mountains Thrust Fault).
Geologic age	Ordovician.
Rock relationships	Sandy siltstone, ore in fractures, gangue, most favored host. Cherty shale, adjacent to ore. Quartzite sandstone, contains some ore. Limestone, dolomitic limestone, sandy calcareous siltstone, beneath ore. Dacite porphyry dikes, near ore. Quartz diorite plug, about 3 km north. Jasperoid, near ore.
Alteration	Silicification, sericitic kaolinitic
Size	Small.

DEVELOPMENT

Current status	Active-producer (intermittent).
Type of operation	Surface.
Mining method	Open pit; bench. Mining by Carlin Gold Mining Co. began in 1974 and consists of 3 pits.
Year of discovery	1959 (first claimed for turquoise in 1929).
Discovery method	Unknown.
Initial production	1975.
Last production	Ongoing 1983.
Past production	About 124 kg (4,000 tr oz) in 1980 (*132*).
Road requirement	8-km access road to Carlin Mine built in 1974.
Mill location	Mill grade trucked 8 km to Carlin mill.
Mill status	Active.
Milling method	Agitated cyanide leach, CCD; oxidation-chlorination pretreatment for carbonaceous ore; CCD wash; Merrill-Crowe zinc precipitation, smelting.
Product type	Dore bars, weighing about 34 kg.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference[1]	1,800,000 tons	0.12 tr oz/ton Au	1974	517

REFERENCES

59, 61, 90, 132, 182, 183, 319, 398, 458, 505, 517, 570, 593, 616.

USGS quad maps	Winnemucca, 1:250,000. Rodeo Creek NE, 7.5'.
USBM sequence number	0320110166.
Mid number	2600500.

Comments: This property was initially developed for its high-quality turquoise. In 1968, Newmont Mining Corp. acquired property and subsequent drilling defined 3 ore bodies (South, East, North) with reserves described above.

[1]Resource referred to as reserves.

BOOTSTRAP—GOLD

Alternate names: Bootstrap Mine Dump

Commodities: Au

LOCATION-OWNERSHIP

County	Elko.	General location	About 56 km northwest of Carlin.
Mining district	Bootstrap.	Meridian	Mount Diablo.
Elevation	1,750 m.	Tract	Sec. 10, T 36 N, R 49 E.
Topography	Rolling hills.	Latitude	41°01′08″ N.
Domain	Private.	Longitude	116°24′58″ W.

Owner-operator ..... Carlin Gold Mining Co., Carlin, NV (subsidiary of Newmont Mining Corp., New York, NY) (1984).

GEOLOGY

Type of ore body	Disseminiated.	Host formation	Vinini (upper plate of Roberts Mountains Thrust Fault).
Origin	Hydrothermal.		
Shape of ore body	Tabular.	Geologic age	Ordovician.
Ore controls	Faulting, fracturing, lithology.	Rock relationships	Brecciated limestone, contains ore in fractures.
Strike of mineralized zone.	N 70° E.		Siltstone, contains ore in fractures.
Mineralized zone average dimensions, m (estimated):			Porphyry dikes, contains ore in fractures.
			Jasperoid, jasperoid breccia, near ore.
Length	400.		
Width	180.	Alteration	Argillic, silicification.
Mineral names	Undetermined.	Size	Small.

DEVELOPMENT

Current status	Active, producing.	Distance to water supply	On-site wells.
Type of operation	Surface, low-grade dump leach.	Road requirement	Existing, 19-km access road built to Carlin Mine.
Mining method	Open pit (inactive-ore body depleted). Mining began by Carlin Mining Co. in 1973.	Distance to power supply	On-site diesel electric generation.
		Mill location	On-site.
		Mill status	Active.
Year of discovery	About 1940; Newmont made additional discoveries in early 1970's.	Milling method	Dump cyanide heap leach, carbon adsorption.
Discovery method	Surface sampling, drilling.	Process rate	200,000 t/a ore, at 54% Au recovery.
		Product type	Gold-loaded carbon in drums.
Initial production	Late 1950's or early 1960's; Carlin in 1975. Present dump leach began in 1979.	Distance shipped	19 km.
		Destination	Carlin mill at Carlin Mine for further processing by caustic-cyanide solution, strip solution, electrowinning on steel wool and smelted to dore products.
Last production	From open pit in 1978. Leach dump to produce until end of 1985 or 1986.		
Past production	104.5 kg Au (1983) (*511*). About 820,000 t, 0.86 g/t Au ore has been treated into mid-1984.		
Annual production rate	About 200 kg Au at peak, less currently.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	2,100,000 tons	About 0.15 tr oz/ton Au (includes Carlin's Blue Star Mine 1974 unmined reserves).	1974	510
2..Proven	<1,000,000 tons	0.044 tr oz/ton Au (0.028 to 0.063 tr oz/ton; low-grade material stockpiled from previous mining operation).	1979	378

REFERENCES

83, 186, 226, 319, 378, 398, 412, 505, 506, 510, 511, 589, 616, 669.

USGS quad maps	McDermitt, 1:250,000. Santa Renia Field, 7.5′.
USBM sequence number	0320070349.
Mid number	2600501.

Comments: About 800,000 t of low-grade material containing 0.96 g/t was stockpiled for leaching from previous mining. Heap leaching of this material continues after construction of dump leach facility in 1978.

BOREALIS—GOLD

Alternate names: Jamies Ridge,[1] East Ridge Project

Commodities: Au, Ag, Hg (byproduct mercury)

LOCATION-OWNERSHIP

County	Mineral.	General location	About 24 km southwest of Hawthorne.
Mining district	Aurora.	Meridian	Mount Diablo.
Elevation	2,195 m.	Tract	Sec. 17, T 6 N, R 29 E.
Topography	Hilly.	Latitude	38°22′57″ N.
Domain	National forest.	Longitude	118°45′36″ W.

Owner: Houston International Minerals Corp. (HIMCO), Denver, CO (subsidiary of Tenneco, Inc.) (1983).
Operator: W. E. Vining Co. (contractor), Carson City, NV (1983).

GEOLOGY

Type of ore body	Breccia fill; stratiform; disseminated.	Host formation	Esmeralda, Volcanics.
Origin	Hydrothermal.	Geologic age	Miocene.
Shape of ore body	Lenticular (flattened football).	Rock relationships	Silicified andesite breccia, is ore.
Ore controls	Faults; lithology; fractures; hot springs vents.		Sponge rock (altered tuff), is ore.
Strike and dip of mineralized zone.	N 55°E: relatively flat.		Andesite flows and breccia, lies under ore.
Age of mineralization	5 to 12 million yr, possibly Pliocene.		Andesite and ash flow tuff, lies along ore.
Mineralized zone average dimensions, m:		Alteration	Potassic, silicification, oxidation (ore zone), argillic, kaolin, propylitic (country rock).
Length	370.	Size	Small.
Width	152.		
Thickness	60.		
Mineral names	Quartz, hematite, montmorillonite, chlorite, calcite, pyrite, barite, kaolinite, alunite.		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	5 km (wells to plan site tanks).
Type of operation	Surface.	Road requirement	0.5 km new plant access.
Mining method	Open-pit.	Distance to power supply	11 km.
		Mill location	On-site.
Year of discovery	1977 (HIMCO began exploration).	Mill status	Active.
Discovery method	Geochemical anomaly.	Milling method	Agglomeration, cyanide heap leaching, Merrill-Crowe zinc precipitation.
Initial production	1981.		
Last production	Ongoing.	Process rate	Crusher, 2,270 t/d.
Annual production rate	About 544,000 t ore planned, about 934 kg combined Au and Ag, about 870 kg (28,000 tr oz) Au.	Process type	34-kg dore buttons.
		Destination	By air to Reno, NV, then shipped to Handy & Harmon, Attleboro, MA.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Identified	2,500,000 to 3,000,000 tons.	0.08 tr oz/ton Au; 0.62 tr oz/ton Ag	1981	383

REFERENCES

73, 196, 209, 228, 287, 356, 378, 380, 383, 485, 488, 512, 598, 651, 688, 696, 766.

USGS quad maps	Walker Lake, 1:250,000. Aurora 15′.
USBM sequence number	0320210463.
Mid number	2601655.

[1]Jamies Ridge is another discrete ore body discovered in 1982, 6 km northeast of Borealis deposit. This 250-m by 100-m by 30-m-thick deposit was placed in production in April 1983 for about 7 months of mining to depletion. Production: first exploited in 1906 and again in the late 1950's; no records available.

BOULDER CITY-MANGANESE

Alternate names: None

Commodities: Mn

LOCATION-OWNERSHIP

County	Clark.
Mining district	Las Vegas.
Elevation	671 m.
Topography	Rolling.
Domain	Municipality.
Owner	City of Boulder City, NV (1980).
General location	About 39 km southeast of Las Vegas.
Meridian	Mount Diablo.
Tract	Sec. 23, T 23 S, R 64 E.
Latitude	35°56'45" N.
Longitude	114°47'23" W.

GEOLOGY

Type of ore body	Sedimentary.
Origin	Hydrothermal; sedimentation.
Shape of ore body	Tabular.
Ore controls	Bedding; lithology.
Strike and dip of mineralized zone.	East-west: 4° S.
Mineralized zone average dimensions, m:	
Length	1,158.
Width	716.
Thickness	18.
Depth	7.
Mineral names	Wad.
Host formation	Muddy Creek.
Geologic age	Miocene.
Rock relationships	Gypsiferous sandstone, encloses ore, lies over and under ore. Tuff, lies over and under ore. Gravel, lies over ore.
Size	Medium.

DEVELOPMENT

Current status	Inactive-explored.
Type of operation	Possible surface.
Year of discovery	1941.
Discovery method	Ore mineral in place.
Initial production	No production.
Distance to water supply	<10 km.
Road requirement	None.
Distance to power supply	<10 km.
Mill location	No mill.

PUBLISHED RESERVES-RESOURCES[1]

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Indicated	1,000,000 tons	Average: 7.5% Mn; cutoff: 5% Mn	1949	407
2.. Do	3,000,000 tons	Average: 4.5% Mn; cutoff: 3% Mn	1949	407
3.. Do	6,000,000 tons	Average: 4.0% Mn; cutoff: 2% Mn	1949	407
4.. Do	15,000,000 tons	Average: 3.0% Mn; cutoff: 1% Mn	1949	407

REFERENCES

36, 41, 267, 354, 386, 407, 547, 721, 733, 844.

USGS quad maps	Kingman, 1:250,000. Boulder City, 7.5'.
USBM sequence number	0320030322.

[1]Tonnages are cumulative and rounded to nearest million.

BRAY-BEULAH—ANTIMONY

Alternate names: Beulah, Genesee, Aberasturi

Commodities: Sb, Ag

LOCATION-OWNERSHIP

County	Lander.	General location	About 22 km south of Austin.
Mining district	Big Creek.	Meridian	Mount Diablo.
Elevation	2,804 m.	Tract	Sec. 27, T 17 N, R 43 E.
Topography	Rugged.	Latitude	39°18′26″ N.
Domain	Private.	Longitude	117°07′52″ W.

Owner: Mary J. Bray (Beulah Claim), James O. Holmes (Genesee Claim) (1963).

GEOLOGY

Type of ore body	Fissure vein.	Host formation	Valmy.
Origin	Hydrothermal.	Geologic age	Ordovician.
Shape of ore body	Tabular.	Rock relationship	Siliceous slate, encloses ore.
Ore controls	Faulting.	Size	Small.
Strike and dip of mineralized zone.	N 30° W: 45° to 85° SW.		
Mineralized zone average dimensions, m:			
Thickness	1.		
Mineral names	Stibnite, pyrite, graphite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	<10 km.
Type of operation	Underground.	Road requirement	<50 km.
		Distance to power supply	<50 km.
Year of discovery	1864.		
Discovery method	Ore mineral in place.		
Initial production	1891.		
Past production	>908 t Sb metal (*376*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

376, 693.

USGS quad maps	Millett, 1:250,000. Austin, 15′.
USBM sequence number	0320150192.

Comments: The Bray-Beulah is reported to be the third largest antimony producer in Nevada.

BUCKHORN—GOLD

Associated names: Barbi Lake Copper Mines, North Buckhorn, South Buckhorn, North Aspen, South Aspen

Commodities: Au, Ag (Au-Ag ratio = 1:15)

LOCATION-OWNERSHIP

County	Eureka.
Mining district	Buckhorn.
Elevation	2,100 m.
Topography	Hilly.
Domain	Private.
General location	About 90 km southwest of Carlin.
Meridian	Mount Diablo.
Tract	Secs. 30, 31, T 27 N, R 49 E.
Latitude	40°10′53″ N.
Longitude	116°29′33″ W.

Owner: Cominco American, Inc., Spokane, WA (76%), and Pembina International Corp., Calgary, AB, Canada, combined will manage the operation. Pembina, as a minority partner, will put up a share of the development money for an identical profit sharing percentage (1984).

GEOLOGY

Type of ore body	Breccia (fault); vein.
Origin	Hydrothermal; oxidation.
Shape of ore body	Irregular; pods.
Ore controls	Faulting; igneous; lithology (breccia).
Age of mineralization	Pliocene (14.6 million yr).
Pit average dimensions, m (estimated):	

	North Buckhorn	South Buckhorn
Length	400	360
Width	340	230

Mineral names	Native gold and silver, pyrite (argentiferous and auriferous), limonite, marcasite, adularia, kaolinite, montmorillonite.
Host formation	Undifferentiated basaltic andesite flows.
Geologic age	Pliocene
Rock relationships	Shale and siltstone, encloses ore. Basaltic andesitic flows, lies above ore. Gravels and conglomerates, lies beneath ore (Tertiary). Breccia, silicified, in places is ore.
Alteration	Argillic, kaolinization.
Size	Small.

DEVELOPMENT

Current status	Active-producing.
Type of operation	Surface.
Mining method	Open pit; about 1,191,000 t/a ore (1,034,000 t waste and subgrade) over 4 yr.
Year of discovery	1908.
Discovery method	Surface prospecting.
Initial production	Early 1984 (for Cominco).
Past production	Operations through 1950 yielded about 1,200 kg Au and 10,000 kg Ag; mining and milling beginning in 1979 yielded about 470 kg/a Au (*132*).
Annual production rate	Producing about 934 kg Au and 8,400 kg Ag.
Distance to water supply	On-site, <1 km.
Road requirement	None.
Distance to power supply	Unavailable.
Mill location	On-site.
Mill status	Development.
Milling method	Agglomeration, cyanide heap leach, Merrill-Crowe zinc precipitation, smelting.
Process rate	680,000 t/a; crusher, 259 t/h (285 ton/h).
Product type	Probably dore.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	5,000,000 tons	0.044 tr oz/ton Au; 0.583 tr oz/ton Ag	1983	769

REFERENCES

132, 135, 452, 593, 594, 675, 769, 779, 780, 781, 782, 784, 787, 833.

USGS quad maps	Winnemucca, 1:250,000. Horse Creek Valley, 15′.
USBM sequence number	0320110167.
USGS MRDS number	W016362.
Mid number	2600785.

Comments: Buckhorn Mine consists of at least 2 ore bodies. Current plans are to operate 2 separate open pits, the North Buckhorn and the South Buckhorn. Ore occurs within 60 m of surface. Ore is within oxide and sulfide zones. Company projected mine life from 1984 is 4 yr; mill, 7 yr.

BUCKINGHAM—MOLYBDENUM

Alternate names: AMAX Molybdenum Deposit, Rocky Mountain Energy Moly Deposit

Commodities: Mo, Ag, Cu, W

LOCATION-OWNERSHIP

County	Lander.	General location	About 11 km southwest of Battle Mountain.
Mining district	Battle Mountain.		
Elevation	1,798 m.	Meridian	Mount Diablo.
Topography	Rugged.	Tract	Sec. 30, T 32 N, R 44 E.
Domain	Mixed; private and BLM administered	Latitude	40°36'56" N.
		Longitude	117°03'42" W

Owner..... AMAX, Inc., Denver, CO (33%); Rocky Mountain Energy Co., Broomfield, CO (Union Pacific Corp.) (1984).
Operator..... AMAX, Inc. (1984).

GEOLOGY

Type of ore body	Stockwork; disseminated.	Host formation	Widely varying lithologies.
Origin	Hydrothermal; contact metasomatic.	Geologic age	Cambrian; Tertiary.
Shape of ore body	Massive; irregular.	Size	Large.
Ore controls	Igneous; fracturing.		
Mineralized zone average dimensions, m:			
Length	2,000.		
Width	1,200.		
Thickness	640.		
Mineral names	Pyrite, molybdenite, pyrrhotite, chalcopyrite, sphalerite, galena, arsenopyrite, bismuthinite, freibergite, tetrahedrite, quartz, scheelite.		

DEVELOPMENT

Current status	Active-explored prospect.	Distance to water supply	Undetermined.
Type of operation	Prospect.	Road requirement	Undetermined.
		Distance to power supply	Undetermined.
Year of discovery	Undetermined.		
Discovery method	Ore mineral in place.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	907,000,000 tons	0.06% Mo	1982	701

REFERENCES

56, 381, 588, 590, 591, 592, 605, 606, 610, 693, 701, 706, 712, 717, 742, 794, 803, 813, 837.

USGS quad maps ..... Winnemucca, 1:250,000.
Antler Peak, 15'.
USBM sequence number ..... 0320150108.

Comments: Ore largely in fractures in hornfels and quartzites of the Harmony Formation (Cambrian).

BUENA VISTA—IRON

Alternate names: None

Commodities: Fe

LOCATION-OWNERSHIP

County ..... Churchill.
Mining district ..... Mineral Basin.
Elevation ..... 1,341 m.
Topography ..... Hilly.
Domain ..... Private.

General location ..... About 36 km southwest of Lovelock.
Meridian ..... Mount Diablo.
Tract ..... Sec. 4, T 24 N, R 34 E.
Latitude ..... 39°58'25" N.
Longitude ..... 118°09'55" W.

Owner-operator ..... Southern Pacific Co., San Francisco, CA; U.S. Steel Corp., Salt Lake City, UT (1975).

GEOLOGY

Type of ore body ..... Replacement, breccia fill, disseminated.
Origin ..... Contact metasomatic.
Shape of ore body ..... Tabular, irregular, pipelike.
Ore controls ..... Igneous, faulting.
Mineralized zone average dimensions, m:
  Length ..... 3,353.
  Width ..... 914.
  Thickness ..... 137.
Mineral names ..... Magnetite, hematite, scapolite, chlorite, calcite, quartz, apatite, sphene, hornblende.

Host formation ..... Leach.
Geologic age ..... Pennsylvanian.
Rock relationships ..... Lamprophyre, lies along ore, near ore.
Size ..... Medium.

DEVELOPMENT

Current status ..... Inactive-past producer.
Type of operation ..... Surface.

Discovery method ..... Ore mineral in place.

Initial production ..... 1952.
Last production ..... 1960.

Distance to water supply ... <10 km.
Road requirement ..... None.
Distance to power supply ... <50 km.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Measured[1]	18,000,000 long tons.	32.7% Fe	1971	454
2..Indicated[1]	3,000,000 long tons.	33.3% Fe	1971	454
3..Measured[2]	5,000,000 long tons.	26.2% Fe	1971	454
4..Indicated[2]	900,000 long tons.	22.1% Fe	1971	454
5..Inferred[2]	5,700,000 long tons.	22.1% Fe	1971	454
6..Measured[3]	5,500,000 long tons.	25.5% Fe	1971	454
7..Indicated[3]	2,400,000 long tons.	25.5% Fe	1971	454
8..Inferred[3]	4,700,000 long tons.	25.5% Fe	1971	454

REFERENCES

10, 75, 150, 282, 324, 332, 367, 454, 515, 536, 568, 579, 583, 733, 751, 802, 841.

USGS quad maps ..... Reno, 1:250,000.
Dixie Hot Springs, 15'.
USBM sequence number ..... 0320010043.

[1]West ore body.
[2]South Central ore body.
[3]East ore body.

BUILLION MONARCH—GOLD

Alternate names: Polar Resources Pit

Commodities: Au, Ag

LOCATION-OWNERSHIP

County	Eureka.	General location	About 30 km northwest of Carlin.
Mining district	Lynn.	Meridian	Mount Diablo.
Elevation	1,770 m.	Tract	Sec. 10, T 35 N, R 50 E.
Topography	Hilly.	Latitude	40°55′03″ N.
Domain	BLM administered.	Longitude	116°20′37″ W.

Owner-operator ..... Universal Gas (Montana), Inc., Elko, NV (1984).

GEOLOGY

Type of ore body	Vein (fault zone); disseminated.	Host rocks	Roberts Mountains and Volcanics.
Origin	Hydrothermal.	Geologic age	Devonian (Roberts Mountains), Tertiary (Volcanics).
Shape of ore body	Podlike (along fault zone).		
Ore controls	Faulting; fracturing.	Rock relationships	Fault gouge, contains ore, is ore.
Strike and dip of mineralized zone.	N 50° W: steeply northeast.		Limestone, lies under ore (footwall).
			Volcanics, lies above ore (hanging wall).
Age of mineralization	Miocene.		
Mineralized zone average dimensions, m:			Jasperoid, near ore.
		Alteration	Silicification (gold zone), argillic (carbonate wall rock).
Length	270.		
Width	Unknown.	Size	Small.
Pit depth	6 (estimated 1982).		
Mineral names	Quartz, iron oxides, clays.		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	On-site, developed.
Type of operation	Surface.	Road requirement	Developed to site.
Mining method	Conventional open pit.	Mill location	On-site.
		Mill status	Active.
Past production	More than 90,000 t ore produced by 1981 (*728*).	Milling method	Carbon-in-pulp cyanide.
		Process rate	180 t/d (peak load 360 t/d).

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information; however, published grade is 0.2 tr oz/ton Au (see comments) (*690*).

REFERENCES

182, 183, 593, 690, 728.

USGS quad maps	Winnemucca, 1:250,000. Rodeo Creek NE, 7.5′.
USBM sequence number	0320110214.
Mid number	2601343.

Comments: Average grade ranges from 7.5 to 56.6 g/t Au; highest grade reaching 240 to 270 g/t Au.

C-M ALUNITE—ALUMINUM

Alternate names: Clover Mountains

Commodities: Al, K_2SO_4, S

LOCATION-OWNERSHIP

County	Lincoln.	General location	About 43 km southeast of Caliente.
Mining district	Unorganized.	Meridian	Mount Diablo.
Elevation	1,610 m.	Tract	Sec. 10, T 7 S, R 70 E (unsurveyed).
Topography	Rolling.	Latitude	37°21'19" N.
Domain	BLM administered.	Longitude	114°10'05" W.
Owner	Earth Sciences, Inc., Golden, CO (1984).		

GEOLOGY

Type of ore body	Replacement.	Host formation	Volcanics.
Origin	Hydrothermal.	Geologic age	Tertiary.
Shape of ore body	Undetermined.	Rock relationships	Agglomerate, replaced by ore.
Ore controls	Igneous, lithology.		Tuff, replaced by ore.
Mineralized zone average dimensions, m:		Size	Medium.
Length	3,000.		
Width	3,000.		
Thickness	16.		
Depth	6.		
Mineral names	Alunite.		

DEVELOPMENT

Current status	Inactive-raw prospect.	Distance to water supply	<10 km.
Type of operation	Possible surface.	Road requirement	<10 km.
		Distance to power supply	<50 km.
Year of discovery	1971.	Mill location	No mill.
Discovery method	Ore mineral in place.		
Initial production	No production.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

239, 549, 724, 753.

USGS quad maps	Caliente, 1:250,000. Jack Mountain, 7.5'.
USBM sequence number	0320170001.

CALICO HILLS—IRON

Alternate names: Calico Deposit

Commodities: Fe, Cu

LOCATION-OWNERSHIP

County	Mineral.	General location	About 51 km south of Fallon.
Mining district	Unincorporated.	Meridian	Mount Diablo.
Elevation	1,390 m.	Tract	Sec. 5, T 13 N, R 29 E.
Topography	Gentle.	Latitude	39°01'03" N.
Domain	Indian reservation.	Longitude	118°45'54" W.
Owner	Undetermined.		

GEOLOGY

Type of ore body	Replacement, fissure vein.	Host formation	Possibly Luning.
Origin	Contact metasomatism.	Geologic age	Upper Triassic.
Shape of ore body	Unknown (possibly lenticular).	Rock names	Sandstone.
Ore controls	Contact zone, lithology, faulting.		Shale.
Mineralized zone average dimensions, m.	Unknown.		Limestone.
			Skarn (tactite).
Mineral names	Magnetite, pyrite, pyrrhotite, chalcopyrite, grossularite, actinolite, epidote, galena, sphalerite, molybdenite, tremolite.	Size	Large.

DEVELOPMENT

Current status	Unknown.	Distance to water supply	<50 km.
Type of operation	Prospect.	Road requirement	None.
		Distance to power supply	<50 km.
Year of discovery	1963.		
Discovery method	Geophysical anomaly.		
Initial production	None.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information. Moore reports (*454*) that the Calico Hills deposit contains a very large quantity of material averaging 20% Fe and 0.07% Cu, and that high-grade portions have an average grade of 44% Fe.

REFERENCES

454, 598, 740.

USGS quad maps	Reno, 1:250,000.
	Weber Reservoir, 15'.
USBM sequence number	0320210388.

CANDELARIA—SILVER

Alternate names: Candelaria Partners Mine and Plant
Pit names: Lucky Hill, Mt. Diablo, Northern Belle

Commodities: Ag, Au

LOCATION-OWNERSHIP

County	Mineral.	General location	About 80 km south of Hawthorne.
Mining district	Candelaria.	Meridian	Mount Diablo.
Elevation	1,731 m.	Tract	Sec. 3, T 3 N, R 35 E.
Topography	Hilly.	Latitude	38°09'32" N.
Domain	Mixed; private and BLM administered.	Longitude	118°05'11" W.

Owner-operator ..... NERCO Metals, Inc., Fairbanks, AK (subsidiary of Pacific Power & Light Co., Portland, OR) (1984).
Owner ..... CoCa Mines, Inc., Denver, CO (owns 37% limited partnerships) (1984).

GEOLOGY

Type of ore body	Disseminated, veins parallel to bedding.	Host formation	Candelaria.
Origin	Hydrothermal.	Geologic age	Triassic.
Shape of ore body	Tabular.	Rock relationships	Shale (tuffaceous), serpentinite, contains ore.
Ore controls	Fracturing.	Alteration	Silicification, dolomization.
Strike and dip of mineralized zone.	N 45° E: 40° to 60° N.	Size	Medium.
Age of mineralization	Early Cretaceous.		
Mineralized zone average dimensions, m:			
Length	1,230.		
Width	40.		
Thickness	130.		
Open pit depth	90 to 120.		

Mineral names ..... Limonite, jarosite, gold, jamesonite, pyrite, chalcopyrite (minor), galena (minor), clays, dolomite.

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	8 km to two 300-m wells.
Type of operation	Surface, heap leach.	Road requirement	About 10 km, county road improved.
Mining method	Open pit (2,400,000-t/a ore capacity; 32,600-t/d ore plus waste of which 9,300 t is recovered ore).	Distance to power supply	14 km, 69-kV power.
		Mill location	On-site.
		Mill status	Active.
		Milling method	Agglomeration, cyanide heap leach, Merrill-Crowe zinc dust precipitation.
Year of discovery	1863.		
Discovery method	Surface outcrop.		
		Mill feed capacity	7,300-t/d heap leach facility.
Initial production	August 1980 by Occidental; August 1983 by NERCO.	Product type	Dore bullion (34-kg buttons).
Last production	June 1982 by Occidental; ongoing production by NERCO.		
Past production	8,389 kg Ag (1980) (*165*). 52,100 kg Ag, >286 kg Au (1981) (*165*, *764*).		
Annual production rate	About 53,000 kg Ag (1.7 million tr oz) and 280 kg Au (9,000 tr oz) produced between April and September.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven	12 to 13,000,000 tons	3.15 tr oz/ton Ag and 0.002 tr oz/ton Au	1980	158
2..Not reported in reference	18,500,000 tons	1.09 tr oz/ton Ag (with gold byproduct)	1982	423

REFERENCES

48, 82, 83, 90, 92, 133, 158, 165, 197, 208, 300, 305, 378, 412, 423, 427, 436, 440, 491, 498, 540, 598, 599, 649, 655, 688, 691, 763, 764, 776, 777.

USGS quad maps ..... Walker Lake, 1:250,000.
Candelaria, 7.5'.
USBM sequence number ..... 0320210476.
Mid number ..... 2601511.

Comments: The Candelaria Mine is the largest open pit silver mine in the United States. NERCO plans 5,000-ton/d mine rate (1.6 million tr oz) Ag production. A deeper ore body of massive sulfide nature has been tentatively recognized.

CARLIN—GOLD

Ore body names: Carlin-West, Main, East

Commodities: Au, Ag, Hg (byproduct mercury)

LOCATION-OWNERSHIP

County	Eureka.	General location	About 32 km north of Carlin.
Mining district	Lynn.	Meridian	Mount Diablo.
Elevation	1,877 m.	Tract	Sec. 14, T 35 N, R 50 E.
Topography	Hilly.	Latitude	40°54′41″ N.
Domain	Mixed; private and BLM administered.	Longitude	116°19′13″ W.

Owner-operator ..... Carlin Gold Mining Co., Carlin, NV (subsidiary of Newmont Mining Corp., New York, NY) (1984).

GEOLOGY

Type of ore body	Disseminated, replacement stratiform.	Host formation	Upper Roberts Mountains.
Origin	Hydrothermal, oxidation.	Geologic age	Upper Silurian and Lower Devonian.
Shape of ore body	Tabular, irregular.	Rock relationships	Dolomitic siltstone, replaced by ore, ore in fractures, gangue.
Ore controls	Fractures (near attitude of host rocks), breccia zones, faults, lithology.		Silty dolomite, replaced by ore, ore in fractures, gangue.
Strike and dip of mineralized zone.	Northeast: 60° W.		Silty to sandy carbonaceous dolomitic limestone, in vicinity of ore (unmineralized, unaltered host formation).
Age of mineralization	Mid-Tertiary.		Feldspar porphyry dikes, in mine area, sometimes contains gold.
Mineralized zone average dimensions (estimated exposure at mine), m:		Alteration	Argillization, silicification, pyritization, decarbonatization.
Length	2,000.	Size	Medium.
Width	800.		
Thickness	100.		

Mineral names ..... Gold, pyrite, barite, iron oxides, arsenopyrite, realgar, stibnite, cinnabar, galena, calcite, kaolinite, quartz, sericite, ellisite, weissbergite, avicennite, lorandite.

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	4 km by pipeline from wells.
Type of operation	Surface.	Road requirement	32 km paved access road built.
Mining method	Open pit—6-m benches, 26,000 t/d ore and waste mined.	Distance to power supply	75 km from Battle Mountain area.
		Mill location	On-site.
		Mill status	Active.
Year of discovery	1962.	Milling method	Agitated cyanide leach, CCD; oxidation-chlorination pretreatment circuit for carbonaceous ores; Merrill-Crowe zinc precipitation.
Discovery method	Geological inference, surface mapping, geochemical sampling, drilling.		
Initial production	1965.	Process rate	2,000 t/d oxide ore, 450 t/d carbonaceous ore (Newmont's 1983 annual report—mill capacity of 2,495 t/d).
Last production	Ongoing 1983.		
Past production (includes production from Carlin, Bootstrap, Blue Star, and Maggie Creek pits).	94,700 kg (3,044,000 tr oz) Au (1965–79) (*61*).	Product type	Dore buttons (about 34-kg), about 95% Au; byproduct mercury.
	17,311 kg (556,559 tr oz) Au; includes 2,442 kg (78,523 tr oz) Au from heap leach (1980–83) (*511*).	Destination	Various refiners (Englehard, Handy & Harmon, et al).
Annual production rate	3,700 kg Au (Carlin mill only) (*511*).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	11,000,000 tons	0.32 tr oz/ton Au (original reserves, Carlin pit only, stripping ratio = 3:1).	1964	319, 398
2.. Do[1]	4,700,000 tons	0.164 tr oz/ton Au	1982	2
3..Proven and probable	4,497,000 tons	0.160 tr oz/ton Au (includes Blue Star)	1983	511

REFERENCES

2, 6, 27, 59, 61, 83, 90, 114, 115, 132, 182, 183, 230, 233, 234, 240, 245, 247, 248, 297, 319, 378, 398, 409, 410, 411, 435, 505, 511, 516, 562, 569, 571, 572, 573, 589, 593, 616, 692, 773.

USGS quad maps	Winnemucca, 1:250,000. Rodeo Creek NE, 7.5′.
USBM sequence number	0320110027.
Mid number	2600062.

Comments: Silver and mercury production is minor. Some published sources state most favorable host lithology as silty dolomitic limestone.

[1]Resource is referred to as reserves.

CARSON RIVER—MERCURY

Alternate names: None

Commodities: Hg, possible Au, Ag

LOCATION-OWNERSHIP

County	Carson City.	General location	About 13 km east of Carson City.
Mining district	Delaware.	Meridian	Mount Diablo.
Elevation	1,375 m.	Tract	Sec. 7, T 15 N, R 21 E.
Topography	River bed; in hilly to rugged terrain.	Latitude	39°10′52″ N.
Domain	BLM administered.	Longitude	119°39′56″ W.

Claimants ..... Rocky Comers, Craig Maxwell, Korey Farnworth, Carson City, NV (1982).

GEOLOGY

Type of ore body	Placer.	Host	Carson River bottom.
Origin	Mill tailing.	Geologic age	Quaternary.
Shape of ore body	Disseminated; stratiform.	Rock relationships	Stream gravel, contains mercury. Various bedrock, contains mercury.
Ore controls	River channel.		
Age of deposit	Recent (1862—see Published Reserves-Resources section).	Size	Unknown, possibly medium.
Mineralized zone average dimensions (estimated), m:			
Length	<900.		
Width	<15.		
Thickness	Thin.		
Mineral names	Mercury.		

DEVELOPMENT

Current status	Inactive-limited exploration.	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	On-site.
Mining method	Placer.	Distance to power supply	3 km.
		Mill location	No mill.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.[1]

REFERENCES

3, 29, 96, 189, 453, 509, 585, 586, 736.

USGS quad maps	Reno, 1:250,000. New Empire, 7.5′.
USBM sequence number	0325100062.

Comments: Mercury is present in deep holes, bedrock, and gravel beds.

[1]It has been reported that perhaps up to 14 to 15 million lb of mercury found its way into the river when mercury was used to recover precious metals from the Comstock (1982) (3).

CASELTON—LEAD-ZINC

Alternate names: Combined Metals Reduction, Raymond and Ely

Commodities: Zn, Pb, Ag, Au, Mn

LOCATION-OWNERSHIP

County	Lincoln.	General location	About 1 km south of Pioche.
Mining district	Pioche.	Meridian	Mount Diablo.
Elevation	1,890 m.	Tract	Sec. 29, T 1 N, R 67 E.
Topography	Hilly.	Latitude	37°55′06″ N.
Domain	Mixed.	Longitude	114°29′01″ W.

Owner: Kerr-McGee Corp., Oklahoma City, OK (1983).

GEOLOGY

Type of ore body	Replacement, fissure vein.	Host formation	Lyndon.
Origin	Hydrothermal.	Geologic age	Middle Cambrian.
Shape of ore body	Tabular.	Rock relationships	Limestone, replaced by ore, encloses ore.
Ore controls	Bedding, faulting.		
Mineralized zone average dimensions, m:		Host formation	Combined Metal Member of Pioche Shale.
Length	2,440.	Geologic age	Lower Cambrian.
Width	400.	Rock relationships	Limestone, replaced by ore, encloses ore.
Thickness	10.		Shale, lies over ore, lies under ore.
Depth	300.	Size	Medium.
Mineral names	Sphalerite, galena, manganosiderite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	On-site.
Type of operation	Underground.	Road requirement	None.
Mining method	Room and pillar.	Distance to power supply	On-site.
		Mill location	On-site.[1]
Year of discovery	1864.	Mill status	Inactive, standby.
Discovery method	Ore mineral in place.	Milling method	Flotation.
		Process rate	1,400 t/d.
Initial production	1864.	Product type	Zinc concentrate, lead concentrate.
Last production	1958.		
Past production	2.95 million t sulfide ore averaging 171.4 g/t Ag, 4.5% Pb, and 12% Zn (*724*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.[2]

REFERENCES

216, 274, 322, 720, 721, 724, 791.

USGS quad maps	Caliente, 1:250,000. Pioche, 7.5′.
USBM sequence number	0320170099.
USGS MRDS number	M032004.

[1]Caselton mill is owned by Combined Metals Reduction Corp.
[2]Sulfide ore has been largely exhausted; large quantities of oxidized ore remain.

CROWELL—FLUORINE

Alternate names: Daisy Mine, Fluorspar Mine, Beatty Fluorspar, Betsy Mine

Commodities: CaF_2

LOCATION-OWNERSHIP

County	Nye.	General location	About 102 km southeast of Goldfield.
Mining district	Fluorine.	Meridian	Mount Diablo.
Elevation	1,356 m.	Tract	Sec. 23, T 12 S, R 47 E.
Topography	Hilly.	Latitude	36°52′52″ N.
Domain	BLM administered.	Longitude	116°41′40″ W.

Owner-operator ..... Crowell Fluorspar Co., Beatty, NV (1984).

GEOLOGY

Type of ore body	Replacement, breccia fill, fissure vein.	Host formation	Nopah.
Origin	Hydrothermal.	Geologic age	Upper Cambrian.
Shape of ore body	Irregular, pipelike, lenticular.	Rock relationships	Dolomite, replaced by ore.
Ore controls	Faulting, lithology		Limestone, lies along ore, replaced by ore.
Strike and dip of mineralized zone.	N 45° E: 88° E.		Shale, lies along ore.
Mineralized zone average dimensions, m:		Size	Medium.
Length	274.		
Width	8.		
Thickness	152.		
Depth	25.		
Mineral names	Fluorite, cinnabar, calcite, quartz, orthoclase, montmorillonite.		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	<10 km.
Type of operation	Underground.	Road requirement	None.
Mining method	Open stope.	Distance to power supply	On-site.
Year of discovery	1918.		
Discovery method	Ore mineral in place.		
Initial production	1919.		
Past production	185,527 t (1919–76).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

4, 31, 97, 98, 99, 207, 213, 217, 266, 275, 281, 283, 368, 373, 381, 401, 545, 557, 714, 733, 811, 812, 815, 816.

USGS quad maps	Death Valley, 1:250,000. Bare Mountain, 15′.
USBM sequence number	0320230001.
USGS MRDS number	W006927.
Mid number	2600091.

DAYTON—IRON

Alternate names: Rosetta Mine

Commodities: Fe

LOCATION-OWNERSHIP

County	Lyon.	General location	About 36 km southeast of Reno.
Mining district	Red Mountain.	Meridian	Mount Diablo.
Elevation	1,370 m.	Tract	Sec. 6, T 17 N, R 23 E.
Topography	Rolling.	Latitude	39°21'56" N.
Domain	Private.	Longitude	119°26'57" W.

Owner: Utah International, San Francisco, CA (1956).

GEOLOGY

Type of ore body	Replacement.	Host formation	Metamorphosed sediments.
Origin	Contact metasomatic, oxidation.	Geologic age	Triassic.
Shape of ore body	Massive.	Rock relationships	Marble, replaced by ore.
Ore controls	Lithology, igneous.		Skarn (tactite), replaced by ore.
Mineralized zone average dimensions, m:			Hornfels, replaced by ore.
			Gneiss, encloses ore, gangue.
Length	400.		Schist, encloses ore, gangue.
Width	150.	Size	Medium.
Thickness	150.		
Depth	5.		
Mineral names	Hematite, limonite, magnetite, pyrite.		

DEVELOPMENT

Current status	Inactive-explored prospect.	Distance to water supply	<10 km.
Type of operation	Prospect.	Road requirement	None.
Mining method	Proposed open pit.	Distance to power supply	<10 km.
Year of discovery	1910.		
Discovery method	Test shaft, bedrock sampling.		
Initial production	Unknown.		
Last production	None.		
Past production	A small quantity mined during World War II for ship ballast (*454*).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	45,000,000 long tons.	42% Fe	1971	454

REFERENCES

110, 113, 214, 453, 454, 536, 559, 580, 583, 600, 695.

USGS quad maps	Reno, 1:250,000. Churchill Butte, 15'.
USBM sequence number	0320190060.

DEE—GOLD

Alternate names: Boulder Creek deposit

Commodities: Au
Ag (not recovered)

LOCATION-OWNERSHIP

County	Elko.	General location	About 46 km northwest of Carlin.
Mining district	Bootstrap.	Meridian	Mount Diablo.
Elevation	1,645 m.	Tract	Sec. 34, T 37 N, R 49 E.
Topography	Hilly.		Sec. 3, T 36 N, R 49 E.
Domain	BLM administered.	Latitude	41°01'26" N.
		Longitude	116°25'18" W.

Owner: Cordex V Syndicate (1984).
Operator: Dee Gold Mining Co. (Cordex V operational entity) (Dee Gold comprises Rayrock Mines, Inc., Lacana Mining Corp., Dome Exploration Ltd., all of Toronto, ON, Canada; each with 29.3%; J. S. Livermore, 12%. Rayrock will manage the operation for the partnership company).

GEOLOGY

Type of ore body	Disseminated.	Host formation	Vinini (upper plate of Roberts Mountains Thrust Fault).
Origin	Hydrothermal.	Rock relationships	Silicic shale and chert, is ore, gangue.
Shape of ore body	Elongate.		Jasperoid, near ore, contains some Au.
Ore controls	Faults (steep normal).	Alteration	Silicification, pyritization, argillic.
Strike and dip of mineralized zone.	East-west: unavailable.	Size	Small.
Planned pit average dimensions (approximate), m:			
Length	800.		
Width	800 (at widest point, narrow at each end).		
Pit area	23 ha (57 acres).		
Mineral names	Free gold (oxidized ore zone).		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	On-site wells.
Type of operation	Surface.	Road requirement	About 3 km haul access.
Mining method	Pit; about 800 t/d ore will be mined; stripping ratio = 7:1.	Distance to power supply	About 9 km to Rossi area.
		Mill location	On-site.
		Mill status	Under construction.
Year of discovery	Mid-1970's by Phillip Davis, local prospector.	Milling methods	Agitated cyanide leach, carbon-in-pulp, electrolysis.
Discovery method	Surface outcropping, geochemical, drilling.		Heap leach.
		Process rate	820 t/d.
		Product type	Dore bullion.
Initial production	September-October 1984.		
Annual production rate	About 1,200 kg (38,000 tr oz) Au anticipated for first 2 yr, then 1,000 kg/yr (33,000 tr oz) gold thereafter.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	1,110,000 tons	0.028 tr oz/ton Au (leach grade)	1983	493
	2,670,000 tons	0.115 tr oz/ton Au (milling grade)	1983	493
2..Probable	2,670,000 tons	0.115 tr oz/ton Au	1984	659
	1,100,000 tons	Heap leach, low grade	1984	659

REFERENCES

14, 27, 28, 59, 61, 72, 90, 226, 278, 493, 529, 530, 555, 659, 669, 754.

USGS quad maps: McDermitt, 1:250,,000.
Santa Renia Fields, 7.5'.
USBM sequence number: 0320070126.

Comments: Property adjoins Carlin's Bootstrap Mine and was acquired by Cordex in 1981. Minimum mine life is 8 yr. During 1981 and 1982, about 240 exploratory drill holes were completed in proposed pit area. In late summer and early fall of 1982, 2 pilot-scale heap leach tests were conducted. Silver (high grade) reported tied to silica beneath gold zone. Company reported mine life is 8 yr from 1984.

DODGE-FORD—IRON

Alternate names: Ford Mine, Iron Horse, Iron Colt

Commodities: Fe

LOCATION-OWNERSHIP

County	Pershing.
Mining district	Mineral Basin.
Elevation	1,262 m.
Topography	Gentle.
Domain	Mixed; private and BLM administered.
Owner	C. W. Hunley, et al (1971).
General location	About 25 km southeast of Lovelock.
Meridian	Mount Diablo.
Tract	Sec. 6, T 25 N, R 34 E.
Latitude	40°04'10" N.
Longitude	118°12'00" W.

GEOLOGY

Type of ore body	Replacement, breccia fill, disseminated.
Origin	Contact metasomatic, hydrothermal.
Shape of ore body	Lenticular, tabular.
Ore controls	Faulting, igneous.
Mineralized zone average dimensions, m:	
Length	450.
Width	300.
Thickness	10.
Depth	3.
Mineral names	Magnetite, scapolite, apatite, chlorite.
Host formation	Metavolcanics.
Geologic age	Upper Jurassic.
Rock relationships	Andesite, gangue. Diorite, gangue.
Size	Medium.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Surface.
Mining method	Open pit.
Year of discovery	1952.
Discovery method	Ore mineral not in place.
Initial production	1954.
Last production	1961.
Past production	800,000 t prior to 1971 (*454*).
Distance to water supply	<10 km.
Road requirement	None.
Distance to power supply	<50 km.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

329, 454.

USGS quad maps	Lovelock, 1:250,000. Buffalo Mountain, 15'.
USBM sequence number	0320270390.
USGS MRDS number	M060449.

DRY CANYON—ANTIMONY

Alternate names: Antimony No. 4, Beulah, Bray

Commodities: Sb, Ag

LOCATION-OWNERSHIP

County	Lander.
Mining district	Big Creek.
Elevation	2,505 m.
Topography	Rugged.
Domain	National forest.
Owner	Mary J. Bray (1958).
General location	About 13 km southwest of Austin.
Meridian	Mount Diablo.
Tract	Sec. 35, T 18 N, R 43 E.
Latitude	39°22′51″ N.
Longitude	117°06′41″ W.

GEOLOGY

Type of ore body	Fissure vein.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Fracturing.
Strike and dip of mineralized zone.	N 35° W: 55° SW.
Mineralized zone average dimensions, m:	
Thickness	0.3.
Mineral names	Stibnite, pyrite, tetrahedrite, sphalerite.
Host formation	Valmy.
Geologic age	Ordovician.
Rock relationships	Limestone, encloses ore.
Size	Small.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Underground.
Year of discovery	Unknown.
Discovery method	Ore mineral in place.
Initial production	Undetermined.
Last production	1916–18.
Past production	272 t of 55% Sb (*376*).
Distance to water supply	<10 km.
Road requirement	<50 km.
Distance to power supply	<50 km.
Mill location	No mill.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

376, 693.

USGS quad maps	Millett, 1:250,000. Austin, 15′.
USBM sequence number	0320150136.

Comments: Some production apparently combined with or reported as output from Antimony King (Last Chance) Mine.

EAST NORTHUMBERLAND—BARITE

Alternate names: Bluestone, IMCO Pit, All Minerals, Liesa, Merry Christmas, Blackstar

Commodites: $BaSO_4$

LOCATION-OWNERSHIP

County	Nye.	General location	About 67 km southeast of Austin.
Mining district	Northumberland.	Meridian	Mount Diablo.
Elevation	2,380 m.	Tract	Sec. 5, T 12 N, R 46 E.
Topography	Rugged.	Latitude	38°53'37" N.
Domain	National forest.	Longitude	116°49'30" W.

Owner-operator ..... All Minerals Corp., Murray, UT (1983).

GEOLOGY

Type of ore body	Replacement.	Host formation	Pinecone.
Origin	Sedimentation, metamorphic.	Geologic age	Devonian.
Shape of ore body	Lenticular, irregular.	Rock relationships	Chert, lies over ore.
Ore controls	Bedding, faulting.		Shale, lies over ore.
Strike and dip of mineralized zone.	N 70° E: 10° W.		Mudstone, lies under ore.
Mineralized zone average dimensions, m:		Size	Medium.
Length	1,500.		
Width	100.		
Thickness	15.		
Depth	15.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	<10 km.
Type of operation	Surface.	Road requirement	<10 km.
Mining method	Open pit.	Distance to power supply	On-site generation.
		Mill location	On-site.
Year of discovery	1967.	Mill status	Active.
Discovery method	Ore mineral in place.	Milling method	Jigging.
		Process rate	514 t/d.
Initial production	1975.	Product type	Crude barite.
Last production	1983.	Destination	California, Oklahoma, Texas.
Past production	Confidential proprietary data.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

87, 338, 357, 368, 546, 601, 623, 624.

USGS quad maps	Tonopah, 1:250,000.
	Northumberland Pass, 7.5'.
USBM sequence number	0320230183.
Mid number	2600847.

Comments: The deposit occurs as 3 separate ore bodies: Liesa Group, All Minerals Group, and Merry Christmas Group.

EASY MINER—BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elk.	General location	About 29 km northeast of Wells.
Mining district	Snake Mountain.	Meridian	Mount Diablo.
Elevation	1,900 m.	Tract	Secs. 11, 12, T 40 N, R 63 E.
Topography	Hilly.	Latitude	41°21′45″ N.
Domain	Public and private.	Longitude	114°48′04″ W.

Owner-operator ..... A. W. Arnold and Associates, Houston, TX (1983).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Valmy.
Origin	Syngenetic-diagenetic.	Geologic age	Ordovician.
Shape of ore body	Tabular.	Rock relationships	Chert, overlies ore.
Ore controls	Bedding.		Argillite, underlies ore.
Strike and dip of mineralized zone.	North-south: 30° W.		Chert, underlies ore.
		Size	Medium.
Mineralized zone average dimensions, m:			
Length	120.		
Width	90.		
Thickness	30.		
Depth	0 to 6.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	On-site (diesel generator).
		Mill location	Mine site.
Year of discovery	1970's.	Mill status	Idle.
Discovery method	Geological.	Milling method	Gravity separation.
		Process rate	1,200 t/d.
Initial production	1980.	Product type	3.95 sp gr barite-rich rock.
Last production	1982.	Distance shipped	Truck—35 km, then rail either 2,000 km or 3,000 km, depending on market.
Past production	Confidential proprietary data.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

226, 546, 612, 669, 716.

USGS quad maps	Wells, 1:250,000.
	Melandco, 7.5′.
USBM sequence number	0320070887.
Mid number	2601667.

EMERSON—TUNGSTEN

Alternate names: Tempiute, Tem Piute, Lincoln, Wah Chang Tungsten Mine
North Tempiute, South Thumb

Commodities: W, Mo, Zn, CaF_2, U

LOCATION-OWNERSHIP

County	Lincoln.	General location	About 99 km west of Caliente.
Mining district	Tem Piute.	Meridian	Mount Diablo.
Elevation	2,013 m.	Tract	Sec. 36, T 3 S, R 56 E.
Topography	Rugged.	Latitude	37°38′28″ N.
Domain	Mixed; private and BLM administered.	Longitude	115°37′49″ W.

Owner: Teledyne, Inc., Los Angeles, CA, 75%; North Tempiute Mining and Development, Hiko, NV, 25% (1981).
Operator: Union Carbide Corp., Mining and Metals Div., Alamo, NV (1984).

GEOLOGY

Type of ore body	Replacement, disseminated, shear zone.	Host formation	Guilmette.
Origin	Contact metasomatic, hydrothermal.	Geologic age	Mississippian.
Shape of ore body	Irregular.	Rock relationships	Limestone, replaced by ore, lies along ore.
Ore controls	Contact zone, lithology.		Hornfels, near ore.
Strike and dip of mineralized zone.	N 40° E: 60° W.		Quartzite, near ore.
Mineralized zone average dimensions, m:			Marble, lies along ore.
Length	2,000.		Skarn (tactite), is ore, gangue.
Width	500.	Size	Large.
Thickness	15.		
Depth	0.		
Mineral names	Scapolite, tremolite, muscovite, magnetite, bismuth, scheelite, sphalerite, fluorite, molybdenite, garnet, pyrite, pyrrhotite.		

DEVELOPMENT

Current status	Active-standby.	Distance to water supply	On-site.
Type of operation	Surface-underground.	Road requirement	None.
Mining method	Shrinkage stoping, open pit.	Distance to power supply	On-site.
		Mill location	On-site.
Year of discovery	1916.	Mill status	Inactive.
Discovery method	Ore mineral in place.	Milling method	Scheelite flotation.
		Product type	WO_3 concentrate.
Initial production	1937.		
Last production	1981.		
Past production	Several million kilograms of tungsten metal recovered.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

52, 69, 137, 231, 271, 343, 553, 724, 738, 800, 843, 848.

USGS quad maps	Caliente, 1:250,000. Tempiute Mountain, 15′.
USBM sequence number	0320170012.
USGS MRDS number	M030087.
Mid number	2600340.

ENFIELD BELL—GOLD

Alternate names: Bell, Jerritt Canyon, Freeport Gold

Commodities: Au

Ore body names: Marlboro Canyon, Alchem, North Generator Hill, Lower Generator Hill, West Generator Hill

LOCATION-OWNERSHIP

County	Elko.	General location	About 80 km northwest of Elko.
Mining district	Jerritt Canyon.	Meridian	Mount Diablo.
Elevation	1,925 m.	Tract	Secs. 33, 34, 35, T 41 N, R 54 E; Sec. 3, T 40 N, R 54 E.
Topography	Rugged.		
Domain	National forest (mine); BLM administered (mill); private.	Latitude	41°23′44″ N.
		Longitude	115°59′39″ W.

Owner: Freeport Gold Co., New York, NY (70%) (subsidiary of Freeport-McMoran, Inc., New York, NY); FMC Gold, Inc., Chicago, IL (30%) (1985).

Operator: Freeport Gold Co. (1985).

GEOLOGY

Type of ore body: Disseminated, stratiform, replacement.

Origin: Hydrothermal, oxidation.

Shape of ore body: Tabular, elongate.

Ore controls: Faults, fractures, lithology.

Strike and dip of mineralized zone: Unknown.

Age of mineralization: Mid-Tertiary.

Ore body dimensions (approximate), m:

	Marlboro	Otherfour ore bodies
Length	1,220.	230 to 760.
Width	120.	60 to 120.
Thickness	110.	Unknown.

Mineral names: Gold (free), gold (tied to organics), pyrite, realgar, oripiment, arsenopyrite, cinnabar, stibnite, barite, calcite, quartz.

Host formations: Hansen Creek (primary); Roberts Mountains (basal 60 m).

Geologic age: Upper Ordovician. Lower Silurian.

Rock relationships: Hansen Creek:
- Chert carbonate, jasperoid, lies under ore, lies over ore.
- Dolomite, above ore.
- Carbonaceous banded limestone, is ore, lies along ore, gangue.
- Bioclastic limestone, under ore.

Roberts Mountains:
- Dolomite, lies above ore.
- Calcareous siltstone, encloses ore, is ore, gangue.

Alteration: Silicification (over ore zone), oxidation and argillic around jasperoid (minor), and carbonization.

Size: Medium.

DEVELOPMENT

Current status: Producer-active.

Type of operation: Surface.

Mining method: Open pit, multiple bench, about 4,400 t/d ore, 23,000 t/d waste; stripping ratio = 7.9:1.

Year of discovery: 1971 (anomaly), 1973 (Alchem ore body); 1976 (Marlboro Canyon).

Discovery method: Geochemical, geologic inference, drilling.

Initial production: July 1981.

Past production: 426 kg Au (13,700 tr oz) in sales, (1981) (*316*).
>6,100 kg (196,000 tr oz) Au (1982) (*435*).
8,150 kg (262,000 tr oz) Au forecast (1984) (*418*).

Annual production rate: 6,000 kg (200,000 tr oz) dore annual rated capacity (*435*).

Distance to water supply: 3 km to deep wells.

Road requirement: 10 km paved plant access.

Distance to power supply: 26 km, 120 kV.

Mill location: 13 km east of mine (truck).

Mill status: Active.

Milling method: Agitated cyanide leach (pretreatment of carbonaceous ore by preoxidation chlorination); carbon-in-pulp; zinc precipitation; electrolysis.

Process rate: 3,040 t/d (3,350 ton/d); original capacity was 2,490 t/d (50% of capacity oxide circuit, 50% carbonaceous circuit).

Product type: Dore bullion bars (about 34 kg each).

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven and probable	11,614,000 tons	0.233 tr oz/ton Au	1983	551
2.. Do	13,700,000 tons	0.205 tr oz/ton Au	1984	313

REFERENCES

53, 61, 85, 90, 116, 173, 190, 224, 226, 253, 254, 278, 297, 299, 302, 306, 313, 316, 336, 344, 346, 348, 376, 378, 415, 418, 423, 430, 435, 479, 551, 599, 612, 616, 669, 688, 692, 730, 773, 839.

USGS quad maps: Wells, 1:250,000. California Mountain, 7.5′.

USBM sequence number: 0320070879.

Mid number: 2601620.

Comments: Mineral zone is in lower plate of Roberts Mountains Thrust Fault. Ore is carbonaceous (50%) and oxide (50%) requiring segregation during milling. Area of 5 ore bodies measures about 1,200 m by 3,300 m, and about 100 m thick.

FANNIE RYAN—MANGANESE

Alternate names: None

Commodities: Mn

LOCATION-OWNERSHIP

County	Clark.	General location	About 24 km southeast of Las Vegas.
Mining district	Las Vegas.	Meridian	Mount Diablo.
Elevation	610 m.	Tract	Sec. 36, T 21 S, R 63 E.
Topography	Rolling.	Latitude	36°05'06" N.
Domain	BLM administered.	Longitude	114°53'27" W.

Owner: United States (managed by BLM) (1980).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Muddy Creek.[1]
Origin	Hydrothermal, sedimentation.	Geologic age	Pliocene.
Shape of ore body	Tabular.	Rock relationships	Gypsiferous sandstone, encloses ore, lies over ore.
Ore controls	Lithology, faulting.		Gravel, lies over ore.
Strike and dip of mineralized zone.	N 55° E: 30° W.	Size	Small.
Mineralized zone average dimensions, m:			
Length	300.		
Width	176.		
Thickness	3.7.		
Depth	25.		
Mineral names	Wad.		

DEVELOPMENT

Current status	Inactive-explored.	Distance to water supply	<3 km.
Type of operation	Possible surface.	Road requirement	<10 km.
		Distance to power supply	<10 km.
Year of discovery	1941.	Mill location	No mill.
Discovery method	Ore mineral in place.		
Initial production	No production.		

PUBLISHED RESERVES-RESOURCES[2]

Class	*Quantity*	*Grade*	*Year*	*Reference*
1. Measured	900 tons	Average: 17.2% Mn; cutoff: 15% Mn	1949	407
2. Do	1,720 tons	Average: 15.7% Mn; cutoff: 12% Mn	1949	407
3. Do	2,380 tons	Average: 14.3% Mn; cutoff: 10% Mn	1949	407
4. Do	3,960 tons	Average: 12.6% Mn; cutoff: 8% Mn	1949	407
5. Do	25,800 tons	Average: 7.6% Mn; cutoff: 5% Mn	1949	407

REFERENCES

354, 386, 407, 547, 721.

USGS quad maps	Las Vegas, 1:250,000. Henderson, 7.5'.
USBM sequence number	0320030008.
USGS MRDS number	M031084.

[1]Manganiferous zone consists of 3 beds ranging 0.76 to 2.5 m thick.
[2]Tonnages are cumulative.

FENCEMAKER—ANTIMONY

Alternate names: Fenstonmaker, Lucky Lode, S & W

Commodities: Sb

LOCATION-OWNERSHIP

County	Pershing.	General location	About 53 km east of Lovelock.
Mining district	Table Mountain.	Meridian	Mount Diablo.
Elevation	1,600 m.	Tract	Sec. 31, T 26 N, R 37 E.
Topography	Rolling.	Latitude	40°04′19″ N.
Domain	BLM administered.	Longitude	117°51′26″ W.

Owner: Silver Bell Mining and Developing, Inc., Lovelock, NV (1983).

GEOLOGY

Type of ore body	Shear zone, replacement, disseminated.	Host formation	Boyer Ranch.
Origin	Hydrothermal.	Geologic age	Middle Jurassic.
Shape of ore body	Irregular, tabular.	Rock relationships	Limestone, encloses ore, replaced by ore.
Ore controls	Fracturing, faulting.		Shale, lies over ore, lies under ore
Strike and dip of mineralized zone.	N 30° E: 30° E.	Size	Medium.
Mineralized zone average dimensions, m:			
Length	25.		
Width	4.		
Thickness	13.		
Depth	7.		
Mineral names	Stibnite, cinnabar, chalcopyrite, silver, gold, calcite, quartz.		

DEVELOPMENT

Current status	Past producer-standby.	Distance to water supply	On-site.
Type of operation	Underground.	Road requirement	None.
Mining method	Open stope.	Distance to power supply	On-site.
		Mill locaton	On-site.
Year of discovery	1880.		
Discovery method	Ore mineral in place.		
Initial production	1880.		
Last production	1982.		
Past production	1 t Sb metal (*376*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

29, 68, 329, 376, 381, 464, 541, 671, 672.

USGS quad maps	Winnemucca, 1:250,000. Fencemaker, 15′.
USBM sequence number	0320270414.
USGS MRDS number	M055423.
Mid number	2601650.

FISH CREEK—BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.	General location	About 27 km north of Carlin.
Mining district	Swales Mountain.	Meridian	Mount Diablo.
Elevation	1,950 m.	Tract	Sec. 2, T 35 N, R 52 E.
Topography	Hilly.	Latitude	40°57'10" N.
Domain	Mixed.	Longitude	116°06'15" W.

Owner: Maggie Creek Ranch Co., Elko, NV; New Park Resources, Inc., Metairie, LA (1983).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Vinini.
Origin	Sedimentation.	Geologic age	Ordovician.
Shape of ore body	Tabular.	Rock relationships	Chert, encloses ore.
Ore controls	Bedding.		Siltstone, replaced by ore.
Strike and dip of mineralized zone.	N 50° to 60°E: 10° to 20° W.		Sandstone, lies over ore.
Mineralized zone average dimensions, m:		Size	Large.
Length	2,100.		
Width	300.		
Thickness	15.		
Depth	1.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-explored (extensively drilled).	Distance to water supply	<30 km.
Type of operation	Possible surface.	Road requirement	<10 km.
		Distance to power supply	<50 km.
Year of discovery	1955.	Mill location	No mill.
Discovery method	Ore mineral in place.		
Initial production	No production.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

87, 185, 226, 283, 349, 546, 669.

USGS quad maps	Winnemucca, 1:250,000. Swales Mountain, 7.5'.
USBM sequence number	0320070901.

GARNET-TENNESSEE MOUNTAIN—TUNGSTEN

Alternate names: Knowles Bros. Tungsten Claims, Tennessee Mountain Mine, Tennessee Mountain, Garnet Tungsten, Garnet

Commodities: W, Mo

LOCATION-OWNERSHIP

County ..... Elko.
Mining district ..... Alder.
Elevation ..... 2,438 m.
Topography ..... Rugged.
Domain ..... National forest.

General location ..... About 24 km east of Mountain City.
Meridian ..... Mount Diablo.
Tract ..... Sec. 17, T 45 N, R 56 E.
Latitude ..... 41°47'41" N.
Longitude ..... 115°40'25" W.

Owner ..... Knowles Bros., 50%; P. D. Montrose, 50% (1981).
Operator ..... PAB Oil and Mining (1981).

GEOLOGY

Type of ore body ..... Replacement.
Origin ..... Contact metasomatic, metamorphism.
Shape of ore body ..... Tabular.
Ore controls ..... Contact zone, igneous.
Strike and dip of mineralized zone. N 50° W: 55° S.
Mineralized zone average dimensions, m:
  Length ..... 335.
  Width ..... 53.
  Thickness ..... 8.
  Depth ..... 53.
Mineral names ..... Scheelite, powellite, molybdenite, pyrite, chalcopyrite, magnetite, garnet, uraninite, chlorite, epidote.

Host formation ..... Tennessee Mountain.
Geologic age ..... Ordovician.
Rock relationship ..... Limestone, encloses ore, replaced by ore.
Shale, encloses ore, replaced by ore.
Skarn (tactite), replaced by ore.
Hornfels, replaced by ore.
Size ..... Medium.

DEVELOPMENT

Current status ..... Inactive-past producer.
Type of operation ..... Underground.
Mining method ..... Sublevel.

Year of discovery ..... 1949.
Discovery method ..... Ore mineral in place.

Initial production ..... 1970.
Last production ..... 1977.
Past production ..... Confidential proprietary data.

Distance to water supply ... On-site.
Road requirement ..... None.
Distance to power supply ... >100 km.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	396,000 tons	0.42% WO_3	1977	526, 527

REFERENCES

70, 91, 139, 154, 226, 278, 526, 527, 669, 733.

USGS quad maps ..... Wells, 1:250,000.
Rowland, 15'.
USBM sequence number ..... 0320070011.
USGS MRDS number ..... D001177.

GETCHELL—GOLD

Alternate names: None

Commodities: Au, Ag, W, As

LOCATION-OWNERSHIP

County	Humboldt.	General location	About 70 km northeast of Winnemucca.
Mining district	Potosi.	Meridian	Mount Diablo.
Elevation	1,707 m.	Tract	Sec. 33, T 39 N, R 42 E.
Topography	Hilly.	Latitude	41°12'59" N.
Domain	Mixed; private and BLM adminstered.	Longitude	117°15'23" W.

Owner: FRM Minerals, Inc., Denver, CO (subsidiary of First Mississippi Corp., Jackson, MS) (1984).

GEOLOGY

Type of ore body	Disseminated, replacement.	Host formation	Preble.
Origin	Hydrothermal.	Geologic age	Cambrian.
Shape of ore body	Sheetlike, irregular.	Rock relationships	Gouge (quartz, carbon, clay), is ore, encloses ore, gangue.
Ore controls	Faulting, fracturing, folding, lithology.		Argillite, sheared and replaced by gouge, ore in fractures, gangue.
Strike and dip of mineralized zone.	N 25° W: 45° to 90° E.		Arenaceous limestone, sheared and replaced by gouge, ore in fractures, gangue.
Age of mineralization	Cretaceous to Miocene (90 million yr).		Shale, lies over ore, lies under ore.
Mineralized zone average dimensions, m:			Granodiorite and dacite porphyry dikes, near ore.
Length	>2,100.	Alteration	Silicification, decarbonatization, sericitic, argillic, chlorite.
Width	1,000 (downdip).	Size	Small.
Thickness	12 (assay walls).		
Mineral names	Native gold, quartz (Au), carbon (Au), pyrite (Au), arsenopyrite (Au), calcite, kaolinite, chlorite, realgar, orpiment, cinnabar, stibnite, chalcopyrite, sphalerite, marcasite, magnetite, barite, fluorite, chabasite, getchellite, galkhaite, scheelite.		

DEVELOPMENT

Current status	Active-past producer, exploration.	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	Existing.
Mining method	Open pit; tailings and dump recovery was being planned by Conoco (see comments).	Distance to power supply	Existing.
		Mill location	On-site.
		Mill status	Active (1983).
		Milling method	Tailings test-cyanide leach tank, carbon columns.
Year of discovery	1934.	Process rate	91 t/d.
Discovery method	Ore mineral in place.		
Initial production	1938.		
Last production	1967.		
Past production	12,069 kg (388,033 tr oz) Au (1938-50); no production in 1946-47 (*44*). 1,916,910 t (2,113,030 tons), 9.29 g/t (0.271 tr oz/ton) Au (1962-67) (*44*).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	3,200,000 tons	0.3 tr oz/ton Au; 0.1 tr oz/ton Ag	1982	690
2.. Do	3,250,000 tons	0.18 tr oz/ton Au	1982	61
Possible	10,000,000 tons	0.16 tr oz/ton Au	1982	61
3..Proven	1,400,000 tons	0.22 tr oz/t Au	1983	84
4..Not reported in reference	>750,000 tr oz[1]	Not applicable	1983	201

REFERENCES

43, 44, 45, 47, 61, 67, 79, 81, 84, 174, 201, 232, 242, 243, 269, 270, 285, 292, 308, 334, 335, 336, 364, 425, 616, 628, 656, 690, 702, 773, 801, 807, 808.

USGS quad maps	McDermitt, 1:250,000. Osgood Mountains, 15'.
USBM sequence number	0320130063.
USGS MRDS number	M030027.
Mid number	2601801.

Comments: Gold mineralization has also been observed on the Village Fault, located 300 m east of the Getchell Fault described above. Conoco, Inc. sold the property in 1983. Plans were to dewater and explore the 3 existing pits beginning in mid-1983. Two phases of development were planned: Phase I—heap leaching existing tailings and old mine waste material from 1983 to 1994; Phase II—open pit mining with associated milling operations. Construction was to start in late 1985, with production commencing 1 yr later.

[1]Company reports "reserves appear to exceed" troy ounce total.

GIBELLINI—MANGANESE

Alternate names: Niganz Manganese-Nickel, Black Iron

Commodities: Mn, Ni, Zn

LOCATION-OWNERSHIP

County	Eureka.	General location	About 27 km south of Eureka.
Mining district	Fish Creek.	Meridian	Mount Diablo.
Elevation	2,103 m.	Tract	Sec. 35, T 16 N, R 52 E.
Topography	Hilly.	Latitude	39°12'30" N.
Domain	BLM administered.	Longitude	116°05'23" W.
Owner	Louis Gibellini (1976).		

GEOLOGY

Type of ore body	Shear zone, replacement.	Host formation	Vinini.
Origin	Hydrothermal, replacement.	Geologic age	Lower Devonian.
Shape of ore body	Pipelike, massive.	Rock relationships	Limestone, ore in fractures.
Ore controls	Fracturing, faulting.		Sandstone, lies along ore, lies over ore.
Strike and dip of mineralized zone.	N 70° E: 30° W.		Shale, near ore, lies along ore.
Mineralized zone average dimensions, m:			Chert, near ore, lies along ore.
Length	50.		Quartzite, near ore, lies along ore.
Width	30.	Size	Small.
Thickness	20.		
Depth	10.		
Mineral names	Psilomelane, pyrolusite.		

DEVELOPMENT

Current status	Inactive-explored.	Distance to water supply	<3 km.
Type of operation	Surface, underground.	Road requirement	None.
		Distance to power supply	<100 km.
Year of discovery	1942.	Mill location	No mill.
Discovery method	Ore mineral in place.		
Past production	No production; 2 car lots shipped in 1953 for testing, averaged 31.7% Mn (*721*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

51, 593, 721.

USGS quad maps	Millett, 1:250,000.
	Cockalorum Wash, 15'.
USBM sequence number	0320110006.
USGS MRDS number	W000698.

Comments: The manganese-rich material contains equal amounts of pyrolusite and psilomelane; it also contains appreciable amounts of zinc, nickel, and minor amounts of cobalt, copper, vanadium, and molybdenum. An analysis of a metallurgical sample revealed the following in percent (*51*):

Mn	*Fe*	*Ni*	*Co*	*Zn*	*Cu*	*Mo*	V_2O_5	*Ba*	*CaO*	*S*	*Insol*	Al_2O_3
18.5	3.0	1.7	0.3	3.2	0.12	0.11	0.88	3.7	2.3	0.2	41.6	6.0

GOLD QUARRY—GOLD

Alternate names: None

Commodities: Au, Hg

LOCATION-OWNERSHIP

County	Eureka.	General location	About 23 km south-southeast of Carlin Mine.
Mining district	Maggie Creek.		
Elevation	1,658 m.	Meridian	Mount Diablo.
Topography	Hilly.	Tract	Sec. 34, 35, T 34 N, R 51 E.
Domain	Private, private lease, BLM administered.	Latitude	40°47′27″ N.
		Longitude	116°13′00″ W.

Owner: Newmont Mining Corp., New York, NY (1985).
Operator: Carlin Gold Mining Co., Carlin, NV (subsidiary of Newmont Mining Corp.) (1985).

GEOLOGY

Type of ore body	Disseminated.	Host formation	Vinini (upper plate of Roberts Mountains Thrust Fault).
Origin	Hydrothermal.		
Shape of ore body	Pipelike.	Geologic age	Ordovician.
Ore controls	Faults; lithology.	Rock relationships	Cherts, contains ore in shears and fractures, gangue.
Mineralized zone average dimensions (estimated), m:			Quartzites, contains ore in shears and fractures, gangue.
Length	620.		Siltstones, probable host of new discovery.
Width	460.		Carbonates, probable host of new discovery.
Mineral names	Native gold.	Alteration	Silicification (jasperoid), argillic.
		Size	Large.

DEVELOPMENT

Current status	Active-development, construction.	Mill location	On-site probable.
Type of operation	Surface.	Mill status	Development.
Mining method	Open pit; will mine about 2.3 million t/a ore.	Milling method	Cyanide heap leach and cyanide agitated leach, carbon-in-pulp gold recovery.
Year of discovery	1977 (new).	Process rate	6,120 t/d (6,750 ton/d) ore.
Discovery method	Geological inference, drilling.	Product type	Dore bars and byproduct Hg.
Initial production	1936; by Newmont from full-scale test heap leach (about 1982-83); mill production scheduled to commence August 1985.		
Past production	54.1 t (59.7 tons), 14.3 g/t (0.417 tr oz/ton) Au, 30.2 g/t (0.88 tr oz/ton) Ag (1936) (*593*). 1,314 kg (42,230 tr oz) from 886,202 t (976,871 tons) ore from test heap leach (1983) (*511*).		
Annual producton rate	5,300 kg Au (170,000 tr oz) anticipated beginning August 1985.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1. Proven and probable	45,000,000 tons	0.078 tr oz ton/Au (high grade)	1983	511
	89,000,000 tons	0.032 tr oz ton/Au (low grade, stripping ratio 1.6:1)	1983	511
	49,000,000 tons	0.029 tr oz ton/Au (unrecoverable)	1983	511
Total	183,000,000 tons	0.043 tr oz ton/Au (recoverable and unrecoverable)	1983	511

REFERENCES

27, 90, 116, 134, 184, 224, 237, 319, 435, 505, 507, 511, 514, 593, 834.

USGS quad maps	Winnemucca, 1:250,000. Schroeder Mountain, 7.5′.
USBM sequence number	0320110219.
Mid number	2601635.

Comments: Mine-mill construction began in the spring of 1984. Newmont pays royalties of 18% on 87.5% of the mineral rights held by Ash and Thornton. Geology and ore characteristics are reported much the same as at Carlin. In 1982, full-scale heap leaching and milling tests were conducted. Total recoverable high- and low-grade 1983 proven and probable reserves is 134 million tons, 0.048 tr oz/ton Au.

GOLDFIELD—GOLD

Alternate names: Goldfield Project, Pacific Gold and Uranium, Goldfield Consolidated Main Vein

Commodities: Au, Ag (Au-Ag ratio about 3:1)

LOCATION-OWNERSHIP

County	Esmeralda.	General location	About 40 km south of Tonopah.
Mining district	Goldfield.	Meridian	Mount Diablo.
Elevation	1,720 m.	Tract	Secs. 25, 26, 36, T 2 S, R 42 E.
Topography	Hilly-mountainous.	Latitude	37°43'30" N.
Domain	Patented claims.	Longitude	117°13'11" W.

Owner: Davis Goldfield Mining Co. (receives 7.5% net royalty increasing to 10%) (1983).
Lessees: Southern Pacific Land Co., San Francisco, CA, 50%; Noranda Exploration, Inc., Toronto, ON, Canada, 25%; Pacific Gold and Uranium, Inc. (PG & U), Los Angeles, CA 25% (1983).
Operator: Blackhawk Mines Corp. (1984).

GEOLOGY

Type of ore body	Vein systems, replacement.	Host formations	Porphyritic Rhyodacite.
Origin	Hydrothermal.		Quartz Latite flows and tuffs (Kendall Tuff).
Shape of ore bodies	Variable-pipes, lenticular, tabular.	Geologic ages	Lower Miocene.
Ore controls	Faults, fractures.		Oligocene.
Strike and dip of mineralized zone.	North: 30° to 40° E.	Rock relationships	Silicified porphyritic rhyodacite, portions are ore, encloses ore (major host).
Age of mineralization	Miocene.		Porphyritic rhyodacite, gangue.
Proposed pit average dimensions (estimated), m:			Silicified quartz latite, portions are ore, encloses ore.
Length	460.		Quartz latite, gangue.
Width	45.		Siliceous shale and argillite, lies beneath ore (Ordovician Palmetto Formation).
Thickness	30.		Quartz monzonite, lies beneath ore (Tertiary).
Mineral names	Native gold, famatinite, tetrahedrite-tennantite, bismuthinite, goldfieldite, chalcopyrite, galena, sphalerite, sylvanite, hessite, petzite, calaverite, pyrite, quartz, jasperoid, limonite, halloysite, gypsum.	Alteration	Highly bleached and altered—advanced argillization, alunitization, silicification.
		Size	Small.

DEVELOPMENT

Current status	Active-developing.	Distance to water supply	Two 300-gpm wells near plant site.
Type of operation	Surface.	Road requirement	2.4 km (improvement).
Mining method	Open pit (shallow).	Distance to power supply	3.2 km.
		Mill location	Near mine.
Year of discovery	1902 (district); 1981 (option acquired by Noranda and PG & U).	Mill status	Development.
Discovery method	Recent drilling.	Milling method	Anticipated agglomerated cyanide heap leach; zinc precipitation or carbon absorption.
Initial production	Anticipated fourth quarter 1984.	Process rate	About 1,100 t/d ore.
Last production	Unknown.		
Past production	District—130,326 kg Au; 45,107 kg Ag; 3,479 t Cu; 23 t Pb from 7,021,750 t ore (1903–60). 1948–51 production withheld (*8*).		
Annual production rate	About 270,000 t ore.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	500,000 tons	0.07 tr oz/ton Au	1980	162
2..Proven	2,115,000 tons	0.070 tr oz/ton Au	1984	502

REFERENCES

7, 8, 19, 20, 21, 22, 23, 24, 162, 208, 209, 246, 325, 340, 497, 502, 576, 627, 631, 632, 703, 809.

USGS quad maps: Goldfield, 1:250,000. Goldfield, 15'.
USBM sequence number: 0320090415.

Comments: Specific geology of the proposed pit area was not available. Geologic data describe the area of the district that will host the proposed development work. Reserve tonnage reported from 3 discrete ore bodies along Goldfield ledge. Reserve cutoff grade is 0.020 tr oz/ton Au.

GOLDSTRIKE—GOLD

Ore body names: Long Lac deposit, Bazza (past open pits: Goldstrike No. 6, Goldstrike No. 9, Pan Cana No. 1, E. P. No. 1, E. P. No. 2)

Commodities: Au, Ag (Au-Ag ratio = 20:1)

LOCATION-OWNERSHIP

County	Eureka.
Mining district	Lynn.
Elevation	1,700 m.
Topography	Hilly.
Domain	BLM administered.
General location	About 38 km northwest of Carlin.
Meridian	Mount Diablo.
Tract	Sec. 30, T 36 N, R 50 E.
	Sec. 24, T 36 N, R 49 E.
Latitude	40°58′12″ N.
Longitude	116°21′55″ W.

Operator: Western States Minerals Corp., Wheat Ridge, CO (in a joint venture partnership with Pan Cana Industries) (1984).

GEOLOGY

Type of ore body	Disseminated.
Origin	Hydrothermal.
Shape of ore body	Tabular to elongated lensoid.
Ore controls	Faulting, fracturing-brecciation, lithology.
Strike of mineralized zone.	N 55° W.
Age of mineralization	Cretaceous (78 million yr).
Mineralized area average dimensions (estimated), m:	
Length	2,100.
Width	1,400.
Thickness	75 to 170..
Depth	10.
Principal minerals	Pyrite (auriferous), marcasite (auriferous), quartz, sericite, kaolinite, montomorillonite, goethite.
Other	Chalcopyrite, scheelite, hematite, garnet, diopsite, tremolite, calcite, barite, jarosite, variscite, chalcedony, alunite, stibnite, aragonite, realgar, orpiment, arsenopyrite, sphalerite.
Host formation	Vinini Formation (most favorable); skarn, latite, dike, granodiorite.
Geologic age	Ordovician (Vinini).
Rock relationships	Argillites (carbonaceous), fractures contain ore.
	Shales (sometimes carbonaceous), fractures contain ore.
	Siltstone, fractures contain ore.
	Quartzite (minor), near ore, gangue.
	Chert (minor), near ore, gangue.
	Limestone (rare), gangue.
	Granodiorite-to-diorite stock, contains ore (Early Cretaceous).
	Quartz latite and latite dikes, contains ore.
	Skarn (zenoliths in diorite stock), contains ore.
	Jasperoid, above ore, near ore.
Alteration	Silicification, argillic, sericite.
Size	Small.

DEVELOPMENT

Current status	Active-producer.
Type of operation	Surface.
Mining method	Open pit.
Initial production	1976-77 (by Pan Cana Industries).
Past production	About 230 kg Au (1979) (*132*).
Road requirement	None, existing to the site.
Mill location	On-site.
Mill status	Active.
Milling method	Cyanide heap leach.
Process rate	Unknown.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

132, 182, 183, 460, 593, 690.

USGS quad maps	Elko, 1:250,000.
	Rodeo Creek NE, 7.5′.
USBM sequence number	0320110168.
Mid number	2601089.

Comments: Best mineralization occurs at intersection of high-angle structures and following low-angle structures. About 4 to 5 areas or zones of gold mineralization occur in the mine area. Northwest-trending high-angle faults (pre-mineral) have dominant control over mineralization. Individual mineral zones are 60 to 300 m in length with northwest elongation and 15 to 60 m in width. Both oxide and unoxidized ore exists. Oxide ore is known to exist up to 90 m in depth. Unoxidized sulfide ore has been as shallow as 20 m.

GOOSEBERRY—SILVER

Alternate names: Gooseberry Claims, Red Top Claims

Commodities: Ag, Au

LOCATION-OWNERSHIP

County	Storey.
Mining district	Unorganized.
Elevation	1,646 m.
Topography	Rugged.
Domain	Mixed, private (patented claims); BLM administered (unpatented claims).
General location	About 24 km east of Reno.
Meridian	Mount Diablo.
Tract	Sec. 25, T 19 N, R 22 E.
Latitude	39°29'03" N.
Longitude	119°27'52" W.
Owner-operator	Asamera Minerals (U.S.), Inc., Reno, NV (subsidiary of Asamera, Inc., Calgary, AB, Canada), 75% (1984).
Owner	Ican Resources Ltd., Vancouver, BC, Canada, 25% (1984).

GEOLOGY

Type of ore body	Fissure vein, shear zone, disseminated.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Faulting, fracturing.
Strike and dip of mineralized zone.	N 20° W: 80° S.
Age of mineralization	Tertiary.
Vein average dimensions, m:	
Length	>900.
Width	>440 (downdip).
Thickness	2.5.
Mineral names	Electrum, argentite, native gold and silver, pyrite, stephanite, minor galena, chalcopyrite, sphalerite, calcite, quartz, adularia.
Host formation	Kate Peak.
Geologic age	Miocene.
Rock relationships	Dacite porphyry, ore in veins and fractures, gangue.
	Rhyodacite, ore in veins and fractures, gangue.
	Flow breccia, near ore.
	Calcite-quartz-adularia vein, contains ore, gangue.
	Granodiorite, near ore.
Alteration	Propylitic, argillic.
Size	Small.

DEVELOPMENT

Current status	Active-producer.[1]
Type of operation	Underground.
Mining method	Cut-and-fill stoping (by yearend 1983, 25% of mill feed will be drawn by shrinkage stoping).
Year of discovery	1906.
Discovery method	Surface outcrop.
Initial production	1976, by Westcoast Oil and Gas Corp.; 1983, by Asamera.
Last production	1981, Westcoast Oil and Gas Corp.; Asamera currently producing in 1985.
Past production	15,551 kg Ag (1980) (*165*).
	4,959 kg Ag (1981) (*165*).
	9,528.7 kg Ag, 216.7 kg Au (1983) (*172*).
Distance to water supply	11 km, pumped from river.
Road requirement	Existing.
Distance to power supply	On-site.
Mill location	On-site.
Mill status	Active.
Milling method	Flotation, cyanidation of concentrate, Merrill-Crowe zinc dust precipitation.
Process rate	320 t/d.
Product type	Pb, Ag, Au precipitate.
Destination	Englehard Industries, Los Angeles, CA.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven and probable	607,000 tons	9.73 tr oz/ton Ag; 0.23 tr oz/ton Au	1983	101
Possible	730,000 tons			
2..Reserves	500,000 tons	9 tr oz/ton Ag; 0.25 tr oz/ton Au	1984	537
3..Proven and probable	561,300 tons	10.18 tr oz/ton Ag; 0.26 tr oz/ton Au	1984	504

REFERENCES

66, 90, 101, 165, 172, 378, 412, 470, 504, 528, 537, 597, 607, 695, 783.

USGS quad maps	Reno, 1:250,000. Churchill Butte, 15'.
USBM sequence number	0320290018.
Mid number	2600249.

Comments: Asamera is considering installation of an on-site plant to produce dore bullion from the precipitate. In 1982, Asamera acquired the property from Scurry-Rainbow (subsidiary of Westcoast Oil and Gas Corp.), which had been operating the Gooseberry.

[1]Gooseberry production was suspended in February 1985 because of depressed metal prices. Exploration and development was reported to continue during the suspension.

GREYSTONE—BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Lander.
Mining district	Bullion.
Elevation	2,000 m.
Topography	Hilly.
Domain	BLM administered.
Owner	Dresser Industries, Dallas, TX (1984).
General location	About 41 km south of Battle Mountain.
Meridian	Mount Diablo.
Tract	Sec. 26, T 28 N, R 45 E.
Latitude	40°16'27" N.
Longitude	116°52'21" W.

GEOLOGY

Type of ore body	Sedimentary, replacement.
Origin	Sedimentation.
Shape of ore body	Tabular.
Ore controls	Bedding, lithology.
Strike and dip of mineralized zone.	N 40° W: 30° S.
Mineralized zone average dimensions, m:	
Length	900.
Width	110.
Thickness	90.
Depth	0.
Mineral names	Barite.
Host formation	Slaven Chert.
Geologic age	Devonian.
Rock relationships	Chert, encloses ore, gangue.
	Shale, encloses ore.
	Limestone, encloses ore.
Size	Medium.

DEVELOPMENT

Current status	Active-producer.
Type of operation	Surface.
Mining method	Open pit.
Year of discovery	1951.
Discovery method	Ore mineral in place.
Initial production	1954.
Last production	1983.
Past production	More than 3.6 million t mined, processed, and shipped (*385*).
Distance to water supply	<3 km.
Road requirement	None.
Distance to power supply	On-site.
Mill location	On-site.
Mill status	Operating.
Milling method	Crushing, screening, jigging.
Process rate	1,813 t/d.
Product type	Crushed barite concentrate.
Distance shipped	46 km.
Destination	Battle Mountain, NV.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

76, 87, 218, 283, 330, 346, 385, 392, 546, 548, 601, 693.

USGS quad maps	Winnemucca, 1:250,000. Mt. Lewis, 15'.
USBM sequence number	0320150073.
Mid number	2600411.

Comments: The Greystone is reported to be the largest producing barite mine in the country and one of the largest ever discovered and developed (*385*).

GUNMETAL—TUNGSTEN

Alternate names: Desert Scheelite; Garnet; Lindsay; Summerfield

Commodities: W, Mo, Au

LOCATION-OWNERSHIP

County	Mineral.	General location	About 70 km northwest of Tonopah.
Mining district	Shoshone.	Meridian	Mount Diablo.
Elevation	2,255 m.	Tract	Sec. 18, T 6 N, R 37 E.
Topography	Rugged.	Latitude	38°23'10" N.
Domain	Private.	Longitude	117°53'40" W.

Owner: Union Carbide Corp., Danbury, CT (1981).

GEOLOGY

Type of ore body	Replacement.	Host formation	Luning.
Origin	Contact metasomatic.	Geologic age	Triassic.
Ore controls	Lithology, faulting.	Rock relationships	Limestone, replaced by ore.
Mineralized zone average dimensions, m:			Marble, gangue, encloses ore.
Length	214.		Skarn (tactite), gangue, encloses ore.
Thickness	15.	Size	Large.
Mineral names	Scheelite, garnet, galena, tetrahedrite, molybdenite, sphalerite, quartz, calcite, epidote.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	On-site.
Type of operation	Surface-underground.	Road requirement	None.
		Distance to power supply	<50 km.
Year of discovery	1916.		
Discovery method	Unknown.		

Past production: Confidential proprietary data.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

223, 343, 444, 598, 608, 733, 740, 774.

USGS quad maps	Tonopah, 1:250,000.
USBM sequence number	0320210054.
USGS MRDS number	M030116.

HARD LUCK-PRADIER—ANTIMONY

Alternate names: Pradier, Romano, Big Creek

Commodities: Sb, Ag

LOCATION-OWNERSHIP

County	Lander.	General location	About 22 km south of Austin.
Mining district	Big Creek.	Meridian	Mount Diablo.
Elevation	2,804 m.	Tract	Sec. 27, T 17 N, R 43 E.
Topography	Rugged.	Latitude	39°18′17″ N.
		Longitude	117°07′57″ W.

Owner: Big Creek Mining and Milling Co., Austin, NV (1958).

GEOLOGY

Type of ore body	Silicified fault breccia.	Host formation	Valmy.
Origin	Hydrothermal.	Geologic age	Ordovician.
Shape of ore body	Tabular, podlike.	Rock relationships	Shale, encloses ore.
Ore controls	Faulting.		Slate, encloses ore.
Strike and dip of mineralized zone.	N 20° W: flat lying.	Size	Small.

Mineral names: Stibnite, malachite, tetrahedrite, azurite.

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	<10 km.
Type of operation	Underground, surface.	Road requirement	<50 km.
Mining method	Unknown.	Distance to power supply	<50 km.
		Mill location	No mill.

Year of discovery: Prior to 1936.
Discovery method: Ore mineral in place.

Initial production: About 1936.
Last production: 1958.
Past production: 68 t Sb metal (*376*).

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

376, 693.

USGS quad maps	Millett, 1:250,000. Austin, 15′.
USBM sequence number	0320150193.

Comments: Stibnite occurs as blebs, small pods, and single crystals.

HEAVY SPAR—BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.	General location	About 25 km north of Carlin.
Mining district	Swales Mountain.	Meridian	Mount Diablo.
Elevation	1,685 m.	Tract	Sec. 10, T 35 N, R 52 E.
Topography	Hilly.	Latitude	40°56′12″ N.
Domain	BLM administered.	Longitude	116°06′51″ W.

Owner: New Park Resources, Inc., Metairie, LA (1983).

GEOLOGY

Type of ore body	Replacement.	Host formation	Vinini.
Origin	Hydrothermal.	Geologic age	Ordovician.
Shape of ore body	Tabular.	Rock relationships	Siltstone, replaced by ore.
Ore controls	Bedding.		Chert, encloses ore.
Strike and dip of mineralized zone.	N 15° E: 45° W.		Shale, encloses ore.
		Size	Medium.
Mineralized zone average dimensions, m:			
Length	213.		
Width	91.		
Thickness	15.		
Depth to	15.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	<3 km.
Type of operation	Surface.	Road requirement	<10 km.
Mining method	Open pit.	Distance to power supply	<50 km.
		Mill location	No mill.
Year of discovery	1953.		
Discovery method	Ore mineral in place.		
Initial production	1981.		
Last production	1983.		
Past production	Confidential proprietary data.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

87, 185, 226, 283, 349, 546, 669.

USGS quad maps	Winnemucca, 1:250,000.
	Swales Mountain, 7.5′.
USBM sequence number	0320070098.
Mid number	2601673.

Comments: The property ceased production in 1983 because of depressed barite market conditions. The Heavy Spar may be an extension of the Fish Creek deposit in sec. 2, T 35 N, R 52 E.

HOLLYWOOD—ANTIMONY

Alternate names: Lakeview, Antelope Springs, Lee

Commodities: Sb, Ag

LOCATION-OWNERSHIP

County	Pershing.
Mining district	Antelope Springs (Relief, Pershing).
Elevation	1,390 m.
Topography	Rugged.
Domain	BLM administered.
Owner	Alma D. Priester (1960).
General location	About 29 km east of Lovelock.
Meridian	Mount Diablo.
Tract	Sec. 2, T 26 N, R 34 E.
Latitude	40°08'54" N.
Longitude	118°07'04" W.

GEOLOGY

Type of ore body	Fissure vein.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Faulting, fracturing.
Strike and dip of mineralized zone.	N 35° to 60° W: 60° to 65° NE.
Mineralized zone average dimensions, m:	
Length	>50.
Width	Unknown.
Thickness	0.5.
Depth	0.
Mineral names	Stibnite, pyrite.
Host formation	Grass Valley.
Geologic age	Upper Triassic.
Rock relationships	Calcareous shale, near ore. Limestone, near ore. Siltstone, near ore.
Size	Small.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Underground.
Mining method	Unknown.
Year of discovery	1864.
Discovery method	Ore mineral in place.
Initial production	1916.
Last production	1967.
Past production	464 t Sb metal (*376*).
Distance to water supply	<10 km.
Road requirement	<3 km.
Distance to power supply	<50 km.
Mill location	Ore shipped to Austin, NV, for milling in 1967.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

329, 376, 718.

USGS quad maps	Lovelock, 1:250,000. Buffalo Mountain, 15'.
USBM sequence number	0320270361.
USGS MRDS number	M060417.

Comments: Principal period of production from the Hollywood Mine was during World War I.

HORSE CANYON—GOLD

Alternate names: None

Commodities: Au

LOCATION-OWNERSHIP

County	Eureka.	General location	About 100 km southwest of Elko.
Mining district	Cortez-Mill Canyon.	Meridian	Mount Diablo.
Elevation	2,530 m.	Tract	Sec. 3, T 26 N, R 48 E (unsurveyed).
Topography	Rugged.	Latitude	40°08′50″ N.
Domain	BLM administered.	Longitude	116°32′45″ W.

Owners: Placer U.S., Inc., San Francisco, CA (subsidiary of Placer Development, Ltd., Vancouver, BC, Canada); Kennecott Copper Corp., Salt Lake City, UT; Vernon F. Taylor, Jr. (1984).

Operator: Cortez Gold Mines (operational entity of Placer U.S., Inc.) (1984).

GEOLOGY

Type of ore body	Disseminated.	Host formation	Vinini (upper plate of Roberts Mountains Thrust Fault).
Origin	Hydrothermal.	Geologic age	Ordovician.
Ore controls	Faults, fractures, lithology.	Rock relationships	Shale, in part cherty and carbonaceous, ore host. Siltstone, ore host. Rhyolite dikes, near ore, intrudes host (Miocene). Silicified jasperoid breccia, hosted in Vinini.
Planned pit size	27 ha (68 acres).		
Mineral names	Native gold, quartz, iron oxides, clays, barite, jasperoid, jarosite.	Alteration	Silicification, iron staining, bleaching.
		Size	Small.

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	On-site at Cortez.
Type of operation	Surface, mine rate about 660,000 t/a ore; stripping ratio is about 3:1 (waste:ore).	Road requirement	About 22 km to Cortez mill.
		Distance to power supply	Existing to Cortez mill.
		Mill location	Cortez mill (22 km haulage from mine).
Mining method	Open pit.	Mill status	Active.
Initial production	February 1983 (mining); May 1983 (milling).	Milling method	Agitated tank cyanide leach (CIL-carbon in leach), carbon columns, pressure stripping, electrolysis-steel wool, smelting.
Annual production rate	600 kg (20,000 tr oz) Au (1983); then 1,200 kg (40,000 tr oz) Au thereafter.	Process rate	1,800 t/d (2,000 ton/d).
		Product type	Dore buttons.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1.	Not reported in reference	3,121,000 t	1.89 g/t Au	1982	564
2.	Do	3,400,000 tons	0.055 tr oz/ton Au	1983	169

REFERENCES

27, 84, 90, 100, 169, 170, 219, 426, 513, 564, 593, 692, 780, 781, 785.

USGS quad maps: Winnemucca, 1:250,000. Cortez, 15′.

USBM sequence number: 0320110228.

Comments: The Horse Canyon ore is milled at the Cortez mill. The Cortez gold deposit was mined until 1973 when mining operations shifted west to Placer Amex's Gold Acres gold deposit across the valley. Mining and milling continued until February 1976. Cortez and Gold Acres dumps were leached to 1980. In 1980, mining on other Cortez and Gold Acres dumps began; Cortez material was leached and Gold Acres material milled. Horse Canyon ore replaced output from Gold Acres low-grade dumps in May 1983. The Cortez dumps were still actively being mined and leached in late 1983. Company reported mine life is less than 5 yr from 1983.

INDIAN SPRINGS—TUNGSTEN

Alternate names: None

Commodities: W

LOCATION-OWNERSHIP

County	Elko.	General location	About 82 km northeast of Wells.
Mining district	Delano.	Meridian	Mount Diablo.
Elevation	2,047 m.	Tract	Sec. 10, T 43 N, R 68 E.
Topography	Rugged.	Latitude	41°37'29" N.
Domain	Mixed; private and BLM administered.	Longitude	114°14'46" W.

Owner: Norman Ludwig; AZL Resources, Inc., Phoenix, AZ; Utah International, Inc., San Francisco, CA (1981).
Operator: Utah International, Inc. (1981).

GEOLOGY

Type of ore body	Stockwork, replacement.	Host formation	Pequop.
Origin	Hydrothermal, contact metasomatic.	Geologic age	Upper Permian.
Shape of ore body	Irregular.	Rock relationships	Sandstone, ore in fractures, replaced by ore.
Ore controls	Contact zone, igneous.		
Strike and dip of mineralized zone.	N 30° E: 90° E.	Size	Large.
Mineralized zone average dimensions, m:			
Length	1,524.		
Width	150.		
Thickness	30.		
Depth	30.		

Mineral names: Scheelite, garnet, powellite, pyrite, chalcopyrite, molybdenite, galena, sphalerite, tetrahedrite, chalcocite, argentite, bornite, covellite, magnetite, goethite.

DEVELOPMENT

Current status	Inactive-developed deposit.	Distance to water supply	On-site.
		Road requirement	None.
Year of discovery	1951.	Distance to power supply	<50 km.
Discovery method	Ore mineral in place.		

Initial production: None.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	43,600,000 tons	0.164% WO_3	1970	147
2.. Do	13,900,000 tons	0.265% WO_3	1970	147

REFERENCES

147, 226, 278, 538, 661, 669.

USGS quad maps	Wells, 1:250,000. Delano Mountain, 15'.
USBM sequence number	0320070016.
USGS MRDS number	D002193.

JUNGLE—BARITE

Alternate names: Jungle A & B, Boies, Consolation, Jungle Extension, Ala

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.
Mining district	Snake Mountains.
Elevation	2,135 m.
Topography	Hilly.
Domain	Mixed; patented mining claims and located mining claims on public lands administered by BLM.
General location	About 48 km northeast of Wells.
Meridian	Mount Diablo.
Tract	Sec. 7, T 42 N, R 62 E.
Latitude	41°32′30″ N.
Longitude	114°59′42″ W.
Owner-operator	Chromalloy American Corp., St. Louis, MO (1983).

GEOLOGY

Type of ore body	Sedimentary.
Origin	Sedimentation, hydrothermal.
Shape of ore body	Tabular, irregular.
Ore controls	Bedding, lithology.
Strike and dip of mineralized zone.	Flat lying.
Mineralized zone average dimensions, m:	
Length	>180.
Width	170.
Thickness	8.5.
Depth	35.
Mineral names	Barite.
Host formation	Valmy.
Geologic age	Ordovician.
Rock relationship	Chert, encloses ore.
	Shale, encloses ore.
	Conglomerate, encloses ore.
Size	Medium.

DEVELOPMENT

Current status	Inactive-past producer (standby).
Type of operation	Surface.
Mining method	Open pit.
Year of discovery	1955.
Discovery method	Ore mineral in place.
Initial production	1977.
Last production	1981.
Past production	Confidential proprietary data.
Distance to water supply	>10 km.
Road requirement	None.
Distance to power supply	<50 km.
Mill location	Off-site 18 km east.
Mill status	Standby.
Milling method	Crushing, screening, jigging.
Product type	Unground barite concentrate.
Distance shipped	70 km to Wells, NV, by truck; then 2,350 km to Cyril, OK, by rail.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

77, 95, 123, 205, 226, 278, 546, 669, 688, 716, 775, 778.

USGS quad maps	Wells, 1:250,000. Boies Reservoir, 7.5′.
USBM sequence number	0320070357.
Mid number	2601098.

KAY–BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Nye.	General location	About 56 km southeast of Austin.
Mining district	Northumberland.	Meridian	Mount Diablo.
Elevation	2,820 m.	Tract	Sec. 14, T 13 N, R 45 E.
Topography	Rugged.	Latitude	38°57′50″N.
Domain	National forest.	Longitude	116°51′58″ W.

Owner: Chromalloy American Corp., St. Louis, MO (1983).

GEOLOGY

Type of ore body	Replacement	Host formation	Pinecone.
Origin	Sedimentation.	Geologic age	Devonian.
Shape of ore body	Irregular.	Rock relationships	Chert, encloses ore
Ore controls	Bedding, faulting.		Shale, encloses ore.
Strike and dip of mineralized zone.	N 45° E: 10° W.		Greenstone, encloses ore.
		Size	Medium.
Mineralized zone average dimensions, m:			
Length	Unknown.		
Width	Unknown.		
Thickness	1.5.		
Depth	11.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-explored.	Distance to water supply	On-site.
Type of operation	Possible surface.	Road requirement	On-site.
		Distance to power supply	<10 km.
Year of discovery	1958.	Mill location	No mill.
Discovery method	Ore mineral in place.		

Initial production: No production.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

338, 357, 368, 546, 623, 624.

USGS quad maps	Tonopah, 1:250,000. Northumberland, 7.5′.
USBM sequence number	0320230719.

LAKES--BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.	General location	About 46 km north of Carlin.
Mining district	Lakes.	Meridian	Mount Diablo.
Elevation	2,220 m.	Tract	Sec. 1, T 37 N, R 51 E.
Topography	Hilly.	Latitude	41°08'06" N.
Domain	Private.	Longitude	116°11'36" W.

Owner: 25 Corporation, Lincoln, NE; NL Baroid (a division of NL Industries, Inc., New York, NY--lessee) (1983).

GEOLOGY

Type of ore body	Bedded.	Host formation	Vinini.
Origin	Replacement.	Geologic age	Ordovician.
Shape of ore body	Tabular, massive.	Rock relationships	Chert, lies under ore, replaced by ore.
Strike and dip of mineralized zone.	S 45° W: 5° S.		Tuffs, lies over ore.
Mineralized zone average dimensions, m:		Size	Large.
Length	320		
Width	185.		
Thickness	45.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	<10 km.
Mining method	Open pit.	Distance to power supply	<10 km.
		Mill location	No mill.
Year of discovery	1955.		
Discovery method	Ore mineral in place.		
Initial production	1973.		
Last production	1981.		
Past production	Confidential proprietary data.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference..	8,000,000 tons	4.10 sp gr	1982	304

REFERENCES

87, 226, 304, 546, 669.

USGS quad maps	McDermitt, 1:250,000. Lake Mountain, 7.5'.
USBM sequence number	0320070354.
Mid number	2600959.

Comments: Ownership of the Lakes deposit has been the subject of 2.5 yr of litigation. In June 1982, the Nevada Supreme Court ruled in favor of NL Industries.

LINKA--TUNGSTEN

Alternate names: Garnetite, Spruce Mountain, Toiyabe Claims

Commodities: W, Mo

LOCATION-OWNERSHIP

County	Lander.
Elevation	1,800 m.
Domain	BLM administered.
General location	About 27 km southeast of Austin.
Meridian	Mount Diablo.
Tract	Sec. 18, T 17 N, R 45-1/2 E.
Latitude	39°19'00" N.
Longitude	116°50'00" W.
Owner	Consolidated Uranium Mines, Inc., Salt Lake City, UT (1972).

GEOLOGY

Type of ore body	Replacement, shear zone.
Origin	Contact metasomatism, hydrothermal.
Shape of ore body	Irregular.
Ore controls	Lithology, contact zone.
Mineralized zone average dimensions, m:	
Length	153.
Width	12.
Thickness	46.
Mineral names	Scheelite, quartz, garnet, epidote, calcite, molybdenite, pyrite.
Host formation	Antelope Valley.
Geologic age	Ordovician.
Rock relationships	Marble, lies along ore. Hornfels, lies along ore. Limestone, replaced by ore. Skarn, is ore, gangue.
Size	Small.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Surface-underground.
Year of discovery	1941.
Discovery method	Ore mineral in place.
Past production	Confidential proprietary data.
Distance to water supply	<3 km.
Distance to power supply	<50 km.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

404, 693, 733.

USGS quad maps	Millett, 1:250,000. Spencer Hot Springs, 15'.
USBM sequence number	0320150011.
USGS MRDS number	M030019.

MAGGIE CREEK–GOLD

Ore body names: Main, West

Commodities: Au

LOCATION-OWNERSHIP

County	Eureka.
Mining district	Maggie Creek (Schroeder).
Elevation	1,603 m.
Topography	Hilly.
Domain	Mixed, private, private lease, BLM administered.
General location	About 11 km north of Carlin.
Meridian	Mount Diablo.
Tract	Sec. 4, T 34 N, R 51 E.
Latitude	40°51′49″ N.
Longitude	116°14′47″ W.
Owner	Newmont Mining Corp., New York, NY (1985).
Operator	Carlin Gold Mining Co. (subsidiary of Newmont Mining Corp.) (1985).

GEOLOGY

Type of ore body	Disseminated, replacement, stratiform.
Origin	Hydrothermal, oxidation.
Shape of ore body	Tabular.
Ore controls	High-angle fault, northeast-trending fracture zone, lithology.
Strike of mineralized zone.	About N 30° E.
Age of mineralization	Mid-Tertiary.

Mineralized zone average dimensions, m:

	Main	West
Length	730	120
Width	60 to 180	120
Thickness	40 (estimated)	40 (estimated)

Pit area	85.7 ha (210 acres).
Mineral names	Native gold, pyrite, quartz, clays, carbon (not associated with gold), barite, chert, illite, kaolinite, montmorillonite.
Host formation	Roberts Mountains (upper plate of Roberts Mountains Thrust Fault).
Geologic age	Upper Silurian.
Rock relationships	Argillaceous dolomitic limestone, ore in fractures, replaced by ore, gangue. Siltstone, ore in fractures, replaced by ore, gangue. Shale, ore in fractures, replaced by ore, gangue. Sandstone, ore in fractures, gangue.
Alteration	Silicification, decarbonation, argillization.
Size	Small.

DEVELOPMENT

Current status	Active-producer.
Type of operation	Surface.
Mining method	Open pit, about 15,000 t/d ore and waste mined. Mining began in July 1980.
Year of discovery	1976–77.
Discovery method	Geological inference, drilling.
Initial production	April 1981 (leach facility commissioned).
Past production	987.19 kg (31,739 tr oz) Au from 240,794 t (265,430 tons) ore treated (1983) (*511*).
Annual production	450,000 t (500,000 tons) leaching grade ore; estimated 220,000 t (240,000 tons) milling grade.
Distance to water supply	On-site wells.
Road requirement	23 km to Carlin mill.
Distance to power supply	On-site diesel electric generation, 1,300 kW (four 275-kW units, one 200-kW standby unit).
Mill location	Heap leach–on-site; milling ore to Carlin mill.
Mill status	Active.
Milling methods	Leaching grade ore–cyanide agglomeration, cyanide heap leach, carbon adsorption, electrolysis, smelting. Milling grade–agitated cyanide leach, CCD, Merrill-Crowe zinc precipitation.
Process rate	Leaching grade–2,300 t/d (450,000 t/a). Milling grade–1,040 t/d is trucked and processed at Carlin mill.
Product type	Dore bullion approximately 950 fine.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	4,350,000 t[1]	3.20 g/t Au (milling plus leaching grade)	1980	435
2..Proven and probable	3,606,000 tons	0.079 tr oz/ton Au	1983	511
Above contains	2,202,000 tons	0.037 tr oz/ton Au	1983	511

REFERENCES

27, 59, 90, 129, 184, 319, 398, 400, 435, 505, 508, 511, 593, 688, 832.

USGS quad maps	Winnemucca, 1:250,000. Schroeder Mountain, 7.5′.
USBM sequence number	0320110182.
Mid number	2601635.

Comments: Maggie Creek deposit adjoins the Gold Quarry property.

[1]Published reserves consist of about 2.09 million t, 5.14 g/t Au milling grade ore, and 2.26 million t, 1.3 g/t Au leaching grade. Anticipated last year of production is 1986.

MAMMOTH–FLUORINE

Alternate names: Star Mine, Perkins Claim, Perkins Prospect, Pine Creek Prospect, Carlson Prospect, Rocket Group and Big Jim, Jumbo Prospect, Horseshoe, Northern Horseshoe, Higrade, White Horse, North Star Group

Commodities: CaF_2

LOCATION-OWNERSHIP

County	Nye.
Mining district	Quinn Canyon Range.
Elevation	2,256 m.
Topography	Hilly.
Domain	National forest.
Owner	Norman E. Wood (1976).
General location	About 101 km west of Caliente.
Meridian	Mount Diablo.
Tract	Sec. 2, T 3 N, R 56 E.
Latitude	38°09'04" N.
Longitude	115°39'20" W.

GEOLOGY

Type of ore body	Breccia fill, replacement.
Origin	Hydrothermal.
Shape of ore body	Irregular, lenticular.
Ore controls	Lithology, contact zone.
Strike and dip of mineralized zone.	N 15° E: 15° to 30° W.
Mineralized zone average dimensions, m:	
Length	229.
Width	30.
Thickness	30.
Mineral names	Fluorspar, jasper, calcite.
Host formation	Antelope Formation.
Geologic age	Ordovician.
Rock relationships	Limestone, ore in fractures, replaced by ore.
Host formation	Shingle Pass.
Geologic age	Tertiary.
Rock relationships	Unspecified extrusive, ore in fractures.
Host formation	Needles Range.
Geologic age	Tertiary.
Rock relationships	Unspecified extrusive, ore in fractures.
Size	Medium.

DEVELOPMENT

Current status	Inactive-explored prospect.
Type of operation	Surface.
Year of discovery	1943.
Discovery method	Ore mineral in place.
Distance to water supply	<3 km.
Road requirement	None.
Distance to power supply	<50 km.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

281, 283, 357, 545, 604, 733, 815, 816.

USGS quad maps	Lund, 1:250,000.
USBM sequence number	0320230202.

MANHATTAN–GOLD

Related names: Houston Oil & Minerals Manhattan (HIMCO) Project Claim Group includes Big Four, Mayflower, Reilly Fraction, Iron Queen, Iron King, Gold Wedge, Little Grey, Jumping Jack, June, St. George, Stray Dog, Skookum

Commodities: Au, Ag

LOCATION-OWNERSHIP

County	Nye.
Mining district	Manhattan.
Elevation	1,290 m.
Topography	Hilly.
Domain	Private.
General location	About 56 km northeast of Tonopah.
Meridian	Mount Diablo.
Tract	Sec. 23, T 8 N, R 44 E.
Latitude	38°32′19″ N.
Longitude	117°00′31″ W.
Owner-operator	Tenneco Minerals Corp., Inc., Houston, TX (1985). (Mining is by contractor--W.E. Vining, Carson City, NV.)

GEOLOGY

Type of ore body	Disseminated, stockwork-quartz veining.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Faults, fractures (joints).
Age of mineralization	Miocene (16 million yr.)
Mineral names	Free gold, electrum, quartz, calcite, adularia, manganese oxide, pyrite, iron oxide.
Host formation	Gold Hill.
Geologic age	Cambrian.
Rock relationships	Schist, ore in fractures, gangue. Pyrite, shale, ore in fractures, gangue. Quartzite, sandstone, ore in fractures, gangue.
Alteration	Pyritization.
Size	Small.

DEVELOPMENT

Current status	Active-producer
Type of operation	Surface.
Mining method	Open pit (by contract); about 2,700 t/d ore.
Year of discovery	1866, silver first discovered in district; 1905, gold discovered.
Discovery method	Geochemical, drilling.
Initial production	1980 by HIMCO; late 1983 for Tenneco.
Last production	Late 1982 by HIMCO; ongoing for Tenneco (1985).
Annual production rate	Between 810 kg Au and 840 kg Au anticipated (26,000 to 27,000 tr oz).
Distance to water supply	On-site.
Road requirement	Existing.
Distance to power supply	Unknown.
Mill location	On-site.
Mill status	Active.
Milling method	Gravity concentration, flotation, batch cyanide agitated leach, Merrill-Crowe zinc precipitation.
Process rate	Crusher about 2,700 t/d; flotation about 1,369 t/d.
Product type	Au-Ag precipitate.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1...Proven	5,000,000 tons	0.036 tr oz/ton Au	1983	311

REFERENCES

90, 136, 191, 192, 194, 311, 357, 368, 378, 494, 584, 719, 768.

USGS quad maps	Tonopah, 1:250,000. Manhattan, 7.5′.
USBM sequence number	0320230395.
Mid number	2601566.

Comments: The mine was temporarily shut down between January 1982 and fall of 1983.

McARTHUR–COPPER

Alternate names: None

Commodities: Cu

LOCATION-OWNERSHIP

County	Lyon.	General location	About 45 km southeast of Carson City.
Mining district	Mason.		
Elevation	1,438 m.	Meridian	Mount Diablo.
Topography	Gentle.	Tract	Sec. 25, T 14 N, R 24 E.
Domain	Mixed; private and BLM administered.	Latitude	39°02′56″ N.
		Longitude	119°14′17″ W.

Owner: The Anaconda Minerals Co., Denver, CO (a wholly owned subsidiary of Atlantic Richfield Co., Denver, CO) (1979).

GEOLOGY

Type of ore body	Replacement, breccia fill.	Host formation	Igneous intrusive.
Origin	Contact metasomatic, hydrothermal.	Geologic age	Mesozoic.
Shape of ore body	Unknown.	Rock relationships	Quartz monzonite, replaced by ore, gangue.
Ore controls	Igneous, fracturing, faulting.		Breccia, encloses ore, gangue.
Strike of mineralized zone.	N 70° W.	Size	Large.
Mineral names	Chalcocite, pyrite, chalcopyrite, cuprite, malachite.		

DEVELOPMENT

Current status	Inactive-explored prospect.	Distance to water supply	<10 km.
		Road requirement	<10 km.
Discovery method	Trenching, drilling.	Distance to power supply	<10 km.
Last production	1943.		
Past production	Reported 5 carloads ore shipped in 1943 (*695*).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	13,000,000 tons	0.43% Cu	1976	822

REFERENCES

126, 128, 453, 567, 695, 822, 824.

USGS quad maps	Reno, 1:250,000. Wabuska, 15′.
USBM sequence number	0320190023.

Comments: Extensive exploration done by the Bureau in 1948–50; further drilling done by Anaconda Co. in 1974.

McDERMITT–MERCURY

Alternate names: None

Commodities: Hg

LOCATION-OWNERSHIP

County ..... Humboldt.
Mining district ..... Opalite (Cordero).
Elevation ..... 1,402 m.
Topography ..... Flat.
Domain ..... Mixed; BLM administered, public lands-private.
General location ..... About 10 km southwest of McDermitt.
Meridian ..... Mount Diablo.
Tract ..... Sec. 27, T 47 N, R 37 E.
Latitude ..... 41°55'13" N.
Longitude ..... 117°48'37" W.

Owner-operator ..... Placer U.S. Inc., San Francisco, CA (subsidiary of Placer Development Ltd., Vancouver, BC, Canada), 51% (1983).
Owner ..... Sterling Mineral Venture, 49% (1983).

GEOLOGY

Type of ore body ..... Sedimentary, replacement.
Origin ..... Hydrothermal, sedimentation.
Shape of ore body ..... Tabular overall.
Ore controls ..... Faulting, bedding.
Strike and dip of mineralized zone. N 45° W: 4° E.
Age of mineralization ... Miocene.
Mineralized zone average dimensions, m:
Length ..... 760.
Width ..... 670.
Thickness ..... 6.
Depth ..... 30.
Mineral names ..... Cinnabar, corderoite, montmorillonite, chalcedony, iron and manganese oxides, calcite, cristobalite, gypsum, alunite, apatite, stibnite, alpha tridynite.
Host formation ..... Tuffaceous sediment (lake beds).
Geologic age ..... Miocene.
Rock relationships ..... Clay, is ore, encloses ore.
Chert, under ore, is ore.
Alteration ..... Argillic.
Size ..... Medium.

DEVELOPMENT

Current status ..... Active-producer.
Type of operation ..... Surface.
Mining method ..... Open pit; overall stripping ratio is about 4.7:1 waste:ore.
Year of discovery ..... 1941 (drill penetration of ore body).
Discovery method ..... Geological inference.
Initial production ..... 1975 (stripping began in 1974).
Past production ..... 237,000 t, 4.51 kg/t Hg ore milled; 489,000 kg Hg metal production (1981) (*564*).
273,000 t, 4.06 kg/t Hg ore milled; 452,000 kg Hg metal production (1982) (*564*).
Annual production rate . About 240,000 t ore and 20,000 flasks.
Distance to water supply ... On-site wells.
Road requirement ..... None.
Distance to power supply ... On-site.
Mill location ..... On-site.
Mill status ..... Active.
Milling method ..... Flotation, distillation.
Process rate ..... 2,200 t/d ore, 90 t/h (furnace--0.45 t/h Hg concentrate).
Product type ..... Refined mercury.
Distance shipped ..... 4,348 km.
Destination ..... New York, NY, and various other national locations.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Indicated	3,000,000 tons	10 lb Hg/ton	1976	596
2..Measured	1,648,000 t	0.5 wt pct Hg	1980	563
3.. Do	1,410,000 t	5.15 kg/t Hg	1981	564
4.. Do	1,202,000 t	4.44 kg/t Hg	1982	564

REFERENCES

7, 29, 104, 202, 229, 276, 406, 466, 468, 474, 563, 564, 596, 602, 615, 639, 642, 643, 673, 725, 801, 845.

USGS quad maps ..... McDermitt, 1:250,000.
Jordan Meadows, 15'.
USBM sequence number ..... 0320130259.
USGS MRDS number ..... MO54731.
Mid number ..... 2600646.

Comments: Largest mercury producer in the United States. Individual ore bodies are asymmetric lenslike bodies that thin and decrease in grade away from hot spring centers of mineralization. Reported final pit depth will be about 50 m. The ore body is estimated to contain 400,000 flasks of mercury.

McGILL TAILINGS—COPPER

Alternate names: Keystone Dumps

Commodities: Cu

LOCATION-OWNERSHIP

County	White Pine.	General location	About 19 km northeast of Ely.
Mining district	Robinson Canyon.	Meridian	Mount Diablo.
Elevation	1,865 m.	Tract	Sec. 29, T 18 N, R 64 E.
Topography	Gentle.	Latitude	39°23'55" N.
Domain	Private.	Longitude	114°47'44" W.

Owner: Kennecott Copper Corp., Salt Lake City, UT (1984).

GEOLOGY

Type of ore body	Mill waste, tailings.	Identified resources	Medium.

DEVELOPMENT

Current status	Inactive-explored.	Distance to water supply	On-site.
Mining method	Surface.	Road requirement	None.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	40,000,000 to 80,000,000	0.3 to 0.4% Cu	1979	413

REFERENCES

160, 284, 413, 473, 477.

USGS quad maps	Ely, 1:250,000. McGill, 15'.
USBM sequence number	0320330056.

Comments: The tailings deposit at McGill represents a 70-yr accumulation of tailings from the adjacent concentrator. Over the years the "natural classification of the coarse and heavy particles resulted in a deposit of minable grade copper-bearing material suitable for concentrating and smelting" (*473*). In 1978–79, Kennecott conducted exploration and feasibility studies on the deposit. In the fall of 1979, Kennecott announced that recovery of copper from about 800 ha (2,000 acres) awaited only a corporate go-ahead. It was stated that an investment of $15 million would be required and would "pay for itself in less than a year" (*160*). The plan was to use conveyors to transport 9.5 million t (10.5 million tons) annually back to the mill and smelter facilities for reprocessing. Recycling of the 0.5% Cu tailings would take between 8 and 10 yr (*160*).

MINNESOTA—IRON

Alternate names: Standard Slag Mine, Minnesota Copper Lode Claim

Commodities: Fe

LOCATION-OWNERSHIP

County	Douglas.
Mining district	Buckskin.
Elevation	1,823 m.
Topography	Hilly.
Domain	Mixed; private and BLM administered.
General location	About 38 km southeast of Carson City.
Meridian	Mount Diablo.
Tract	Sec. 19, T 14 N, R 24 E.
Latitude	39°04'04" N.
Longitude	119°20'00" W.

Owners: V. Cox; J. Adams; A. J. Hawkins; M. Russell; L. J. Anderson; Standard Slag Co., Reno, NV (1975).

GEOLOGY

Type of ore body	Replacement.
Origin	Contact metasomatic.
Shape of ore body	Irregular.
Ore controls	Faulting, lithology.
Mineralized zone average dimensions, m:	
Length	244.
Width	152.
Thickness	122.
Mineral names	Magnetite, hematite, dolomite, pyrite, chalcopyrite, martite, magnesite, malachite, chlorite, sericite.
Host formation	Sedimentary Series.
Geologic age	Triassic.
Rock relationships	Dolomite, replaced by ore, gangue.
Size	Small.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Surface.
Mining method	Surface.
Year of discovery	1900.
Discovery method	Auxiliary mineral in place.
Initial production	1916.
Last production	1967.
Past production	4,000,000 t ore and concentrate through 1967 (*454*).
Distance to water supply	<3 km.
Road requirement	None.
Distance to power supply	On-site.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

296, 381, 453, 454, 580.

USGS quad maps	Reno, 1:250,000. Como, 15'.
USBM sequence number	0320050021
USGS MRDS number	W016379.

MODARELLI—IRON

Alternate names: Amarilla Deposit, Requa Mine, Simplot Mine

Commodities: Fe

LOCATION-OWNERSHIP

County	Eureka.
Mining district	Modarelli.
Elevation	2,067 m.
Topography	Very rugged.
Domain	Private.
Owner	Linda and Vincent Modarelli (1981).
Owner-operator	J. R. Simplot Co., Boise, ID (1981).
General location	About 39 km south of Carlin.
Meridian	Mount Diablo.
Tract	Sec. 30, T 29 N, R 51 E.
Latitude	40°21′59″ N.
Longitude	116°15′44″ W.

GEOLOGY

Type of ore body	Replacement, stockwork.
Origin	Contact metasomatic.
Shape of ore body	Irregular.
Ore controls	Faulting.
Strike and dip of mineralized zone.	N 45° W: 60° N.
Mineral names	Hematite, magnetite, quartz, calcite, apatite.
Host formation	Older Volcanic Series.
Geologic age	Oligocene.
Rock relationships	Tuff, near ore, Dacite, near ore. Latite, near ore. Rhyolite, replaced by ore, ore in fractures. Andesite, lies under ore.
Size	Medium.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Surface.
Year of discovery	1903.
Discovery method	Ore mineral in place.
Initial production	1951.
Last production	1959.
Past production	406,000 t mined between 1951–59 (*454*).
Distance to water supply	On-site.
Road requirement	None.
Distance to power supply	<50 km.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Indicated	44,000,000 long tons.	42.75% Fe, 1.05% P_2O_5	1971	454

REFERENCES

10, 75, 150, 235, 282, 324, 332, 366, 454, 462, 536, 568, 583, 593, 625, 733, 751.

USGS quad maps	Winnemucca, 1:250,000. Frenchie Creek, 15′.
USBM sequence number	0320110028.
USGS MRDS number	W016363.

MONTANA MOUNTAINS—LITHIUM

Alternate names: McDermitt Caldera Lithium; Kings River Lithium; Uravada

Commodities: Li, U

LOCATION-OWNERSHIP

County	Humboldt.	General location	About 48 km southwest of McDermitt.
Mining district	None; closest is Opalite (McDermitt), 38 km northeast.	Meridian	Mount Diablo.
		Tract	Sec. 24, T 45 N, R, 34 E.
Elevation	2,080 m.	Latitude	41°45'44" N.
Domain	Public, BLM administered.	Longitude	118°06'29" W.

Owners: J. M. Huber Corp., Macon, GA (1984); Chevron Resources, Denver, CO (1984); Jim and Grace LeBret, Frank and Ann Bengoa, Orovada, NV (1984); Norman LeBret, Priscilla Vaagen, George and Lynn LeBret, Spokane, WA (1984).

GEOLOGY

Type of ore body	Volcanic moat deposits.	Host formation	Tuffaceous sediments.
Origin	Hydrothermal, hot springs.	Geologic age	Tertiary.
Shape of ore body	Tabular.	Rock relationships	Hectorite, is ore.
Ore controls	Hot springs vent zones, moat sediments.	Alteration	Zeolite.
Strike and dip of mineralized zone.	Horizontal.	Size	Large.
Age of mineralization	Tertiary.		
Mineralized zone average dimensions, m:			
Length	15,000.		
Width	1,000.		
Thickness	75.		
Depth	75.		
Mineral names	Smectite, calcite, chalcedony, analcime.		

DEVELOPMENT

Current status	Active-exploration.	Distance to water supply	5 km.
Type of operation	Possible surface.	Road requirement	Paved haul road.
Mining method	Open pit.	Distance to power supply	5 km.
Year of discovery	1979.		
Discovery method	Field mapping, drilling.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

108, 125, 155, 221, 244, 379, 396, 397, 602, 603, 638, 801.

USGS quad maps	McDermitt, 1:250,000. Disaster Peak, 15'.
USBM sequence number	0320130482.

Comments: Potentially the largest single lithium resource in the United States containing a drill-hole-indicated resource of 200 million t averaging 1.2% Li_2O.

MOUNT HOPE—MOLYBDENUM

Alternate names: Whim Shaft, Lorraine Workings, Nevada Morn Prospect

Commodities: Mo, Zn, Cd, Pb, Cu, Ag, Au

LOCATION-OWNERSHIP

County	Eureka.	General location	About 34 km southeast of Eureka.
Mining district	Mt. Hope.	Meridian	Mount Diablo.
Elevation	2,240 m.	Tract	Sec. 18, T 22 N, R 52 E.
Topography	Rugged.	Latitude	39°47'15" N.
Domain	BLM administered.	Longitude	116°09'29" W.
Owner	EXXON Corp., New York, NY (1982).		

GEOLOGY

Type of ore body	Stockwork, disseminated porphyry molybdenum.	Host formation	Quartz porphyry (major host).
Origin	Contact metasomatic, hydrothermal.	Geologic age	Mid-Tertiary.
Shape of ore body	Stockwork.	Size	Large.
Ore controls	Igneous, faulting, fracturing.		
Pit average dimensions (proposed), km:			
Length	2.		
Width	1.75.		
Mineral names	Molybdenite; other minerals unknown.		

DEVELOPMENT

Current status	Active-developing-exploration.	Distance to water supply	16 km.
Type of operation	Surface (proposed).	Road requirement	None.
Mining method	Open pit; mining 27,000 t/d ore, using large electric shovels was proposed.	Distance to power supply	32 km.
		Mill location	On-site.
		Mill status	Proposed.
Year of discovery	1870 (Pb and Zn); 1981 (Mo discovery announced).	Milling method	Concentrator, hydrometallurgical, conversion plant (proposed).
Discovery method	Drilling, geochemistry.	Product type	Molybdic acid, ferromolybdenum (proposed).
Initial production	1886.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	450,000,000 tons	0.13% to 0.32% MoS_2	1981	383

REFERENCES

383, 395, 448, 593, 793, 813, 837.

USGS quad maps	Millett, 1:250,000. Garden Valley, 15'.
USBM sequence number	0320110037.
USGS MRDS number	W016396.
Mid number	2601132.

Comments: Molybdenum was first observed in a drill hole drilled by Phillips Petroleum in 1970–71. The higher grade mineralization is reported to occur where the asymmetric halos of alteration and molybdenum mineralization merge around 2 deep coaxial stocks. Molybdenite has been reported to occur at depths ranging from 46 m to 960 m.

MOUNT WHEELER—BERYLLIUM

Alternate names: Pole Adit

Commodites: Be, CaF_2, W

LOCATION-OWNERSHIP

County	White Pine.	General location	About 60 km southeast of Ely.
Mining district	Mt. Washington.	Meridian	Mount Diablo.
Elevation	2,377 m.	Tract	Sec. 16, T 12 N, R 68 E.
Topography	Very rugged.	Latitude	38°53'50" N.
Domain	National forest.	Longitude	114°20'16" W.

Owner: Mt. Wheeler Mines, Inc., Salt Lake City, UT (1983).

GEOLOGY

Type of ore body	Replacement, fissure vein, shear zone.	Host formation	Pioche Shale.
Origin	Unknown.	Geologic age	Cambrian.
Shape of ore body	Lenticular.	Rock relationships	Limestone, replaced by ore.
Ore controls	Fracturing, bedding.		Shale, lies over ore.
Mineralized zone average dimensions, m:			Shale, lies under ore.
		Size	Large.
Length	1,000.		
Width	8.		
Thickness	5.		
Depth	0.		
Mineral names	Phenacite, fluorite, scheelite, beryl, bertrandite.		

DEVELOPMENT

Current status	Inactive-developed.	Distance to water supply	On-site.
Type of operation	Possible underground.	Road requirement	None.
		Distance to power supply	<10 km.
Year of discovery	1959.	Mill location	No mill.
Discovery method	Auxiliary minerals in place.		
Initial production	No production.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

119, 122, 249, 250, 275, 284, 359, 679, 797, 798.

USGS quad maps	Lund, 1:250,000.
	Wheeler Peak, 15'.
USBM sequence number	0320330039.
USGS MRDS number	D001197.

MOUNTAIN SPRINGS—BARITE

Alternate names: FMC Mine

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Lander.	General location	About 39 km south of Carlin.
Mining district	Mountain Springs.	Meridian	Mount Diablo.
Elevation	1,563 m.	Tract	Sec. 8, T 28 N, R 44 E.
Topography	Rolling.	Latitude	40°18'25" N.
Domain	Mixed, BLM administered.	Longitude	117°02'26" W.

Owner..... FMC Corp. Inc., Chicago, IL (1984).
Operator..... FMC Corp. Inc.; IMCO Services—milling (a wholly owned subsidiary of Halliburton Co., Dallas, TX) (1984).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Slaven.
Origin	Sedimentation.	Geologic age	Devonian.
Shape of ore body	Tabular.	Rock relationships	Chert, lies over ore, encloses ore.
Ore controls	Bedding, lithology.		Limestone, lies over ore.
Strike and dip of mineralized zone.	N 30° W: 45° S.	Size	Large.
Mineralized zone average dimensions, m:			
Length	244.		
Width	36.		
Thickness	30.		
Depth	0.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	On-site.
		Mill location	On-site.
Year of discovery	1947.	Mill status	Producer-standby.
Discovery method	Ore mineral in place.	Milling method	[1].
		Process rate	FMC—63,000 t/a; IMCO—400,000 t/a.
Initial production	1952.	Product type	Crushed concentrated barite.
Last production	Ongoing.	Distance shipped	44 km.
Past production	Confidential proprietary data.	Destination	Battle Mountain, NV.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

78, 87, 131, 173, 315, 330, 346, 347, 385, 392, 546, 548, 601, 688, 693, 735.

USGS quad maps	Winnemucca, 1:250,000. McCoy, 15'.
USBM sequence number	0320150072.
Mid number	2600401.

[1]FMC Corp. operates a small crushing and screening plant; IMCO Services operates a large beneficiation plant. The IMCO plant incorporates jigging, tabling, and flotation concentrating techniques.

NEVADA MOLY—MOLYBDENUM

Alternate names: Anaconda-Nevada Moly Prospect, Hall Copper, Hall Hand Property, Liberty Mine, San Antonio Mine, Hall Molly

Commodites: Mo, Cu, Ag, Au

LOCATION-OWNERSHIP

County	Nye.	General location	About 27 km northwest of Tonopah.
Mining district	San Antone.	Meridian	Mount Diablo.
Elevation	1,798 m.	Tract	Sec. 5, T 5 N, R 42 E.
Topography	Hilly.	Latitude	38°19'23" N.
Domain	Mixed.	Longitude	117°17'31" W.

Owner-operator ..... The Anaconda Minerals Co., Denver, CO (a wholly owned subsidiary of Atlantic Richfield Co., Denver, CO) (1984).

GEOLOGY

Type of ore body	Replacement, stockwork, disseminated.	Host formation	Valmy.
Origin	Hydrothermal, oxidation.	Geologic age	Ordovician.
Shape of ore body	Pipelike, cylindrical.	Rock relationships	Quartz porphyry, is ore. Metamorphosed sediments, ore in fractures, along bedding planes.
Ore controls	Contact zone, igneous, faulting.		
Strike and dip of mineralized zone.	N 45° E: 15° to 50° E.	Size	Large.
Mineralized zone average dimensions, m:			
Length	760.		
Width	760.		
Thickness	40.		
Depth	3.		
Mineral names	Creedite, chalcopyrite, pyrite, sphalerite, chalcocite, molybenite, pyrrhotite, malachite, azurite, powellite, limonite, galena.		

DEVELOPMENT

Current status	Active-producer.[1]	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit, conventional truck and shovel with 14-m benches.	Distance to power supply	On-site.
		Mill location	On-site.
		Mill status	Operating.
Year of discovery	1863.	Milling method	Two-product bulk flotation.
Discovery method	Ore mineral in place.	Process rate	20,000 t/d (full capacity).
		Product type	MoS_2 concentrate to leach plant; Cu concentrate to smelter. MoS_2 product capacity is estimated 7,260 t/a.
Production	Full production capabilities reached in December 1981.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	455,000,000 t	0.072% Mo, 0.06% Cu	1983	736

REFERENCES

26, 161, 181, 196, 279, 310, 355, 357, 368, 402, 420, 469, 472, 475, 599, 608, 619, 736, 759, 813, 837, 842.

USGS quad maps	Tonopah, 1:250,000. San Antonio Ranch, 15'.
USBM sequence number	0320230005.
USGS MRDS number	M030038.

Comments: Eighty percent of resource is in the quartz porphyry intrusive.

[1]The Nevada Moly Mine indefinitely suspended operations in January 1985 because of poor market conditions.

NEVADA SCHEELITE—TUNGSTEN

Alternate names: Leonard Mine

Commodities: W, Cu, Mo

LOCATION-OWNERSHIP

County	Mineral.	General location	About 58 km northeast of Hawthorne.
Mining district	Regent-Rawhide.	Meridian	Mount Diablo.
Elevation	1,555 m.	Tract	Sec. 1, T 13 N, R 32 E.
Topography	Hilly.	Latitude	39°01'00" N.
Domain	BLM administered.	Longitude	118°19'30" W.

Owner-operator ..... Natural Resources Development Ltd., Reno, NV (subsidiary of NRD Mining, Ltd., Vancouver, BC, Canada) (1982).

GEOLOGY

Type of ore body	Shear zone, replacement.	Host formation	Luning.
Origin	Contact metasomatic, hydrothermal.	Geologic age	Triassic.
Shape of ore body	Tabular, irregular.	Rock relationships	Granite, lies along ore, lies over ore.
Ore controls	Contact zone, lithology.		Skarn (tactite), is ore.
Strike and dip of mineralized zone.	N 25° E: 80° E.		Limestone, lies along ore, replaced by ore.
Mineralized zone average dimensions, m:			Hornfels, lies along ore, near ore.
Length	2,000.		Tuff, near ore.
Width	20.	Size	Large.
Mineral names	Scheelite, wollastonite, garnet, pyrite, chalcopyrite, molybdenite, magnetite, epidote, calcite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	<10 km.
Type of operation	Underground.	Road requirement	None.
Mining method	Overhand square set.	Distance to power supply	On-site.
		Mill location	On-site; mill dismantled 1984.
Year of discovery	1930.	Product type	WO_3 concentrate (65%).
Discovery method	Ore mineral in place.	Distance shipped	90 km by truck.
		Destination	Fallon, NV (Kennametal).
Initial production	1937.		
Last production	1982.		
Past production	301,000 stu[1] of WO_3 (*704*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

215, 275, 598, 704, 733, 740, 774.

USGS quad maps	Reno, 1:250,000.
	Big Kasock Mountain, 7.5'.
USBM sequence number	0320210033.
Mid number	2600614.

[1]stu = short ton unit = 20 lb of contained WO_3.

NORTHUMBERLAND—GOLD

Alternate names: Cyprus Northumberland
Ore body names: Chipmunk, Main

Commodities: Au, Ag
(Au-Ag ratio = 2:1)

LOCATION-OWNERSHIP

County	Nye.	General location	About 120 km northeast of Tonopah.
Mining district	Northumberland.	Meridian	Mount Diablo.
Elevation	2,600 m.	Tract	Sec. 24, T 13 N, R 45 E (unsurveyed).
Topography	Rugged.	Latitude	38°57'29" N.
Domain	National forest.	Longitude	116°50'44" W.

Owner-operator ..... Cyprus Northumberland Mining Co., Austin, NV (subsidiary of Amoco Metals Co., Englewood, CO) (1983).

GEOLOGY

Type of ore body	Disseminated, stratabound, replacement.	Host formations	Vinini.
Origin	Hydrothermal.		Roberts Mountains.
Shape of ore body	Irregular, relatively tabular or flat.	Geologic ages	Ordovician.
Ore controls	Faults, igneous contact, fractures, lithology.		Silurian.
Strike of mineralized zone.	West-northwest.	Rock relationships	Tuff, lies above ore.
Age of mineralization	Late Cretaceous (84.6 million yr).		Carbonaceous shales, contains disseminated gold (Vinini).
Mineralized zone average dimensions			Calcareous siltstone, contains disseminated gold (Vinini).
Length	1,100.		Jasperoid replaced limestone, portions are ore, lies above ore.
Width	240.		Jurassic granitic intrusive, occurs as sills in host rocks, is mineralized.
Thickness	18 to 21.		
Depth	0 to 9 (Main).		
Mineral names	Gold, arsenopyrite, pyrite, stibnite, realgar, orpiment, cinnabar, calcite, quartz, jasperoid, dolomite, barite, carbon.	Alteration	Silicification, argillic (Paleozoic), sericitic (intrusive).
		Size	Small.

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	On-site, 3 wells at mill.
Type of operation	Surface.	Distance to power supply	On-site, diesel electric generator.
Mining method	Conventional open pit; mine about 4,500 t/d ore.	Mill location	Off-site, 14 km.
		Mill status	Active.
		Milling method	Cyanide heap leach, carbon adsorption columns, stripping, electro-winning, smelting.
Year of discovery	1936 (low-grade gold in district).		
Discovery method	Surface sampling and drilling.	Process rate	Crusher—4,500 t/d (5,000 ton/d), 5 d/wk.
Initial production	Early 1981 (Cyprus-Amoco).		
Annual production rate	About 620 kg Au (20,000 tr oz).	Product type	Au-Ag dore bullion.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven	6,000,000 tons	0.065 tr oz/ton Au	1979	831
2..Not reported in reference	17,000,000 tons	0.045 tr oz/ton Au	1981	61

REFERENCES

60, 61, 207, 222, 232, 338, 357, 368, 403, 404, 405, 461, 480, 539, 599, 601, 616, 623, 624, 630, 692, 752, 761, 773, 831.

USGS quad maps	Tonopah, 1:250,000. Northumberland Pass, 7.5'.
USBM sequence number	0320230403.
Mid number	2601661.

Comments: Ore reportedly occurs in and adjacent to a thrust fault separating lower plate Roberts Mountains Formation from upper plate Vinini Formation. Amoco 1983 operational plans were to mine the Main ore body to completion in 1985, then mine the Chipmunk ore body from 1985 to 1993. The crusher is co-located with the ore bodies; crushed ore is hauled west to the leaching facility at the mouth of West Northumberland Canyon in Big Smoky Valley. Ore heaps for leaching will be constructed at the rate of 5 to 6 per year. Heaps measure about 1,000 m long, 46 m wide, and 6 m high.

NYCO—FLUORINE

Alternate names: Spar #1 – 3

Commodities: CaF_2

LOCATION-OWNERSHIP

County	Nye.	General location	About 117 km west of Pioche.
Mining district	Quinn Canyon Range.	Meridian	Mount Diablo.
Elevation	2,560 m.	Tract	Sec. 34, T 3 N, R 55 E.
Topography	Hilly.	Latitude	38°04′42″ N.
Domain	National forest.	Longitude	115°46′05″ W.

Owner: C. Solan, 33%; W. Stable, 33%; Don W. Terrill, 33% (1981).
Operator: Teledyne Wah Chang (subsidiary of Teledyne Industries, Los Angeles, CA) (1957).

GEOLOGY

Type of ore body	Fissure vein, breccia fill.	Host formation	Shingle Pass Tuff.
Origin	Hydrothermal.	Geologic age	Tertiary.
Shape of ore body	Lenticular.	Rock relationships	Tuff, ore in fractures.
Ore controls	Faulting.	Size	Medium.
Strike and dip of mineralized zone.	N 80° E: 49° N.		
Mineralized zone average dimensions, m:			
Length	91.		
Width	91.		
Thickness	9.		
Mineral names	Fluorite, sericite, kaolinite, quartz, pyrite.		

DEVELOPMENT

Current status	Inactive-past producer.	Road requirement	<10 km.
Type of operation	Underground.	Distance to power supply	<50 km.
Year of discovery	1950.		
Discovery method	Ore mineral in place.		
Initial production	1951.		
Last production	Undetermined.		
Past production	998 t.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

281, 283, 357, 545, 604, 733, 815, 816.

USGS quad maps	Lund, 1:250,000.
USBM sequence number	0320230201.

OVERTON—MAGNESITE

Alternate names: None

Commodities: MgO

LOCATION-OWNERSHIP

County	Clark.	General location	About 20 km southeast of Moapa.
Mining district	Overton.	Meridian	Mount Diablo.
Elevation	463 m.	Tract	Sec. 34, T 16 S, R 67 E.
Topography	Hilly.	Latitude	36°30'05" N.
Domain	BLM administered.	Longitude	114°29'04" W.
Owner	Laura Gentry, Las Vegas, NV (1983).		

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Horse Spring.
Origin	Sedimentation.	Geologic age	Tertiary.
Shape of ore body	Tabular, lenticular.	Rock relationships	Siltstone, lies under ore.
Ore controls	Bedding.		Dolomite, replaced by ore, gangue.
Strike and dip of mineralized zone.	N 20° W: 34° E.		Siltstone, lies over ore.
			Conglomerate, lies over ore.
Mineralized zone average dimensions, m:		Size	Medium.
Length	3,000.		
Width	18.		
Thickness	90.		
Depth	12.		
Mineral names	Magnesite, quartz, feldspar, plagioclase, dolomite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	<3 km.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	<10 km.
		Mill location	No mill.
Year of discovery	1915.		
Discovery method	Ore mineral in place.		
Initial production	Unknown.		
Last production	Unknown.		
Past production	Small—data not available.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	850,000 tons[1]	38% MgO (minimum)	1936	266
2.. Do	3,700,000 tons[1]	34% MgO (minimum)	1936	266
3.. Do	5,100,000 tons[1]	30% MgO (minimum)	1936	266

REFERENCES

266, 386.

USGS quad maps	Las Vegas, 1:250,000. Overton, 15'.
USBM sequence number	0320030011.

[1]In beds 6 in. or more thick. Tonnages are cumulative.

P & S—BARITE

Alternate names: Old Soldier Mine

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Nye.
Mining district	Northumberland.
Elevation	2,440 m.
Topography	Rugged.
Domain	National forest.
Owner	Standard Slag Co., Reno, NV (1983).
General location	About 62 km southeast of Austin.
Meridian	Mount Diablo.
Tract	Sec. 14, T 13 N, R 45 E.
Latitude	38°58'11" N.
Longitude	116°52'47" W.

GEOLOGY

Type of ore body	Stratiform.
Origin	Sedimentation, metamorphism.
Shape of ore body	Lenticular.
Ore controls	Bedding.
Strike and dip of mineralized zone.	N 45° E: 15° E.
Mineralized zone average dimensions, m:	
Length	160.
Width	135.
Thickness	36.
Depth	50.
Mineral names	Barite.
Host formation	Pinecone.
Geologic age	Middle Devonian.
Rock relationships	Chert, encloses ore, gangue.
	Quartzite, encloses ore, gangue.
	Siltstone, encloses ore, gangue.
	Shale, encloses ore, gangue.
	Dacite, near ore.
Size	Medium.

DEVELOPMENT

Current status	Active-producer.
Type of operation	Surface.
Mining method	Open pit.
Year of discovery	1961.
Discovery method	Unknown.
Initial production	1977.
Last production	1985.
Past production	713,782 t ore (1978–80) (*16*).
Distance to water supply	On-site.
Road requirement	None.
Distance to power supply	<100 km.
Mill location	Fallon, NV.
Mill status	Active.
Milling method	Flotation.
Process rate	130 t/d.
Product type	Crushed barite.
Distance shipped	695 km.
Destination	Bakersfield, CA.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

16, 87, 338, 357, 368, 546, 623, 624.

USGS quad maps	Tonopah, 1:250,000.
	Jet Springs, 7.5'.
USBM sequence number	0320230716.
Mid number	2600823.

PAN AMERICAN—LEAD-ZINC

Alternate names: St. Patrick Mining Co.

Commodities: Zn, Pb, Ag, Au, Mn, Fe

LOCATION-OWNERSHIP

County	Lincoln.	General location	About 15 km southwest of Pioche.
Mining district	Comet.	Meridian	Mount Diablo.
Elevation	1,954 m.	Tract	Sec. 9, T 1 S, R 66 E.
Topography	Rugged.	Latitude	37°52'16" N.
Domain	Mixed.	Longitude	114°36'19" W.

Owner: Resco International, Houston, TX (1983).

GEOLOGY

Type of ore body	Replacement, fissure vein.	Host formation	Combined Metals Member of Pioche Shale.
Origin	Hydrothermal.	Geologic age	Lower Cambrian.
Shape of ore body	Tabular.	Rock relationships	Shale, lies over ore, near ore.
Ore controls	Bedding, faulting.		Limestone, lies over ore, replaced by ore.
Strike and dip of mineralized zone.	North-south: 10° E.		Lamprophyre, lies along ore, lies over ore.
Mineralized zone average dimensions, m:		Size	Medium.
Length	430.		
Width	200.		
Thickness	5.		
Depth	250.		
Mineral names	Sphalerite, galena, psilomelane, pyrolusite.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	On-site.
Type of operation	Underground.	Road requirement	None.
Mining method	Room and pillar.	Distance to power supply	On-site.
		Mill location	Pan American ore was concentrated at the Caselton mill during its last period of production.
Year of discovery	1929.		
Discovery method	Ore mineral in place.		
Initial production	1947.		
Last production	1978.		
Past production	Confidential proprietary data.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven[1]	2,196,000 tons	Pb, 1.17%; Zn, 2.45%; Ag, 2.07% (sic)	1982	168

REFERENCES

168, 216, 274, 322, 720, 721, 724, 791.

USGS quad maps	Caliente, 1:250,000. Bennett Pass, 7.5'.
USBM sequence number	0320170045.
USGS MRDS number	M032032.
Mid number	02600229.

[1]Reserves listed under St. Patrick Mining Co., Inc.

PHELPS-STOKES—IRON

Alternate names: Iron Mountain Claims, Stokes Iron Mine, Phelps-Stokes Iron Deposit

Commodities: Fe

LOCATION-OWNERSHIP

County	Nye.	General location	About 80 km northeast of Hawthorne.
Mining district	Gabbs.	Meridian	Mount Diablo.
Elevation	1,865 m.	Tract	Sec. 21, T 12 N, R 37 E.
Topography	Gentle.	Latitude	38°53'14" N.
Domain	Mixed, private.	Longitude	117°49'45" W.

Owner: Grace Church; Standard Slag Co., Reno, NV (1975).
Operator: Standard Slag Co. (1975).

GEOLOGY

Type of ore body	Replacement.	Host formation	Luning.
Origin	Contact metasomatic.	Geologic age	Upper Triassic.
Shape of ore body	Irregular.	Rock relationships	Shale, lies above ore.
Ore controls	Faulting, lithology, contact zone.		Dolomite, encloses ore.
Strike and dip of mineralized zone.	N 75° W; 60° N.	Size	Small.
Mineralized zone average dimensions, m:			
Length	550.		
Width	61.		
Thickness	122.		
Mineral names	Magnetite, pyrite, pyrrhotite, hematite, gypsum, chlorite, sericite, actinolite, phlogopite, kaolin, calcite, augite, quartz, feldspar.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	<10 km.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	<50 km.
Year of discovery	1902.		
Discovery method	Ore mineral in place.		
Initial production	1949.		
Last production	1957.		
Past production	1,200,000 t shipping grade ore and concentrates (*454*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

357, 368, 454, 580, 750.

USGS quad maps	Tonopah, 1:250,000. Paradise Peak, 15'.
USBM sequence number	0320230155.

PINSON—GOLD

Alternate names: Ogee-Pinson

Commodities: Au, Ag, Hg (recovered byproduct)

LOCATION-OWNERSHIP

County	Humboldt.	General location	About 64 km northeast of Winnemucca.
Mining district	Potosi.	Meridian	Mount Diablo.
Elevation	1,500 m.	Tract	Sec. 32, T 38 N, R 42 E.
Topography	Hilly.	Latitude	41°07'45" N.
Domain	Private.	Longitude	117°17'30" W.

Owner: J. S. Livermore, P. E. Galli, D. M. Duncan (21%); Lacana Mining, Inc. (26.25%); Rayrock Mines, Inc. (26.5%); United Siscoe Mines, Inc. (26.25%); all of Toronto, ON, Canada (1985).

Operator: Pinson Mining Co., Winnemucca, NV (1985).

GEOLOGY

Type of ore body	Disseminated, breccia fill, replacement	Host formation	Comus.
Origin	Hydrothermal.	Geologic age	Ordovician.
Shape of ore body	Tabular.	Rock relationships	Thin-bedded siltstone and limestone, contains lower grade ore.
Ore controls	Faulting, fractures, lithology.		Massive limestone, replaced by ore, lies above ore.
Strike and dip of mineralized zone.	Northeast: 40° to 50° E.		Jasperoid breccia, replaces limestone above, is ore (major host).
Age of mineralization	Late Cretaceous (90 million yr).		Andesite dikes, near ore (altered to clay).
Mineralized zone average dimensions, m:			Phyllitic shale, lies beneath ore and is fault footwall (Cambrian Preble Formation).
Length	370.	Alteration	Silicification (ore zone), seritization (wallrock), oxidation.
Width	130 (downdip).	Size	Small.
Thickness	65.		
Depth	About 5.		
Mineral names	Gold, quartz, chalcedony, pyrite, marcasite, sericite, kaolinite, calcite, jasper, cinnabar.		

DEVELOPMENT

Current status	Active-producer, exploration.	Distance to water supply	<10 km.
Type of operation	Surface.	Road requirement	<1 km.
Mining method	Open pit; about 1,200 t/d ore and 17,000 t/d waste mined.	Distance to power supply	<1 km (road and powerline to Getchell Mine runs very near Pinson).
Year of discovery	1945; again in 1971.	Mill location	On-site.
Discovery method	1945—outcrop; 1971—geological inference and drilling.	Mill status	Active.
		Milling method	Cyanide heap leach. Cyanide pretreatment, carbon column-agitated leach, CIP, electrolysis, smelting.
Initial production	January 1981 (milling); late 1982 (heap leaching). Expected mine life is 10 yr.	Process rate	1,360 t/d (1,500 ton/d) (1983).
Past production	About 91,000 t ore, shipped to Getchell Mine (1949–50) (*318*).	Product type	Dore bullion bars; 34 to 41 kg each, 950 to 975 fine (mercury recovery is 0.9 kg per cathode, 12 to 14 cathodes are refined per shift).
	110,440 t ore mined (1980) (*16*).		
	340,937 t ore milled; 1,753.3 kg Au recovered (1981) (*372*).		
	450,663 t ore milled; 2,200 kg Au recovered (1982) (*372*).		
	1,700 kg Au recovered (1983) (*523*); 1,900 kg Au forecast (1984) (*523*).		
Annual production rate	About 1,741 kg Au (56,000 tr oz).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Indicated	3,245,000 tons	0.105 tr oz/ton Au (diluted mill grade)	1980	640
2.. Do	5,000,000 tons	0.025 tr oz/ton Au (leach grade)	1980	554
3..Proven	3,000,000 tons	0.093 tr oz/ton Au (mill grade)	1983	667
Do	2,400,000 tons	0.026 tr oz/ton Au (leach grade)	1983	667

REFERENCES

16, 47, 79, 83, 90, 173, 204, 269, 285, 290, 292, 318, 372, 378, 412, 435, 439, 443, 482, 523, 525, 554, 555, 560, 561, 566, 578, 640, 662, 667, 713, 770, 773, 801.

USGS quad maps	McDermitt, 1:250,000. Osgood Mountains, 15'.
USBM sequence number	0320130220.
Mid number	2601597.

Comments: Two pits are planned for development. Huttl (*292*) reports 3,760 t ore assaying 6.38 g/t Au was produced at the Ogee-Pinson. Original rated mill capacity in 1980 was 907 t/d (1,000 ton/d). In 1983, exploration drilling resulted in additional indicated resource along the mineral zone extension. The new discovery is fairly deep and narrow.

PIUTE—IRON

Alternate names: None

Commodities: Fe

LOCATION-OWNERSHP

County	Pershing.	General location	About 20 km southeast of Lovelock.
Mining district	Wildhorse.	Meridian	Mount Diablo.
Elevation	1,207 m.	Tract	Sec. 25, T 25 N, R 32 E.
Topography	Gentle.	Latitude	40°00′30″ N.
Domain	Federal.	Longitude	118°20′30″ W.

Owner: C. W. Hunley, 60%; E. L. and H. C. Stephenson, 30%; R. W. and L. M. Belanger, 10% (1975).

GEOLOGY

Type of ore body	Breccia fill, replacement, disseminated.	Host formation	Star Peak Group.
Origin	Contact metasomatic.	Geologic age	Triassic.
Shape of ore body	Pipelike.	Rock relationships	Breccia, replaced by ore, ore in fractures.
Ore controls	Fracturing.		Andesite, encloses ore.
Mineralized zone average dimensions, m:			Marble, replaced by ore.
Depth	230.	Size	Large.
Mineral names	Magnetite, pyrite, calcite, alabanite.		

DEVELOPMENT

Current status	Inactive-explored prospect.	Distance to water supply	>10 km.
Type of operation	Possible surface.	Road requirement	None.
		Distance to power supply	<10 km.
Year of discovery	1952.		
Discovery method	Geophysical anomaly.		
Past production	None.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.[1]

REFERENCES

329, 454.

USGS quad maps	Lovelock, 1:250,000. Lovelock, 15′.
USBM sequence number	0320270382.
USGS MRDS number	M060441.

Comments: Southern Pacific Land Co. owns adjacent odd numbered sections.

[1]Moore reports (*454*) ". . .an enormous quantity of material containing more than 20 percent iron, a very large quantity averaging more than 30 percent iron, and substantial quantity containing more than 50 percent iron."

PREBLE—GOLD

Alternate names: None

Commodities: Au

LOCATION-OWNERSHIP

County ..... Humboldt.
Mining district ..... Potosi.
Elevation ..... 1,430 m.
Topography ..... Hilly.
Domain ..... Private.

General location ..... About 27 km due east of Winnemucca.
Meridian ..... Mount Diablo.
Tract ..... Sec. 18, T 36 N, R 41 E.
Latitude ..... 40°58'23" N.
Longitude ..... 117°24'00" W.

Owner ..... D. M. Duncan, P. E. Galli, J. S. Livemore, 21%; Lacana Mining, Inc., 26.25%; United Siscoe Mines, Inc., 26.25%; Rayrock Mines, Inc., 26.5%; all of Toronto, ON, Canada (1985).
Operator ..... Pinson Mining Co., Winneucca, NV (1985).

GEOLOGY

Type of ore body ..... Disseminated, replacement.
Origin ..... Hydrothermal, shear zone.
Shape of ore body ..... Tabular.
Ore controls ..... Faulting, lithology.
Strike and dip of mineralized zone. Northeast: 30° SE.
Age of mineralization ... Late Cretaceous.
Mineralized zone average dimensions (main ore body), m:
  Length ..... 300.
  Thickness ..... 96.
  Excavation depth ... 360 (planned).
Mineral names ..... Gold, pyrite, clay, limonite, geothite, lepidocrocite, quartz, chalcopyrite.

Host formation ..... Preble.
Geologic age ..... Cambrian.
Rock relationships ..... Massive limestone, replaced by ore, gangue.
Carbonaceous calcareous shale, replaced by ore, gangue (principal host).
Dolomite, in area, but not associated with gold.
Andesite sills (altered to clay), lies beneath ore, lies between ore horizons.
Granodiorite, near ore.
Alteration ..... Silicification, oxidation.
Size ..... Small.

DEVELOPMENT

Current status ..... Active-producer.
Type of operation ..... Surface.
Mining method ..... Open pit.

Year of discovery ..... 1972.
Discovery method ..... Float and outcrop chip sampling; geochemical.

Initial production ..... Fourth quarter 1984.
Annual production rate . 330,000 t ore anticipated.

Mill location ..... Pinson Mine and on-site heap leach.
Mill status ..... Pinson mill active.
Milling method ..... Pinson is carbon column, agitated leach, CIP.
Process rate ..... See Pinson abstract.
Product type ..... Ore.
Distance shipped ..... About 24 km by truck.
Destination ..... Pinson mill.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Indicated	1,340,000 tons	0.08 tr oz/ton Au (leach grade)	1980	554
2..Not reported in reference	1,242,000 tons	0.073 tr oz/ton Au	1983	372
3.. Do	1,800,000 tons	0.062 tr oz/ton Au	1984	770

REFERENCES

175, 176, 177, 178, 179, 180, 198, 204, 372, 435, 439, 443, 482, 554, 560, 561, 578, 611, 640, 770, 801.

USGS quad maps ..... Winnemucca, 1:250,000. Golconda, 7.5'.
USBM sequence number ..... 0320130443.

Comments: The mineralized zone can be traced for at least 1,200 m along strike.

PRINCE—LEAD-ZINC

Alternate names: Virginia Louise, Davidson (Prince Consolidated Mining Co.)

Commodities: Zn, Pb, Ag, Au, Mn

LOCATION-OWNERSHIP

County	Lincoln.	General location	About 4 km southwest of Pioche.
Mining district	Pioche.	Meridian	Mount Diablo.
Elevation	1,780 m.	Tract	Sec. 33, T 1 N, R 67 E.
Topography	Gentle.	Latitude	37°54′04″ N.
Domain	Mixed.	Longitude	114°28′23″ W.

Owner: Prince Consolidated Mining Co., Pioche, NV (1983).

GEOLOGY

Type of ore body	Replacement, fissure vein.	Host formation	Lyndon Limestone.
Origin	Hydrothermal.	Geologic age	Middle Cambrian.
Shape of ore body	Tabular.	Rock relationships	Limestone, encloses ore, ore in fractures.
Ore controls	Bedding, faulting.		Shale, lies under ore, lies along ore.
Strike and dip of mineralized zone.	N 20° W: 15° E.		Quartzite, lies under ore, lies along ore.
Mineralized zone average dimensions, m:		Size	Medium.
Length	380.		
Width	Unknown.		
Thickness	13.		
Mineral names	Cerussite, anglesite, hemimorphite, braunite, pyrolusite, goethite, limonite, hematite.		

DEVELOPMENT

Current status	Inactive-past producer	Distance to water supply	<3 km.
Type of operation	Underground-glory hole.	Road requirement	None.
		Distance to power supply	On-site.
Year of discovery	1869.	Mill location	No mill.
Discovery method	Ore mineral in place.		
Initial production	1870.		
Last production	1949.		
Past production	1,112,000 t ore averaging 102.8 g/t Ag; 1.03 g/t Au; 3% Pb; 4% Zn; and 12% Mn (724).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.[1]

REFERENCES

216, 274, 322, 333, 720, 721, 724, 791.

USGS quad maps	Caliente, 1:250,000. Pioche, 7.5′.
USBM sequence number	0320170023.
USGS MRDS number	D000023.

[1]Much oxidized ore is reported as remaining; however, no published estimate is available.

PUMPKIN HOLLOW—IRON

Alternate names: Lyon Copper-Iron Deposits, Lyon Claims
Ore body names: Northwest Deposit, North Deposit, South Deposit, East Deposit, E–2 Deposit

Commodities: Fe, Cu, Au, Ag

LOCATION-OWNERSHIP

County	Lyon.
Mining district	Unorganized.
Elevation	1,428 m.
Topography	Hilly.
Domain	Mixed.
General location	About 68 km southeast of Carson City.
Meridian	Mount Diablo.
Tract	Sec. 3, T 12 N, R 26 E.
Latitude	38°56'25" N.
Longitude	119°03'03" W.
Owner	U.S. Steel Corp., Pittsburgh, PA (1984).
Lessee	Plexus Resources Co., Salt Lake City, UT (1984).

GEOLOGY

Type of ore body	Replacement, disseminated.
Origin	Contact metasomatism, hydrothermal.
Shape of ore body	Tabular.
Ore controls	Contact zone, lithology, faulting.
Strike and dip of mineralized zone.	Northeasterly: steeply northwest.
Mineralized zone average dimensions, m:	
Length	853.
Width	610.
Thickness	114.
Depth	107.
Mineral names	Magnetite, pyrite, pyrrhotite, chalcopyrite, actinolite, hedenbergite, diopside, calcite, chlorite, epidote, tremolite, garnet, talc, serpentine, quartz, bornite.
Host formation	Metasedimentary rocks.
Geologic age	Triassic.
Rock relationships	Limestone, replaced by ore. Shale, replaced by ore. Chert, replaced by ore. Skarn (tactite), is ore, gangue. Marble, replaced by ore, gangue.
Size	Large.

DEVELOPMENT

Current status	Inactive-explored.
Type of operation	Prospect.
Year of discovery	1960.
Discovery method	Geophysical anomaly.
Past production	None.
Distance to water supply	>10 km.
Road requirement	<10 km.
Distance to power supply	<50 km.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	250,000,000 long tons	40% Fe, 0.3% Cu	1969	771

REFERENCES

360, 453, 454, 668, 695, 771.

USGS quad maps	Walker Lake, 1:250,000. Yerington, 15'.
USBM sequence number	0320190181.
USGS MRDS number	W016414.

Comments: The Pumpkin Hollow deposits contain 6 discrete ore bodies.

QUEEN LODE—BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.
Mining district	Bootstrap.
Elevation	1,860 m.
Topography	Hilly.
Domain	Private.
General location	About 67 km southeast of Battle Mountain.
Meridian	Mount Diablo.
Tract	Sec. 27, T 37 N, R 49 E.
Latitude	41°03'19" N.
Longitude	116°25'50".
Owner	NL Baroid-NL Industries, Inc., Houston, TX (1985).
Operator	Tom Norris Construction (mining contractor), Battle Mountain, NV (1984).

GEOLOGY

Type of ore body	Sedimentary.
Origin	Sedimentation, hydrothermal (submarine hot springs).
Shape of ore body	Tabular, massive, irregular.
Ore controls	Bedding.
Strike and dip of mineralized zone.	N 30° E; 65° N.
Mineralized zone average dimensions, m:	
Length	300.
Width	90.
Thickness	6.
Depth	0.
Mineral names	Barite.
Host formation	Vinini.
Geologic age	Ordovician.
Rock relationships	Chert, encloses ore, gangue.
	Siltstone, encloses ore, gangue.
	Shale, encloses ore, gangue.
	Conglomerate, encloses ore, gangue.
Size	Medium.

DEVELOPMENT

Current status	Inactive-past producer (standby).
Type of operation	Surface.
Mining method	Open pit.
Year of discovery	1938.
Discovery method	Ore mineral in place.
Initial production	1976.
Last production	1982.
Past production	Confidential proprietary data.
Distance to water supply	On-site.
Road requirement	None.
Distance to power supply	Mine—on-site generation. Mill—on-site commercial supply.
Mill location	Dunphy Siding, 48 km south of mine.
Mill status	Standby.
Milling method	Flotation, grinding.
Product type	Fine ground barite.
Destination	Alaska, West Coast, and intermountain markets.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

77, 95, 123, 226, 278, 392, 546, 669, 688, 775, 778, 796.

USGS quad maps	McDermitt, 1:250,000. Santa Renia Fields, 7.5'.
USBM sequence number	0320070364.
Mid number	2601148.

Comments: The Queen Lode is mined in conjunction with the Rossi (Sage Hen).

RAIN—GOLD

Ore body names: Main, Southeast Extension

Commodities: Au, Ag
(Au-Ag ratio = 10–20:1)

LOCATION-OWNERSHIP

County	Elko.	General location	About 14 km southeast of Carlin.
Mining district	Carlin.	Meridian	Mount Diablo.
Elevation	2,070 m.	Tract	Sec. 3, T 31 N, R 53 E.
Topography	Hilly.		Sec. 33, T 32 N, R 53 E.
Domain	Possibly private.	Latitude	40°36′35″ N.
		Longitude	116°00′25″ W.

Owner..... Newmont Mining Corp., New York, NY (1985).
Operator..... Carlin Gold Mining Co., Carlin, NV (subsidiary of Newmont Mining Corp.) (1985).

GEOLOGY

Type of ore body	Epithermal, disseminated, sediment-hosted.	Host formation	Webb.
Origin	Hydrothermal, epithermal.	Geologic age	Mississippian.
Shape of ore body	West-northwest elongate manto.	Rock relationships	Jasperoid breccia, contains ore.
Ore controls	Faulting, fracturing, lithology (minor).		Siltstone and breccia, contains ore.
Strike and dip of mineralized zone.	N 30° to 40° W: dip southwest		Sandstones, contains ore.
Mineralized zone average dimensions, m:			Shales, contains ore.
Length	About 730.	Alteration	Silicification, oxidation, argillization, baritization, bleaching.
Thickness	110 (maximum).	Size	Small.
Depth	46.		
Mineral names	Gold, quartz, barite, limonite, manganese oxides, hematite, jarosite, calcite, illite, kaolinite.		

DEVELOPMENT

Current status	Active-exploration, feasibility, standby.	Mill location	Likely will be co-located with mine.
Type of operation	Surface	Mill status	No mill.
Mining method	Proposed open pit.	Milling method	Cyanide heap leach probable.
Year of discovery	1980.		
Discovery method	Geochemical-rock chip sample, drilling.		
Initial production	Pending development; possibly 1990's.		
Past production	None.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	8,300,000 tons	0.083 tr oz/ton Au (ore in-place)	1983	511
Above contains	3,400,000 tons	0.147 tr oz/ton Au	1983	511

REFERENCES

27, 59, 61, 90, 118, 224, 226, 319, 350, 363, 511, 581, 663, 664, 665, 669.

USGS quad maps ..... Winnemucca, 1:250,000.
Dixie Flats, 15′.
USBM sequence number ..... 0320070271.

Comments: Development of the Rain deposit is expected to recommence after Gold Quarry goes into production. Further drilling may disclose greater reserves as the ore body is reportedly open at depth and to the east. Ore is in fractures and occurs in the axis of a regional north-northwest plunging antiform. At Rain, the antiform is marked by a high-angle reverse fault trending west-northwest and dipping steeply southwest.

RAINBOW—FLUORINE

Alternate names: Bruno Prospect, Fluorspar Corp. of America, Hope

Commodities: CaF_2

LOCATION-OWNERSHIP

County	Nye.	General location	About 117 km west of Pioche.
Mining district	Quinn Canyon Range.	Meridian	Mount Diablo.
Elevation	2,042 m.	Tract	Sec. 1, T 2 N, R 54 E.
Topography	Hilly.	Latitude	30°03′47″ N.
Domain	BLM administered.	Longitude	115°51′17″ W.

Owner: Wesley Koyen, Alamo, NV (Rainbow and Emerald Claims); Ed Slavin, Tonopah, NV (Bruno Claims) (1981).

GEOLOGY

Type of ore body	Fissure vein.	Host formation	Volcanic rocks undivided.
Origin	Hydrothermal.	Geologic age	Tertiary.
Shape of ore body	Lenticular.	Rock relationships	Tuff, ore in fractures.
Ore controls	Faulting, igneous.		Rhyolite, ore in fractures.
Strike and dip of mineralized zone.	N 20° E: 40° W.		Dacite, ore in fractures.
			Latite.
Mineralized zone average dimensions, m:		Size	Small.
Length	2,414.		
Width	805.		
Thickness	30.		
Mineral names	Fluorite, quartz.		

DEVELOPMENT

Current status	Inactive-past producer.	Road requirement	<10 km.
Type of operation	Surface.	Distance to power supply	<50 km.
Mining method	Surface open stope.		
Year of discovery	1941.		
Discovery method	Ore mineral in place.		
Initial production	1945.		
Last production	1946.		
Past production	181 t (*545*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

281, 283, 357, 368, 545, 604, 733, 815, 816.

USGS quad maps	Lund, 1:250,000.
USBM sequence number	0320230200.

RELIEF CANYON—GOLD

Alternate names: (site of) Emerald Spar Fluorite deposit

Commodities: Au, Ag, CaF_2 (nonrecoverable)

LOCATION-OWNERSHIP

County	Pershing.	General location	About 24 km east of Lovelock.
Mining district	Relief-Antelope Springs.	Meridian	Mount Diablo.
Elevation	1,645 m.	Tract	Sec. 16, T 27 N, R 34 E.
Topography	Rugged.	Latitude	40°12′15″ N.
Domain	Mixed, Federal, private lease.	Longitude	118°10′13″ W.

Owner-operator ..... Lacana Mining Corp., Toronto, ON, Canada (1985).
(The development of the property is a joint venture; Lacana's partner is unknown.)

GEOLOGY

Type of ore body	Disseminated epithermal gold, stratabound.	Host formations	Grass Valley. Natchez Pass (Cane Springs).
Origin	Hydrothermal.	Geologic age	Late Triassic.
Shape of ore body	Irregular triangular wedge or bell-shape in plan.	Rock relationships	Argillite, quartzite, siltstone, shale (Grass Valley), adjacent and above principal ore zone. Jasperoid breccia zone, contains ore. Carbonaceous dolomitic limestone, minor shale and siltstone (Natchez Pass), adjacent and below principal ore zone.
Ore controls	Faulting, lithology.		
Age of mineralization	Unknown, possibly from Late Cretaceous to Late Tertiary.		
Mineralized zone average dimensions, m:			
Length	730.		
Width	550.		
Thickness	0 to >30. (deposit open to the southwest)	Alteration	Jasperoid silicification, argillic, iron staining, intense oxidation.
Mineral names	Native gold or electrum, quartz, pyrite, sericite, hematite, fluorspar, jasperoid, clay.	Size	Small.

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	<5 km.
Type of operation	Surface.	Road requirement	<5 km.
Mining method	Conventional open pit; mine 4,500 t/d ore, and about 6,400 t/d waste.	Distance to power supply	<5 km.
		Mill location	On-site.
		Mill status	Active.
Year of discovery	1979–82.	Milling method	Agglomeration, sodium cyanide heap leach, carbon column recovery.
Discovery method	Mapping, stream sediment sampling, drilling by Duval Corp.	Process rate	About 4,500 t/d.
Initial production	September-October 1984.		
Past production	None.		
Annual production rate	762 kg (24,500 tr oz) Au.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	7,000,000 tons	0.042 tr oz/ton Au	1983	530
2.. Do[1]	8,000,000 tons	0.04 tr oz/ton Au (diluted ore; stripping ratio = 1.5:1).	1983	199
3.. Do[2]	9,000,000 tons	0.032 tr oz/ton Au (stripping ratio = 2:1)	1984	658

REFERENCES

90, 199, 224, 329, 331, 496, 525, 530, 658, 662, 755, 810.

USGS quad maps ..... Lovelock, 1:250,000.
Buffalo Mountain, 15′.

USBM sequence number ..... 0320270720.

Comments: Gold is in and near jasperoid silicification principally within a sedimentary breccia at the contact between the above 2 host formations.

[1]Resource is referred to as preliminary pit plan diluted reserves.
[2]Resource is referred to as minable reserves.

RIDGE 7129—ZINC

Alternate names: Gibellini, Bisoni Properties

Commodities: Zn, V, Mo, Se, oil shale

LOCATION-OWNERSHIP

County	Eureka.	General location	About 37 km southwest of Eureka.
Mining district	Fish Creek.	Meridian	Mount Diablo.
Elevation	2,164 m.	Tract	Sec. 3, T 15 N, R 52 E.
Topography	Hilly.	Latitude	39°12'30" N.
Domain	Unknown.	Longitude	116°05'34" W.

Owner: Maynard and Lester Bisoni; Noranda Exploration, Inc., Lakewood CO (1979).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Woodruff.
Origin	Sedimentation, oxidation.	Geologic age	Devonian.
Shape of ore body	Irregular.	Rock relationships	Mudstone, encloses ore.
Ore controls	Lithology.		Siltstone, encloses ore.
Mineralized zone average dimensions, m:			Chert, near ore.
		Size	Medium.
Length	>600.		
Width	300.		
Thickness	60.		
Depth	Surface.		
Mineral names	Sphalerite, metahewettite, molybdenite, kerogen.		

DEVELOPMENT

Current status	Inactive-explored.	Distance to water supply	Unknown.
Type of operation	Possible underground.	Road requirement	<10 km.
		Distance to power supply	<50 km.
Year of discovery	Unknown.	Mill location	No mill.
Discovery method	Drilling, trenching.		
Initial production	No production.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

112, 333, 593.

USGS quad maps	Millett, 1:250,000.
	Cockalorum Wash, 15'.
USBM sequence number	0320110222.

Comments: Assay results:

	Unoxidized rock, ppm	*Oxidized rock,* ppm
V	3,000– 7,000	6,000–8,000
Zn	4,000–18,000	30– 100
Se	30– 200	200– 400
Mo	70– 960	30– 80

Fresh black rock yielded as much as 12 gal/ton (50 L/t) syncrude oil (*112*).

ROBINSON DISTRICT—COPPER

Includes: New Ruth Pit, Ruth-Kimberly, Veteran-Tripp Open Pit, Veteran-Tripp Underground, Veteran-Tripp Lo-Grade

Commodities: Cu, Mo, Ag, Au, platinum group metals

LOCATION-OWNERSHIP

County	White Pine.	General location	About 10 km west of Ely.
Mining district	Robinson.	Meridian	Mount Diablo.
Elevation	1,920 to 2,320 m.	Tract	T 16 N, R 62–63 E.
Topography	Hilly.	Latitude	39°15′20″ N.
Domain	Private.	Longitude	114°57′59″ W.

Owner-operator ..... Kennecott Copper Corp., Salt Lake City, UT (1984).

GEOLOGY

Type of ore body	Disseminated, replacement, vein supergene, stockwork.	Host formation	Various (18 formations).
Origin	Hydrothermal, oxidation, replacement.	Geologic age	Ordovician-Tertiary.
Shape of ore body	Irregular, massive.	Rock relationships	Various sedimentary, encloses ore, replaced by ore.
Ore controls	Igneous, fracturing, lithology.		Quartz monzonite, encloses ore, is ore.
District dimensions:			Metamorphosed and/or altered sedimentary, encloses ore, is ore.
Length	19 km.	Size	Large.
Width	14 km.		
Depth	0 to 500 m.		

Mineral names ..... Chalcopyrite, bornite, molybdenite, argentite, pyrite, chalcocite, cerussite, calcite, fluorite, pyrolusite, braunite, hemimorphite, smithsonite, native gold, scheelite, hematite, jarosite, malachite, azurite, cuprite, native copper, chalcanthite.

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit, underground.	Distance to power supply	On-site.
		Mill location	McGill, 32 km.
Year of discovery	1867.	Mill status	Inactive.
Discovery method	Ore mineral in place.	Milling method	Flotation.
		Process rate	19,972 t/d.
Initial production	1870.		
Last production	1978.		
Past production	Greater than 204 million t ore.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.[1]

REFERENCES

1, 17, 37, 38, 39, 127, 264, 280, 284, 293, 294, 321, 341, 374, 419, 432, 438, 556, 674, 792, 806, 819, 820, 821, 825, 826.

USGS quad maps ..... Ely, 1:250,000.
Ruth, 7.5′.

[1]In 1976, Kennecott Copper Corp. reported that 454,000 t of copper could be recovered from 82,554,000 t ore averaging 0.67% Cu (*792*).

ROCHESTER—SILVER

Alternate names: Silver State, Nenzel Hill

Commodites: Ag, Au

LOCATION-OWNERSHIP

County	Pershing.	General location	About 30 km northeast of Lovelock.
Mining district	Rochester.	Meridian	Mount Diablo.
Elevation	1,829 m.	Tract	Sec. 15, 16, 21, 22, T 28 N, R 34 E.
Topography	Hilly, rugged.	Latitude	40°17′23″ N.
Domain	Mixed; private, BLM administered (4 patented claims and 20 unpatented lode claims).	Longitude	118°12′00″ W.

Owner: Royal Apex Silver, Inc., Wallace, ID (Coeur d'Alene Mines Corp. owns 49.8% of Royal Apex) (1983).
Operator: Coeur d'Alene Mines Corp., Wallace, ID, lessee (acquired 85% of net operating property); ASARCO, Inc., New York, NY, holds a small royalty interest (1985).

GEOLOGY

Type of ore body	Disseminated, stockwork.	Host formation	Koipato Group (Weaver, Rochester, Limerick Formations).
Origin	Hydrothermal.	Geologic age	Permian-Triassic.
Shape of ore body	Tabular, irregular.	Rock relationships	Rhyolite ash-flow tuffs, volcaniclastics, contains veins and disseminated silver (Weaver Formation).
Ore controls	Faults, fractures.		
Strike of mineralized zone.	Northeast.		Rhyolite flows and tuffs, contains veins and disseminated silver (Rochester Formation).
Age of mineralization	Late Cretaceous (70 to 80 million yr).		
Mineralized zone average dimensions, m:		Alteration	Silicification, pyritization, sericitic, oxidation.
Length	1,150.	Size	Medium.
Width	750.		
Thickness	0 to >200.		
Depth	0.		

Mineral names: Argentian tetrahedrite, chlorargyrite, silver, acanthite, sphalerite, arsenopyrite, chalcopyrite, electrum, pyrite (95% of sulfides), quartz, sericite (numerous others).

DEVELOPMENT

Current status	Active-past producer, feasibility.	Distance to water supply	Unavailable.
Type of operation	Possible surface.	Road requirement	Unavailable.
Mining method	Possible open pit.	Distance to power supply	Unavailable.

Year of discovery: 1912 (high-grade silver ore).

Initial production: 1912.
Last production: 1951.
Past production: District— >2,595 kg Au; 276,000 kg Ag; 12.7 t Cu; 152 t Pb; 30 t Zn (*329*).

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Probable	70,000,000 tons	1.39 tr oz/ton Ag; 0.0072 tr oz/ton Au	1980	159
Possible	30,000,000 tons			
2..Not reported in reference	75,000,000 tons	1.5 tr oz/ton Ag	1981	61
3.. Do	>100,000,000 tons	1 to 2 tr oz/ton Ag; "small amounts of Au"	1981	745
4..Indicated	88,300,000 tons	1.5 tr oz/ton Ag; 0.007 tr oz/ton Au	1983	94

REFERENCES

61, 74, 93, 94, 159, 323, 329, 362, 613, 662, 745, 746, 756, 776, 777.

USGS quad maps: Lovelock, 1:250,000. Unionville, 15′.
USBM sequence number: 0320270673.

Comments: Coeur d'Alene Mines Corp. purchased ASARCO's interest in the property in 1983. Mineral zone dimensions represent disseminated silver grade higher than 34 g/t (>1 oz/ton). From 1969–82, ASARCO reportedly spent $2.9 million in exploration costs on the property. Work in 1984 included large-scale leach testing and about 1,800 m of core drilling. In 1984, the drilling season expanded total mineralized material to 102.1 million t.

ROSSI—BARITE

Alternate names: Sage Hen, Dunphy, National Lead Co.

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.	General location	About 66 km southeast of Battle Mountain.
Mining district	Bootstrap.		
Elevation	1,770 m.	Meridian	Mount Diablo.
Topography	Hilly.	Tract	Sec. 22, T 37 N, R 49 E.
Domain	Mixed; private and BLM administered public lands.	Latitude	41°04'03" N.
		Longitude	116°25'31" W.

Owner..... NL Baroid-NL Industries, Inc., Houston, TX (1983).
Operator..... Tom Norris Construction (mining contractor), Battle Mountain, NV (1983).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Vinini.
Origin	Sedimentation, hydrothermal (submarine hot springs).	Geologic age	Ordovician.
		Rock relationships	Chert, encloses ore, gangue.
Shape of ore body	Tabular, massive, irregular.		Shale, near ore, gangue.
Ore controls	Bedding.		Quartzite, near ore.
Strike and dip of mineralized zone.	N 55° E: 60° N.		Limestone, near ore.
		Size	Large.
Mineralized zone average dimensions, m:			
Length	1,800.		
Width	Unknown.		
Thickness	10.		
Depth	0.		
Mineral names	Barite, chert, witherite.		

DEVELOPMENT

Current status	Inactive-past producer (standby).	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	Mine—on-site generator. Mill—on-site commercial supply.
Year of discovery	1937.	Mill location	Dunphy Siding, 48 km south of mine.
Discovery method	Ore mineral in place.	Mill status	Standby.
Initial production	1947.	Milling method	Jigging, flotation, grinding.
Last production	1982.	Product type	Finely ground barite.
Past production	Confidential proprietary data.	Destination	Alaska, West Coast, and intermountain markets.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

71, 87, 95, 123, 226, 278, 392, 449, 546, 669, 688, 775, 778, 796.

USGS quad maps	McDermitt, 1:250,000. Santa Renia Fields, 7.5'.
USBM sequence number	0320070094.
Mid number	2600397.

Comments: The Rossi (Sage Hen) is mined in conjunction with the Queen Lode.

ROUND MOUNTAIN—GOLD

Alternate names: Smoky Valley Mine, Round Mountain Common Operation
Related names: Sunnyside Pit, Southeast Pit

Commodities: Au, Ag
(Au-Ag ratio ≈ 1:2)

LOCATION-OWNERSHIP

County	Nye.	General location	About 80 km north of Tonopah.
Mining district	Round Mountain (Jefferson Canyon).	Meridian	Mount Diablo.
Elevation	1,920 m.	Tract	Sec. 19, T 10 N, R 44 E.
Topography	Hilly.	Latitude	38°42'30" N.
Domain	Mixed; private and BLM administered.	Longitude	117°05'00" W.

Owner..... Louisiana Land and Exploration Co. (LL & E), Lakewood, CO, 50%; Felmont Oil, New York, NY, 25%; Case, Pomeroy and Co., 25% (1984). (Echo Bay Mines Ltd., Edmonton, AB, Canada, bought LL & E's 50% interest subject to completion of definitive agreement, expected in January 1985.)
Operator..... Smoky Valley Mining Division of Copper Range Co. (subsidiary of LL & E) (1984).

GEOLOGY

Type of ore body	Disseminated, fissure vein, stockwork.	Principal host formation	Tertiary Volcanics (Jefferson Caldera).
Origin	Hydrothermal, oxidation.	Geologic age	Oligocene.
Shape of ore body	Unknown.	Rock relationships	Quaternary gravel, is ore (resource unknown).
Ore controls	Fracturing, lithology.		Densely welded rhyolite ignimbrite, is ore, in veins and stockwork.
Strike and dip of mineralized zone.	Northwest: southwest.		Poorly welded rhyolite ignimbrite, is ore, disseminated (contains largest ore reserves).
Age of mineralization	Miocene (25 million yr).		Lithic tuff, is ore in veins.
Mineralized area dimensions (excluding outlying placer areas), m:			Shale, slate, quartzite (Ordovician), is ore in veins.
Length	1,800.		Granite (Cretaceous Shoshone), is ore in veins.
Width	1,200.	Alteration	Sericitic, propylitic, argillic, silicification, oxidation.
Thickness	>750.	Size	Large.

(Disseminated zone is about 600 m wide and 1,700 m long.)
Mineral names ..... Electrum, auriferous pyrite, free gold, pyrite, limonite, adularia, quartz, fluorite, realgar, alunite, calcite.

DEVELOPMENT

Current status	Active-producer, expansion feasibility.	Distance to water supply	13.7 km to stream from Jett Canyon.
Type of operation	Surface.	Road requirement	About 1 km.
Mining method	Open pit; with 1983 production rate of 9,000 t/d ore, 23,000 t/d waste.	Distance to power supply	On-site.
		Mill location	On-site.
		Mill status	Active.
Year of discovery	1901 (district lode gold); 1906 placer gold); 1979 (LL & E).	Milling method	Cyanide heap leach, carbon adsorption, electrowinning, smelting.
Discovery method	Ore mineral in place, drilling.	Pad process rate	48-d cycle, 9,000 t/d.
		Product type	Dore bullion (2/3 Au, 1/3 Ag).
Initial production	1906; again in 1976 (LL & E).		
Past production	16,700 kg Au (district) (1901–59) (*422*).		
	7,493.6 kg Au and 3,940.2 kg Ag (1977–81) (*422*).		
	2,256.9 kg Au (1982).		
	2,900 kg Au, 1,700 kg Ag (1983).		
	3,100 kg Au planned (1984) (*670*).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	11,617,000 tons	0.061 tr oz/ton Au, 0.07 tr oz/ton Ag (original reserves, cutoff grade 0.02 tr oz Au).	1974	412
2..Proven and probable	195,400,000 tons	0.043 tr oz/ton Au, 0.023 tr oz/ton Ag (114,400,000 tons proven and 81,000,000 tons probable (undiluted).	1981	388
3..Indicated	228,300,000 tons	0.03715 tr oz/ton Au	1983	169

REFERENCES

46, 61, 83, 84, 90, 169, 187, 193, 195, 196, 301, 303, 312, 357, 368, 378, 387, 388, 404, 408, 412, 416, 422, 431, 447, 492, 550, 616, 620, 621, 622, 670, 767, 795, 840.

USGS quad maps	Tonopah, 1:250,000. Round Mountain, 7.5'.
USBM sequence number	0320230149.
USGS MRDS number	W001574.
Mid number	2600594.

Comments: A 36,000-t/d (40,000-ton/d) mill to attain 90% recovery of reserves is under study. Reserves reported in 1983 delineated from 1977 through 1982. This reserve includes production in the intervening years.

RUBY HILL—ZINC

Alternate names: Fad Shaft, Eureka Corporation Mine, Look Out Mine, Locan Shaft

Commodities: Zn, Au, Ag, Pb

LOCATION-OWNERSHIP

County	Eureka.	General location	About 2 km west of Eureka.
Mining district	Eureka.	Meridian	Mount Diablo.
Elevation	2,100 m.	Tract	Sec. 22, T 19 N, R 53 E.
Topography	Hilly.	Latitude	39°30'21" N.
Domain	Mixed; private and BLM administered.	Longitude	115°59'02" W.

Owner: Richmond-Eureka Corp., Miami Beach, FL, 75%; Silver Eureka Corp., Toronto, ON, Canada, 25% (1985). (Sharon Steel Corp., Miami Beach, FL, owns 82% of Richmond-Eureka Corp.)

GEOLOGY

Type of ore body	Replacement, breccia fill.	Host formation	Eldorado Dolomite.
Origin	Hydrothermal.	Geologic age	Mid-Cambrian.
Shape of ore body	Irregular, pipelike.	Rock relationships	Limestone, encloses ore, replaced by ore. Dolomite, lies under ore.
Ore controls	Faulting, fracturing, lithology.		
Strike and dip of mineralized zone.	N 40° W: 60° NE (Ruby Hill Fault); N 90° E: 01° W (trend of deep sulfides).	Alteration	Intense pyritic alteration.
		Size	Medium.

Mineralized zone average dimensions, m:

Length	600.
Width	370.
Thickness	<245.
Depth	730.

Mineral names: Pyrite, sphalerite, galena, smithsonite, cerrusite, arsenopyrite, argentite, gold. (Gold is present in pyrite and arsenopyrite; silver is contained in solid solution with galena.)

DEVELOPMENT

Current status	Inactive-standby; partially developed.	Distance to water supply	On-site.
Type of operation	Underground.	Road requirement	Existing paved road.
Mining method	Cut and fill.	Distance to power supply	<5 km to on-site substation.
		Mill location	On-site (building and infrastructure).
Year of discovery	Late 1930's (deep sulfide ore body).		
Discovery method	Diamond drilling.	Mill status	Equipment removed.
Initial production	1866 (Eureka district).		
Last production	1964 (estimated).		
Past production	None from deep sulfide deposit.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Indicated	3,132,000 tons	0.16 tr oz/ton Au; 5.65 tr oz/ton Ag; 3.7% Pb; 8.3% Zn.	1982	168

REFERENCES

50, 84, 105, 152, 168, 238, 255, 256, 257, 261, 326, 389, 450, 451, 518, 519, 520, 521, 593, 697, 722, 741.

USGS quad maps	Ely, 1:250,000. Eureka, 15'.
USBM sequence number	0320110093.
USGS MRDS number	M030021.
Mid number	2600233.

Comments: There has been no commercial production from the deep sulfide ore body. In 1975, a 245-t sample was taken for metallurgical testing. Excessive water and metallurgical problems have long hampered development of the deposit.

SANTA FE—GOLD

Alternate names: None

Commodities: Au, Ag (Au-Ag ratio = 1:15)

LOCATION-OWNERSHIP

County	Mineral.	General location	About 42 km east of Hawthorne.
Mining district	Santa Fe.	Meridian	Mount Diablo.
Elevation	1,490 m.	Tract	Sec. 2, T 8 N, R 34 E.
Topography	Hilly.	Latitude	38°35'05" N.
Domain	BLM administered.	Longitude	118°09'20" W.

Owner: Westley Mines Ltd., Vancouver, BC, Canada, 82%; Brican Resources Ltd., Vancouver, BC, Canada, 18%; (1984).
Operator: Lacana Mining Corp., Reno, NV (will earn 51% interest by late 1985 if presently held agreement conditions are met) (1984).

GEOLOGY

Type of ore body	Disseminated, epithermal, replacement in breccia fill.	Host formations	Guild Mine Member of Mickey Pass Tuff. Pamlico.
Origin	Hydrothermal.		
Shape of ore body	Irregular, pipelike.	Geologic ages	Oliogocene. Triassic.
Ore controls	Faulting, lithology.		
Strike and dip of mineralized zone.	N 30° to 40° W: 75° to 80° NE.	Rock relationships	Rhyodacite tuff (densely welded), above ore, encloses ore. Limestone (medium-grained), encloses ore, lies along ore, below ore. Jasperoid breccia, is ore.
Age of mineralization	Miocene.		
Mineralized zone average dimensions, m:			
Length	530 to 1,100.	Alteration	Silicification, carbonitization, sericitic.
Width	120.		
Thickness	>300.	Size	Small.
Mineral names	Gold, silver, pyrite, quartz, jasper, chalcedony, carbonaceous material, sericite, kaolinite, stibnite, hematite, barite, calcite.		

DEVELOPMENT

Current status	Active-feasibility.	Distance to water supply	Unknown.
Type of operation	Surface.	Road requirement	0.8 km.
Mining method	Open pit proposed (300 m long by 60 wide).	Distance to power supply	Unknown.
		Mill location	On-site (planned).
		Mill status	Feasibility study—1983.
Year of discovery	Claims first staked early 1960's.	Milling method	Cyanide heap leach anticipated; small scale, on-site heap leaching was planned for 1984.
Annual production rate	590,000 t/a ore anticipated as minimum throughput.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	4,360,000 tons	0.082 tr oz/ton Au; 1.22 tr oz/ton Ag	1981	690
2.. Do	5,000,000 tons (oxide)	0.04 tr oz/ton Au; 0.45 tr oz/ton Ag	1984	657
	4,500,000 tons (sulfide)	0.066 tr oz/ton Au; 0.9 tr oz/ton Ag	1984	657
3.. Do	7,000,000 tons (oxide)	0.041 tr oz/ton Au; 0.45 tr oz/ton Ag	1984	786
4.. Do	6,900,000 tons (oxide)	0.048 tr oz/ton Au	1984	531

REFERENCES

86, 130, 196, 463, 503, 523, 531, 598, 650, 657, 690, 786.

USGS quad maps	Walker Lake, 1:250,000. Luning, 7.5'.
USBM sequence number	0320210280.
USGS MRDS number	W016420.

Comments: Gold and silver occur within a pyritic jasperoid replacement of brecciated carbonate and volcanic rocks. By December 1982, drilling had not defined bottom of mineralized pipe. In June 1983, Westley Mines Ltd. was carrying out feasibility studies into the development of an open pit mine using heap leach for metal recovery.

SILVER PEAK—LITHIUM

Alternate names: Clayton Valley

Commodities: Li_2CO_3

LOCATION-OWNERSHIP

County	Esmeralda.	General location	About 49 km southwest of Tonopah.
Mining district	Silver Peak.	Meridian	Mount Diablo.
Elevation	1,300 m.	Tract	Sec. 22, T 2 S, R 39 E.
Topography	Flat.	Latitude	37°45′10″ N.
Domain	BLM administered.	Longitude	117°38′20″ W.

Owner-operator ..... Foote Minerals Co., Exton, PA (1985).

GEOLOGY

Type of ore body	Subsurface brine.	Host formation	Esmeralda.
Origin	Hydrothermal, evaporation.	Geologic age	Tertiary.
Shape of ore body	Tabular.	Rock relationships	Evaporites, encloses brine.
Ore controls	Evaporation.		Clays, encloses brine.
Mineralized zone average dimensions.	Covers an area of 8,300 ha, up to 460 m thick.		Silts, encloses brine.
		Size	Large.
Mineral names	Hectorite.[1]		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	On-site.
Type of operation	Wells.	Road requirement	On-site.
Mining method	Solution mining.	Distance to power supply	On-site.
		Mill location	Silver Peak.
Year of discovery	Early 1900's.	Mill status	Operating.
Discovery method	Drilling.	Milling method	Solar evaporation; chemical precipitation.
Initial production	1966.	Process rate	1,200 t/a Li.
Past production	Confidential proprietary data.	Product type	Lithium carbonate.
		Distance shipped	84 km from Silver Peak.
		Destination	Sold f.o.b. bagging plant at Mina, NV.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Possible	386,250,000 t	0.02% Li	1978	345
2..Demonstrated	45,000 tons	Li as Li_2CO_3	1979	638

REFERENCES

8, 32, 109, 117, 146, 345, 369, 370, 371, 535, 542, 543, 544, 595, 614, 638, 677, 747, 748, 804.

USGS quad maps ..... Goldfield, 1:250,000.
Silver Peak, 15′.

USBM sequence number ..... 0320090109.

[1]Lithium occurs as a constituent in a subsurface saline brine; hectorite may be the source of the brine's lithium content.

SIXTEEN-TO-ONE—SILVER

Alternate names: None

Commodities: Ag, Au

LOCATION-OWNERSHIP

County	Esmeralda.	General location	About 100 km southwest of Tonopah.
Mining district	Red Mountain.	Meridian	Mount Diablo.
Elevation	2,130 m.	Tract	Sec. 32, T 2 S, R 38 E.
Topography	Rugged, mountainous.	Latitude	37°42′57″ N.
Domain	BLM administered.	Longitude	117°47′06″ W.

Owner-operator ..... Sunshine Mining Co., Dallas, TX, 66–2/3% (1985).
Owner ..... Mid-Continent Mining Co., Denver, CO, 33–1/3% (1984).

GEOLOGY

Type of ore body	Fissure vein.	Host formation	Volcanics.
Origin	Hydrothermal.	Geologic age	Miocene.
Shape of ore body	Tabular.	Rock relationships	Quartz vein, portions are ore. Andesite (tuff flows and tuffaceous sediments), primary host to vein. Rhyolite (tuff, flow breccias), host to vein in uppermost levels.
Ore controls	Faulting.		
Strike and dip of mineralized zone.	N 40° to 70° E: 65° to 90° SE.		
Mineralized zone average dimensions, m:		Alteration	Silicification (footwall), argillic (hanging wall).
Length	580.		
Thickness	6.7.	Size	Small.
Development depth	240.		
Mineral names	Argentite-acanthite, proustite, pyrargyrite, marcasite, chalcopyrite, tetrahedrite, native silver (minor), native gold, galena, sphalerite, pyrite, quartz, calcite, barite (minor), siderite (minor).		

DEVELOPMENT

Current status	Active-producer.	Distance to water supply	At millsite, 400-m well.
Type of operation	Underground.	Road requirement	14-km road improvement.
Mining method	Sublevel blasthole stoping; 685 t/d ore (1983).	Distance to power supply	8 to 14 km, 24.6 kV.
		Mill location	5.6 km east of mine.
		Mill status	Active.
Year of discovery	1935 (first staked).	Milling method	Cyanide leach tank, CCD, zinc dust precipitation.
Discovery method	Ore mineral in place.		
		Process rate	635 t/d (700 ton/d).
Initial production	February 1982.	Product type	20- to 30-kg dore buttons.
Past production	19,490.8 kg (626,643 tr oz) Ag; 138.5 kg (4,453 tr oz) Au (1982) (*698*). 28,065.3 kg (902,321 tr oz) Ag; 218.9 kg (7,037 tr oz) Au (1983) (*700*).	Destination	Airlifted to Sunshine's Big Creek Refinery, Kellogg, ID.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference[1]	1,100,000 tons	8.38 tr oz/ton Ag; 0.03 tr oz/ton Au	1982	847
2..Proven and probable	1,077,572 tons	5.4 tr oz/ton Ag; 0.028 tr oz/ton Au	1984	700

REFERENCES

7, 8, 124, 171, 224, 307, 339, 483, 487, 489, 653, 694, 698, 699, 700, 765, 847.

USGS quad maps ..... Goldfield, 1:250,000. Piper Peak, 15′.
USBM sequence number ..... 0320090134.
Mid number ..... 2601638.

Comments: 1983 metal output recovered from ore averaging 1.65 g/t Au and 187 g/t Ag. 1983 mill output averaged 564 t per operating day. Sunshine's 1983 annual report states the potential for additional reserves is excellent as drilling on the western and downdip extensions of the Sixteen-to-One Vein has intersected mineralization. Sunshine reports the nearby Nivloc Mine, under its control, contains up to 900,000 t of minable ore.

[1]Reserve is minable reserve; includes 10% dilution of 1 tr oz/ton Ag, 0.01 tr oz/ton Au, and represents reserves above 6,650-ft elevation.

SNOOSE—BARITE

Alternate names: Snoose Creek

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.	General location	About 28 km due north of Wells.
Mining district	Snake Mountains.	Meridian	Mount Diablo.
Elevation	2,100 m.	Tract	Sec. 4, T 40 N, R 62 E.
Topography	Hilly.	Latitude	41°23′00″ N.
Domain	Private.	Longitude	114°58′17″ W.

Owner: Minerals—Grube Estate, 50%; AZL Resources, Phoenix, AZ, 25%; Superior Oil Co., Sparks, NV, 25%.
Surface—Sierra Pacific Power Co., Reno, NV (1983).
Operator: Chromalloy American Corp., St. Louis, MO (1983).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Valmy.
Origin	Sedimentation, hydrothermal.	Geologic age	Ordovician.
Shape of ore body	Massive, tabular.	Rock relationships	Greenstone, lies over ore.
Ore controls	Bedding.		Siltstone, encloses ore.
Strike and dip of mineralized zone.	N 30° W: 35° E.		Chert, near ore.
			Limestone, encloses ore.
Mineralized zone average dimensions, m:			Shale, encloses ore.
		Size	Medium.
Length	335.		
Width	130.		
Thickness	14.		
Depth	0.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-past producer (standby).	Distance to water supply	Millsite.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	Mill on-site generation.
		Mill location	34 km northeast of mine.
Year of discovery	1978.	Mill status	Standby.
Discovery method	Ore mineral in place.	Milling method	Crushing, screening, jigging.
		Mill feed capacity	565 t/d.
Initial production	1978.	Product type	Unground barite concentrate.
Last production	1982.	Distance shipped	56 km to Wells, NV, by truck; then 2,350 km to Cyril, OK, by rail.
Past production	Confidential proprietary data.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

77, 95, 123, 226, 278, 449, 546, 669, 716, 775, 778.

USGS quad maps	Wells, 1:250,000.
	Loomis Mountain, 7.5′.
USBM sequence number	0320070856.
Mid number	2601759.

SPRINGER—TUNGSTEN

Alternate names: Nevada-Massachusetts, Sutton, Stank Mine, Humboldt Mine, Uncle Sam, Summit Mine, Mill City, Humboldt-Springer, Tungsten

Commodities: W, Mo

LOCATION-OWNERSHIP

County	Pershing.	General location	About 13 km north of Imlay.
Mining district	Mill City.	Meridian	Mount Diablo.
Elevation	1,493 m.	Tract	Sec. 35, T 34 N, R 34 E.
Topography	Hilly.	Latitude	40°46′53″ N.
Domain	Mixed; private and BLM administered.	Longitude	118°07′56″ W.

Owner: General Electric Corp., Fairfield, CT, 80%; Broken Hills Proprietary, Ltd., Melbourne, Australia, 20% (1983).
Operator: Utah International, Inc., San Francisco, CA (a wholly owned subsidiary of Broken Hills Proprietary, Ltd.) (1983).

GEOLOGY

Type of ore body	Replacement, fissure vein.	Host formation	Raspberry.
Origin	Contact metasomatic, hydrothermal.	Geologic age	Upper Triassic.
Shape of ore body	Tabular.	Rock relationshps	Limestone, replaced by ore, gangue.
Ore controls	Lithology, bedding.		Hornfels, lies over ore, lies under ore.
Strike and dip of mineralized zone.	N 20° E: 70° W.		Slate, lies over ore, lies under ore.
Mineralized zone average dimensions, m:			Quartzite, lies over ore, lies under ore.
Length	1,524.	Size	Large.
Width	400.		
Thickness	9.6.		

Mineral names: Scheelite, molybdenite, chalcopyrite, turquoise, arsenopyrite, stilbite, pyrrhotite, garnet, pyrite.

DEVELOPMENT

Current status	Inactive-developed (standby).	Distance to water supply	<3 km.
Type of operation	Underground.	Road requirement	None.
Mining method	Shrinkage stope (65%), cut and fill (35%).	Distance to power supply	On-site.
		Mill location	On-site.
		Mill status	On standby.
Year of discovery	1914.	Milling method	Flotation and chemical (APT).
Discovery method	Ore mineral in place.	Process rate	907 t/d.
		Product type	APT.
Initial production	1982 (from district, 1917).	Distance shipped	3,496 km by truck.
Last production	Produced for a period in 1982.	Destination	Cleveland, OH (G.E.'s Refractory Metals products).

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

206, 259, 260, 263, 314, 329, 342, 343, 352, 376, 421, 478, 608, 685, 715, 739, 774, 830, 846, 848.

USGS quad maps	Lovelock, 1:250,000.
	Eugene Mountains Area, 15′.
USBM sequence number	0320270048.
USGS MRDS number	M060313.
Mid number	2600964.

STERLING—GOLD

Alternate names: Diamond Queen, Gold Ranch, North Panama, Panama, Abrose Open Pit

Commodities: Au, Ag, Hg, Sb (Au-Ag ratio ≈ 100:1)

LOCATION-OWNERSHIP

County	Nye.
Mining district	Bare Mountain.
Elevation	1,220 m.
Topography	Rugged, mountainous.
Domain	BLM administered.
General location	About 10 km east of Beatty.
Meridian	Mount Diablo.
Tract	Sec. 5, T 13 S, R 48 E (unsurveyed).
Latitude	36°49'50" N.
Longitude	116°38'25" W.
Owner-operator	Saga Exploration Co., Winnemucca, NV (1984).
Owner	Geomex Development, Inc., Calgary, AB, Canada, 46.5% (1984).

GEOLOGY

Type of ore body	Disseminated, fault zone, fissure-filling.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore control	Fault (thrust).
Strike and dip of mineralized zone.	North: unknown.
Age of mineralization	13.9 million yr.
Mineralized zone average dimensions, m:	
Length	Undetermined.
Width	Up to 25.
Thickness	Up to 20.
Mineral names	Free gold, kaolinite, halloysite, alunite, limonite, jarosite, calcite, fluorite, stibnite, cerrusite, galena, possible cinnabar and pyrite.
Host formations	Wood Canyon. Bonanza King.
Geologic ages	Possible Precambrian. Cambrian.
Rock relationships	Siltstone (breccia), contains ore (upper plate, Bonanza King). Shale, contains ore (upper plate, Bonanza King). Breccia, common in ore zone. Jasperoid (breccia), near ore, may be ore. Dolomite (breccia), near ore, lies beneath ore.
Alteration	Oxidation, silicification (below ore), kaolinization.
Size	Small.

DEVELOPMENT

Current status	Active-producer.
Type of operation	Underground, surface.
Year of discovery	1980 by Cordex exploration.
Discovery method	Unavailable.
Initial production	1980.
Past production	289 kg Au (9,303 tr oz) (1983) (*533*).
Annual production rate	280 to 370 kg Au.
Distance to water supply	Unknown.
Road requirement	Unknown.
Distance to power supply	On-site diesel electric generation.
Mill location	Estimated 1 km east of mine.
Mill status	Active.
Milling method	Cyanide heap leach, carbon column recovery.
Process rate	270 t/d (300 ton/d) projected in 1980 for crusher; crusher rated capacity is 82 t/h (90 ton/h) (see comments).

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference[1]	250,000 tons	0.5 tr oz/ton Au	1980	61
2..Proven, probable, possible[2]	200,000 tons	0.20 oz/ton Au	1983	533

REFERENCES

61, 97, 98, 209, 210, 533.

USGS quad maps	Death Valley, 1:250,000. Bare mountain, 15'.
USBM sequence number	0320230486.
Mid number	2601503.

Comments: Garside and Tingley (*210*) report disseminated gold mineralization occurs along thrust fault between upper plate siltstone and lower plate dolomite. The ore occurs mainly in the siltstone of the upper plate. Ore contains up to 0.5% Hg. In 1980, a test heap was planned in May and full-scale leaching was anticipated to commence as early as June or July 1980.

[1]Garside and Tingley (*210*) report ore below 0.1 tr oz/ton Au not mined. Ore grades are generally 0.5 to 1 tr oz/ton Au, but can be up to 4 tr oz/ton Au.

[2]Additional 7,500 tr oz recoverable gold reported in open pit. Total recoverable gold reserves is an estimated 41,000 tr oz.

STORMY CREEK—BARITE

Alternate names: None

Commodities: $BaSO_4$

LOCATION-OWNERSHIP

County	Elko.	General location	About 36 km northwest of Wells.
Mining district	Snake Mountains.	Meridian	Mount Diablo.
Elevation	2,195 m.	Tract	Sec. 27, T 42 N, R 61 E.
Topography	Rugged.	Latitude	41°31′24″ N.
Domain	Private.	Longitude	115°11′51″ W.
Owner[1]	(1983).		
Lessee	Old Soldier Minerals, Houston, TX (1983).		
Operator	Geowest Services, Inc., Elko, NV (1983).		

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Valmy.
Origin	Probably submarine volcanism.	Geologic age	Ordovician.
Shape of ore body	Tabular.	Rock relationships	Limestone, lies over ore.
Ore controls	Bedding.		Chert, lies over ore.
Strike and dip of mineralized zone.	N 15° W: nearly flat lying.	Size	Medium.
Mineralized zone average dimensions, m:			
Length	300.		
Width	200.		
Thickness	12.		
Depth	5.		
Mineral names	Barite.		

DEVELOPMENT

Current status	Inactive-past producer (standby).	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	On-site generation.
		Mill location	10.4 km from mine.
Year of discovery	Unknown.	Mill status	Standby.
Discovery method	Ore mineral in place.	Milling method	Crushing, jigging.
		Process rate	908 t/d.
Initial production	1981.	Product type	Crude barite.
Last production	1982.	Distance shipped	3,000 km to Abbeville, LA; 2,000 km to Elk City, OK.
Past production	Confidential proprietary data.		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

87, 205, 226, 330, 392, 546, 548, 612, 669, 688, 716.

USGS quad maps	Wells, 1:250,000.
	Stormy Peak, 7.5′.
USBM sequence number	0320070882.
Mid number	2601592.

[1]Ownership is divided among numerous individuals of the Wright and Marble families of Deeth, NV.

SUTHERLAND—ANTIMONY

Alternate names: Reid, Salvation, Kermesite, Thies-Hutchins

Commodities: Sb

LOCATION-OWNERSHIP

County	Pershing.
Mining district	Block Knob.
Elevation	1,603 m.
Topography	Rugged.
Domain	Private.
General location	About 19 km east of Lovelock.
Meridian	Mount Diablo.
Tract	Sec. 15, T 27 N, R 33 E.
Latitude	40°12′45″ N.
Longitude	118°15′35″ W.

Owner-operator ..... Saga Exploration Co., Winnemucca, NV (1976).

GEOLOGY

Type of ore body	Fault fissure.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Faulting, fracturing.
Strike and dip of mineralized zone.	Northwest: 80° W to 80° E.
Mineralized zone average dimensions, m:	
Length	150.
Width	75.
Thickness	1.
Depth	0.
Mineral names	Stibnite.
Host formation	Possible Auld Lang Syne Group.
Geologic ages	Triassic.
	Jurassic.
Rock relationships	Sandstone, encloses ore.
	Shale, near ore.
	Limestone, encloses ore.
Size	Small.

DEVELOPMENT

Current status	Inactive-past producer.
Type of operation	Underground.
Year of discovery	Unknown—prior to 1870.
Discovery method	Ore mineral in place.
Initial production	1870.
Last production	1975.
Past production	1,542 t Sb metal (*376*).
Distance to water supply	<50 km.
Road requirement	None.
Distance to power supply	<50 km.
Mill location	No mill.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

329, 376, 683, 718.

USGS quad maps	Lovelock, 1:250,000.
	Lovelock, 15′.
USBM sequence number	0320270355.
USGS MRDS number	M060406.
Mid number	2600544.

Comments: Sutherland Mine is reported to have been the largest antimony producer in Nevada. Most of the production was during World War I.

TAYLOR—SILVER

Associated pit names: Northwest, Northeast, Bishop, Argus

Commodities: Ag, Au

LOCATION-OWNERSHIP

County	White Pine.	General location	About 24 km southeast of Ely.
Mining district	Taylor.	Meridian	Mount Diablo.
Elevation	2,290 m.	Tract	Sec. 16, T 14 N, R 65 E.
Topography	Hilly, rugged.	Latitude	39°04′40″ N.
Domain	Mixed; private and National forest.	Longitude	114°40′50″ W.

Owner-operator ..... Silver King Mines, Inc., Salt Lake City, UT, 50% (1984).
Owner ..... NERCO Minerals Co., Fairbanks, AK, 50% (A subsidiary of Pacific Power and Light Co., Portland, OR) (1984).

GEOLOGY

Type of ore body	Disseminated, breccia fill, replacement.	Host formation	Guilmette (possibly Joana).
Origin	Hydrothermal.	Geologic age	Devonian.
Shape of ore body	Tabular, blanketlike.	Rock relationships	Limestone breccia, encloses ore.
Ore controls	Fractures, folding, bedding.		Jasperoid limestone, is ore, gangue.
Strike and dip of mineralized zone.	N 18° W: 40° E.		Rhyolitic dikes and sills, intrudes ore, contains ore zenoliths.
Age of mineralization	Cretaceous or Tertiary.	Alteration	Silicification (jasperiod).
Mineralized zone average dimensions (of central higher deposit), m:		Size	Medium.
Length	900.		
Width	150.		
Thickness	15.		
Depth	9.		

Mineral names ..... Argentite, native silver, possible cerargyrite, rare galena, chalcopyrite, tetrahedrite, sphalerite, stibnite, calcite, clay, limonite, rare fluorite.

DEVELOPMENT

Current status	Active-producer.[1]	Distance to water supply	1.8 km to deep wells.
Type of operation	Surface.	Road requirement	6 km was improved.
Mining method	Open pit, benched; ore production about 1,500 t/d; stripping ratio = 1.7:1 (waste:ore).	Distance to power supply	5-km 69-kV line installed.
		Mill location	On-site.
		Mill status	Producing.
		Milling method	Agitated cyanide leach, CCD, zinc dust precipitation.
Year of discovery	1868 (district); early 1960's (present deposit).	Process rate	1,090 t/d (1,200 ton/d).
Discovery method	Percussion drilling.	Product type	Silver precipitate.
		Distance shipped	885 km.
Initial production	1965 (by Silver King, underground); May 1981 (open pit).	Destination	Handy & Harmon, El Monte, CA.
Past production	District—about 54,000 t ore, 690 g/t Ag (prior to 1885).		
	District—about 91,000 t ore, 340 g/t Ag (1920–60).		
	Taylor underground—3,600 t ore, 1,030 g/t Ag (1964).		
	Taylor Pit—>87,000 kg Ag (1982 to early 1984) (*676*).		
Annual production rate	2,600 to 3,300 kg (85,000 to 105,000 tr oz/month).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven and indicated	10,000,000 tons	3.2 tr oz/ton Ag	1980	636
2..Measured and indicated	7,000,000 tons	3.2 tr oz/ton Ag (cutoff 2 tr oz/ton Ag)	1983	637

REFERENCES

12, 90, 120, 121, 153, 157, 165, 167, 251, 252, 284, 390, 414, 428, 429, 441, 442, 445, 446, 582, 636, 637, 644, 647, 652, 654, 676, 760, 777, 789, 790.

USGS quad maps ..... Ely, 1:250,000.
Conners Pass, 7.5′.
USBM sequence number ..... 0320330465.
Mid number ..... 2601564.

Comments: Mineralized zone—asymmetrical-plunging anticline; orientation of dimensions are gross estimates.

[1]The Taylor Mine closed after December 31, 1984, because of depressed silver prices.

THREE KIDS—MANGANESE

Alternate names: None

Commodities: Mn

LOCATION-OWNERSHIP

County	Clark.	General location	About 23 km southeast of Las Vegas.
Mining district	Las Vegas.	Meridian	Mount Diablo.
Elevation	550 m.	Tract	Sec. 35, T 21 S, R 63 E.
Topography	Hilly.	Latitude	36°04'50" N.
Domain	Mixed	Longitude	114°47'23" W.

Owner: Sam's Ranch Estate, Inc., Las Vegas, NV (1984).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Muddy Creek.
Origin	Hydrothermal, sedimentation.	Geologic age	Pliocene.
Shape of ore body	Tabular.	Rock relationships	Shale, lies over ore.
Ore controls	Lithology, faulting.		Evaporite, lies over ore.
Strike and dip of mineralized zone.	N 45° E: 30° N.		Gypsiferous sandstone, is ore.
			Dolomite, lies over ore.
			Andesite, lies under ore.
Mineralized zone average dimension, m:		Size	Large.
Length	417.		
Width	396.		
Thickness	12.		
Depth	39.		
Mineral names	Wad, psilomelane, pyrolusite.		

DEVELOPMENT

Current status	Inactive, past producer.	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	On-site.
		Mill location	Milling facilities have been removed from site.
Year of discovery	1917.		
Discovery method	Ore mineral in place.		
Initial production	1917.		
Last production	1961.		
Past production	2,260,000 t ore averaging 18% Mn yielded nearly 610,000 t of concentrates averaging 45% Mn (*733*).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Demonstrated	7,230,000 t	13.2% Mn	1982	351

REFERENCES

9, 41, 262, 267, 291, 327, 351, 386, 399, 407, 457, 547, 721, 726, 733, 743, 744.

USGS quad maps	Las Vegas, 1:250,000.
	Henderson, 7.5'.
USBM sequence number	0320030010.
USGS MRDS number	M031085.

TONKIN SPRINGS—GOLD

Alternate names: Rob Claim Group

Commodities: Au

LOCATION-OWNERSHIP

County	Eureka.	General location	About 95 km northeast of Eureka.
Mining district	Antelope.	Meridian	Mount Diablo.
Elevation	2,130 m.	Tract	Sec. 3, T 23-1/2 N, R 49 E.
Topography	Hilly, mountainous.	Latitude	39°54′27″ N.
Domain	BLM administered.	Longitude	116°26′54″ W.

Owner-operator ..... Silver State Mine Corp., Denver, CO, 55% (1985).
Owner ..... Precambrian Exploration, Inc., Lakewood, CO, 45% (1985).

GEOLOGY

Type of ore body	Disseminated, replacement.	Host formation	Lower Vinini.
Origin	Hydrothermal.	Geologic age	Ordovician.
Shape of ore body	Stratiform; irregular in plan.	Rock relationships	Sandy dolomite limestone-jasperoid replacement, contains ore.
Ore controls	Northwest-trending fractures, volcanic capping, sill-like intrusive.		Black carbonaceous shale, near ore.
Strike and dip of mineralized zone.	Northwest: nearly horizontal.		Calcarenite, jasperoid replacement contains ore (best host).
Age of mineralization	Tertiary.		Siltstones, near ore.
Mineralized zone average dimensions, m:			Chert, near ore.
			Intrusives (syenite), near ore.
Length	450.		Tertiary volcanics, above ore.
Width	300.	Alteration	Silicification (jasperoid development), calcification, carbonization.
Thickness:			
Zone	85.		
Bed	≈5 to ≈25.	Size	Small.
Depth	0 to 70.		

Mineral names ..... Pyrite (auriferous), arsenopyrite (auriferous), possible free gold, realgar, orpiment, stibnite, calcite, jasper. (About 75% of the gold is thought to occur in sulfides.)

DEVELOPMENT

Current status	Active-exploration.	Distance to water supply	Unknown.
Type of operation	Would be surface.	Road requirement	Unknown.
Mining method	Would be open pit.	Distance to power supply	Unknown.
		Mill status	Feasibility.
Year of discovery	1981.	Milling method	Would require an autoclave system or some type of pressure chlorination-pressure acidation treatment.
Discovery method	Geochemical survey, geological mapping.		

Initial production ..... No production schedule established.
Past production ..... None.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	4,000,000 tons	0.05 tr oz/ton Au	1976	616
2..Indicated	2,500,000 tons	0.09 tr oz/ton Au; Upper Zone, stripping ratio = 2.4:1 (waste:ore).	1983	241
Indicated	500,000 tons	0.09 tr oz/ton Au; Lower Zone, stripping ratio = 14.7:1 (waste:ore).	1983	241

REFERENCES

27, 241, 486, 593, 616.

USGS quad maps ..... Millett, 1:250,000.
Roberts Creek Mountains, 15′.
USBM sequence number ..... 0320110229.

Comments: A northwest-trending set of high-angle normal faults, probably associated with basin and range rifting, is most important of two faulting patterns for mineralization. Gold distribution is homogeneous throughout microfractured rock along strike of mineral trend.

TONOPAH—TUNGSTEN

Alternate names: Moly Tonopah, Jack

Commodities: W, Cu, Mo

LOCATION-OWNERSHIP

County ..... Humboldt.
Mining district ..... Potosi.
Elevation ..... 1,743 m.
Topography ..... Rugged.
Domain ..... Unknown.

Owner-operator ..... Unavailable.

General location ..... About 53 km northeast of Winnemucca.
Meridian ..... Mount Diablo.
Tract ..... Sec. 33, T 39 N, R 42 E.
Latitude ..... 41°12'36" N.
Longitude ..... 117°15'26" W.

GEOLOGY

Type of ore body ..... Replacement, contact metasomatism.
Origin ..... Sedimentary, igneous intrusion.
Shape of ore body ..... Undetermined.
Ore controls ..... Lithology, fracturing, faulting.
Strike and dip of mineralized zone. North-northeast: east.
Mineralized zone average dimensions, m:
Length ..... >907.
Width ..... Unknown.
Thickness ..... Up to 4.6.
Depth ..... Unknown.
Mineral names ..... Chrysocolla, calcite, epidote, quartz pyrite, chalcopyrite, molybdenite, scheelite, powellite.

Host formation ..... Preble.
Geologic age ..... Cambrian.
Rock relationships ..... Granodiorite, lies along ore.
Skarn, is ore.
Marble, lies along ore, encloses ore.
Hornfels, lies along ore, encloses ore.
Limestone, replaced by ore, lies along ore.
Size ..... Medium.

DEVELOPMENT

Current status ..... Inactive-past producer.
Type of operation ..... Surface, underground.
Mining method ..... Open pit, overhand stope.

Year of discovery ..... Before 1950.
Discovery method ..... Undetermined.

Initial production ..... 1950.
Last production ..... Unknown.
Past production ..... 19,750 tons ore, averaging 0.3% WO_3 containing 5,925 short ton units[1] WO_3 (*285*).

Distance to water supply ... On-site.
Distance to power supply ... On-site.
Road requirement ..... On-site.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

263, 269, 270, 272, 285, 801.

USGS quad maps ..... McDermitt, 1:250,000.
Osgood Mountains, 15'.
USBM sequence number ..... 0320130047.
USGS MRDS number ..... M030029.

Comments: Property is 183 to 366 m west of South Extension pit of the Getchell gold mine, operated by Getchell Mine, Inc., 1950–55. See references for Getchell Mine for additional information.

[1]Short ton unit = 20 lb of contained WO_3.

TONOPAH DIVIDE—GOLD

Alternate names: Old Big Divide, Gold Hill, Gold Mountain, Divide

Commodities: Au, Ag

LOCATION-OWNERSHIP

County	Esmeralda.
Mining district	Divide.
Elevation	1,890 m.
Topography	Hilly, mountainous.
Domain	Unknown.
General location	About 10 km south of Tonopah.
Meridian	Mount Diablo.
Tract	Sec. 26, T 2 N, R 42 E.
Latitude	37°59'42" N.
Longitude	117°14'17" W.
Owner	Tonopah Divide Mining Co., Reno, NV (1984).
Operator	Ebco Enterprises, Tonopah, NV (Parent company is Falcon Explorations Co., Emeryville, CA. A lease-option agreement on the property has been held since 1980.) (1984)

GEOLOGY

Type of ore body	Vein, disseminated in stockwork.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Faults, fractures (shear zone).
Strike and dip of mineralized zone.	N 40° W: nearly vertical (main lode).
Age of mineralization	Miocene (16 to 17 million yr).
Mineralized zone average dimensions (size as determined by assay walls) (*361*), m:	
Length	150.
Width	135.
Thickness	6.5.
Depth	0.
Mineral names	Cerargyrite, "sooty" argentite, molybdenite, powellite, ferrimolydite, sphalerite, chalcopyrite, argentiferous galena, possible tetrahedrite, limonite, sericite, pyrite, adularia, quartz, kaolinite.
Host formations	Volcanics—Fraction Breccia (principal host). Siebert—Oddie Rhyolite.
Geologic age	Tertiary.
Rock relationships	Rhyolitic volcanics, fractures contain ore, gangue. Rhyolitic breccia, fractures contain ore, gangue.
Alteration	Minor silicification, sericitic, chloritic, oxidation, pyritization; potassic, and propylitic zoned around fault zone.
Size	Small.

DEVELOPMENT

Current status	Active-producer.
Type of operation	Surface.
Mining method	Open pit; 1981-82 production rate was about 900 t/d ore.
Year of discovery	1902, Au; 1917, Ag (district).
Initial production	About 1912; 1981 by Falcon Exploration Co.
Last production	Closed in July 1982; reported active in 1983-84. Open pit expected to be mined out by end of 1984.
Past production	District total; 101,866 kg (3,275,079 tr oz) Ag; 1,010 kg (32,474 tr oz) Au. Most production from 1920-29 and from Tonopah Divide Mine (*209*).
Distance to water supply	On-site, 154-m well (mill).
Road requirement	Existing.
Distance to power supply	Unknown.
Mill location	10 km southwest of mine in Alkali Flat.
Mill status	Active.
Milling method	Cyanide heap leach, zinc precipitation (Ag), carbon precipitation (Au).
Process rate	907 t/d (1,000 ton/d) (1981); rated crusher capacity of 181 t/h (200 ton/h).

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.[1]

REFERENCES

7, 8, 62, 63, 64, 65, 209, 211, 361, 377, 629, 703.

USGS quad maps	Goldfield, 1:250,000. Mud Lake, 15'.
USBM sequence number	0320090087.
USGS MRDS number	M030063.
Mid number	2601527.

Comments: Original mine life planned in 1981 was 5 yr. The mine plan was to initially mine and truck 70,000 t of mine dumps to the millsite at the approximate rate of 907 t/d. After completion of mining the dumps, mining would commence on the main open pit that contains approximately 1.45 million t ore. Each heap pad contains approximately 360,000 t ore.

[1]Falcon Exploration 1981 operations plans were to initially mine about 1.5 million t of combined dump material and lode material. Garside and Tingley's field examination report of March 26, 1982 (*211*), states that the average grade is 8.6 g/t (0.25 tr oz/ton) Ag and about 2.7 g/t (0.08 tr oz/ton) Au.

TONOPAH HASBROUCK—GOLD

Alternate names: None

Commodities: Au, Ag

LOCATION-OWNERSHIP

County	Esmeralda.	General location	About 8 km southwest of Tonopah.
Mining district	Divide.	Meridian	Mount Diablo.
Elevation	1,735 m.	Tract	Sec. 33, T 2 N, R 42 E.
Topography	Hilly, mountainous.	Latitude	37°59'29" N.
Domain	BLM administered, private.	Longitude	117°16'09" W.

Owner: Cordex Exploration Co., Reno, NV (1984).

GEOLOGY

Type of ore body	Fissure veins, disseminated.	Host formation	Siebert (Volcanic).
Origin	Hydrothermal.	Geologic age	Miocene.
Shape of ore body	Tabular.	Rock relationships	Rhyolite tuff, contains disseminated Au.
Ore controls	Faulting, fracturing, lithology.		Dacite and rhyolite breccia, contains ore.
Age of mineralization	Mid-Miocene (15.5 to 16.5 million yr).		Volcaniclastics, cut by ore veins, below disseminated Au.
Mineralized zone average dimensions, m:		Alteration	Argillic, silicification, oxidation; potassic, phyllic, propylitic zones around fractures and faults.
Length	>1,500 (workings).	Size	Small.
Depth	>90.		
Mineral names	Free gold, electrum, argentite, silver halides, pyrite, quartz, sericite.		

DEVELOPMENT

Current status	Active-exploration, past producer.
Type of operation	Explored by Cordex for low-grade precious metal open pit.
Year of discovery	1902, Ag discovered in district; 1974, exploration commenced by Cordex Exploration Co.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	5,000,000 tons	0.06 tr oz/ton Au, 1.5 tr oz/ton Ag	1982	611

REFERENCES

7, 8, 62, 63, 64, 65, 209, 211, 224, 361, 377, 381, 611, 629.

USGS quad maps	Goldfield, 1:250,000. Klondike 7.5'.
USBM sequence number	0320090339.

Comments: Sixteen samples taken from silicified sedimentary rocks on Hasbrouck Mountain by the Nevada Bureau of Mines and Geology in the 1970's averaged 2 g/t (0.06 tr oz/ton) Au and 43.2 g/t (1.26 tr oz/ton) Ag (*211*).

VICTORIA—COPPER

Alternate names: Anaconda-Victoria

Commodities: Cu, Ag, Bi

LOCATION-OWNERSHIP

County	Elko.	General location	About 126 km northeast of Ely.
Mining district	Dolly Varden.	Meridian	Mount Diablo.
Elevation	2,316 m.	Tract	Sec. 5, T 28 N, R 66 E.
Topography	Rugged.	Latitude	40°19'45" N.
Domain	Private.	Longitude	114°33'05" W.
Owner-operator	Hecla Mining Co., Wallace, ID (1985).		

GEOLOGY

Type of ore body	Skarn-breccia pipe.	Host formation	Pequop.
Origin	Solution collapse, contact metamorphism.	Geologic age	Permian.
Shape of ore body	Arcuate in plan.	Rock relationships	Limestone, encloses ore, breccia contains ore.
Ore controls	Fracturing, contact zone.		Dolomite, encloses ore, breccia contains ore.
Dip of mineralized zone.	45°		Calcareous sandstone-quartzite, encloses ore, breccia contains ore.
Age of mineralization	Possibly Cretaceous.		Quartz latite porphyry dike, near ore.
Mineralized zone average dimensions, m:			Porphyritic quartz monzonite, beneath ore.
Length	100.	Alteration	Silicification, argillic, oxidation.
Width	175.	Size	Medium.
Thickness	180.		
Mineral names	Chalcopyrite, pyrite, chalcocite, bornite, bismuthinite, quartz, calcite, wittichenite, covellite, chrysocolla, malachite, azurite, native copper (minor), cuprite, Fe-oxides, diopside, calcite.		

DEVELOPMENT

Current status	Inactive-past producer, standby.	Distance to water supply	On-site.
Type of operation	Underground.	Road requirement	None.
Mining method	Sublevel block caving.	Distance to power supply	On-site.
		Mill location	On-site.
Year of discovery	1872.	Mill status	Inactive, standby.
Discovery method	Ore mineral in place.	Milling method	Flotation.
		Process rate	907 t/d.
Initial production	1973-74 (Anaconda).	Product type	Cu-Ag concentrate.
Last production	1977 (Anaconda); 1981 (Day Mines, Inc.-Hecla Mining Co.).		
Past production	Confidential proprietary data.		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven	1,491,200 tons	2.34% Cu	1977	337
2..Probable	148,383 tons	2.51% Cu	1977	337

REFERENCES

25, 226, 337, 476, 669, 788, 823, 824, 836.

USGS quad maps	Elko, 1:250,000.
USBM sequence number	0320070001.
USGS MRDS number	W002693.
Mid number	2600558.

Comments: See reference 836 for additional reserve-resource data. Anaconda Minerals Co. explored the ore body in the early 1940's. Day Mines, Inc., purchased the property from Anaconda in 1979. Day Mines was purchased by Hecla in 1981. The Victoria ore body is a breccia-fill deposit in the Pequop Limestone Formation near the contact of the Melrose porphyritic quartz monzonite stock of Cretaceous-Jurassic age. Bedded limestone, dolomite, and sandstone sediments of the Pequop surrounding the Victoria ore body have strikes trending from N 34° E to almost due east. Dips range from 0° to 34° S to SW, with an average dip of approximately 20° SW (*337*).

VIRGIN RIVER—MANGANESE

Alternate names: None

Commodities: Mn

LOCATION-OWNERSHIP

County	Clark.	General location	About 61 km east of Las Vegas.
Mining district	Virgin River.	Meridian	Mount Diablo.
Elevation	439 m.	Tract	Sec. 13, T 20 S, R 67 E.
Topography	Hilly.	Latitude	36°11'40" N.
Domain	National recreation area.	Longitude	114°27'28" W.

Owner: United States (managed by National Park Service) (1985).

GEOLOGY

Type of ore body	Sedimentary.	Host formation	Muddy Creek.
Origin	Hydrothermal, sedimentation.	Geologic age	Pliocene.
Shape of ore body	Tabular.	Rock relationships	Shale, lies over ore.
Ore controls	Bedding, lithology.		Gypsiferous sandstone, is ore.
Strike and dip of mineralized zone.	N 5° W: 30° E.		Basalt, lies over and under ore.[1]
Mineralized zone average dimensions, m:		Size	Large.
Length	1,460.		
Width	260.		
Thickness	7.		
Depth	39.		
Mineral names	Wad.		

DEVELOPMENT

Current status	Inactive-explored.	Distance to water supply	<3 km.
Type of operation	Possible surface.	Road requirement	<50 km.
		Distance to power supply	<50 km.
Year of discovery	1902.	Mill location	No mill.
Discovery method	Ore mineral in place.		
Initial production	No production.		

PUBLISHED RESERVES-RESOURCES[2]

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Measured	14,000 tons	Average: 17% Mn: cutoff: 15% Mn:	1949	407
2.. Do	55,000 tons	Average: 15% Mn; cutoff: 12% Mn	1949	407
3.. Do	134,000 tons	Average: 13% Mn; cutoff: 10% Mn	1949	407
4.. Do	215,000 tons	Average: 12% Mn; cutoff: 8% Mn	1949	407
5.. Do	320,000 tons	Average: 10% Mn; cutoff: 5% Mn	1949	407

REFERENCES

9, 262, 267, 291, 327, 353, 386, 407, 547, 721, 726, 733

USGS quad maps	Las Vegas, 1:250,000. Virgin Basin, 15'.
USBM sequence number	0320030009.
USGS MRDS number	M031088.

[1]A 4.5-m basalt flow separates 2 manganiferous beds.
[2]Tonnages are cumulative and represent minimum mining width of 0.95 m.

WARD—ZINC-LEAD

Associated ore bodies: Caroline, Good Luck

Commodities: Zn-Pb, Ag, Cu, Au, Mo (Mo—not recoverable, deep seated)

LOCATION-OWNERSHIP

County	White Pine.	General location	About 13 km south-southwest of Ely.
Mining district	Ward.	Meridian	Mount Diablo.
Elevation	2,560 m.	Tract	Sec. 15, T 14 N, R 63 E.
Topography	Rugged.	Latitude	39°04′45″ N.
Domain	BLM administered.	Longitude	114°52′55″ W.

Owner-operator ..... Silver King Mines, Inc., Salt Lake City, UT (60%); Pacific Silver Corp., Salt Lake City, UT (40%) (1985).
Royalties to ..... Gulf Oil Corp., Denver, CO (a 2-1/2% net smelter return (NSR) on future production until accruance of $3.5 million); Phillips Petroleum Co., Bartlesville, OK (a 3% NSR).

GEOLOGY

Type of ore body	Replacement.	Host formations	Ely.
Origin	Hydrothermal.		Joana.
Shape of ore body	Tabular, mantos.		Guilmette Limestone.
Ore controls	Lithology, fracturing.	Geologic ages	Pennsylvanian.
Strike and dip of mineralized zone.	N 55° W: 20° E.		Mississippian.
			Devonian.
Age of mineralization	Tertiary.	Rock relationships	Limestone, gangue.
Mineralized zone average dimensions, m:			Skarn, replaced by ore.
			Marble, gangue.
Length	760.		Tertiary monzonite stock, sills, dikes, intrudes ore.
Width	60.		
Thickness	14.	Alteration	Carbonization, silicification.
Depth	280.	Size	Medium.

Mineral names ..... Sphalerite, chalcopyrite, galena, pyrite, covellite, chalcocite, barite, smithsonite, molybdenite, jasperoid.

DEVELOPMENT

Current status	Active-development.	Distance to water supply	<3 km.
Type of operation	Underground, access by twin 1,370-m declines.	Road requirement	None.
		Distance to power supply	<10 km.
Mining method	Unknown.	Mill location	On-site.
		Mill status	Development.
Year of discovery	1968 (deep ore bodies).	Milling method	Flotation.
Discovery method	Geological inference, drilling.	Process rate	1,100 t/d (1,200 ton/d) planned. Construction to begin in 1985, completion in late 1986.
Initial production	Expected in 1986-87.		
Last production	1967 (district).	Product type	Zn, Cu, Pb concentrates.

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference[1]	5,000,000 tons	3 tr oz/ton Ag; 1.4% Cu; 5.5% combined Pb-Zn at North Good Luck portion of deposit.	1983	637
Indicated	17,000,000 tons	30 million tr oz Ag; 2 billion lb combined Cu, Pb, and Zn.	1983	637

REFERENCES

145, 153, 166, 188, 203, 224, 258, 268, 284, 381, 424, 433, 471, 490, 633, 634, 635, 636, 637, 644, 645, 757, 776.

USGS quad maps	Ely, 1:250,000.
	Ely, 15′.
USBM sequence number	0320330112.
USGS MRDS number	W016410.
Mid number	2600576.

Comments: A 1,100-t/d (1,200-ton/d) flotation plant is being designed such that capacity can be increased to 1,800 t/d or 2,700 t/d (2,000 or 3,000 ton/d) at a later date. The first 5 yr of production are anticipated to average 100 g/t Ag, 5.5% Zn, and 1.4% Cu.

[1]Resource is referred to as blocked.

WHITE CAPS—ANTIMONY

Alternate names: None

Commodities: Au, Sb, As, Hg

LOCATION-OWNERSHIP

County	Nye.	General location	About 56 km northeast of Tonopah.
Mining district	Manhattan.	Meridian	Mount Diablo.
Elevation	2,438 m.	Tract	Sec. 21, T 8 N, R 44 E.
Topography	Rugged.	Latitude	38°31′54″ N.
Domain	Unknown.	Longitude	117°02′57″ W.

Owner: Argus Resources, Inc., Glendale, CA (1985).

GEOLOGY

Type of ore body	Replacement.	Host formation	White Caps Limestone Member of the Gold Hill Formation.
Origin	Replacement of limestone.		
Shape of ore body	Irregular.	Geologic age	Cambrian.
Ore controls	Lithology, faulting.	Rock relationships	Limestone, replaced by ore.
Mineralized zone average dimensions.	Unknown.	Size	Small.
Mineral names	Gold, realgar, pyrite, stibnite, fluorite, cinnabar, orpiment.		

DEVELOPMENT

Current status	Inactive-past producer.	Distance to water supply	Can be developed on-site.
Type of operation	Underground.	Road requirement	None.
		Distance to power supply	<10 km.
Year of discovery	1905.	Mill location	Unknown.
Discovery method	Ore mineral in place.		
Initial production	1911.		
Last production	1964.		
Past production	$2.5 million Au; 45 t Sb metal (*376*).		

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

29, 191, 192, 194, 195, 276, 357, 368, 376, 814.

USGS quad maps	Tonopah, 1:250,000. Manhattan, 7.5′.
USBM sequence number	0320230120.
USGS MRDS number	M05530.

Comments: White Caps Mine is primarily a gold deposit containing appreciable amounts of antimony in the form of stibnite.

WHITE PINE—FLUORINE

Alternate names: None

Commodities: CaF_2

LOCATION-OWNERSHIP

County	Nye.
Mining district	Unorganized.
Elevation	2,438 m.
Topography	Hilly.
Domain	National forest.
Owners	Maynard and Lester Bisoni (1981).
General location	About 61 km southwest of Ely.
Meridian	Mount Diablo.
Tract	Sec. 21, T 12 N, R 58 E.
Latitude	38°52′57″ N.
Longitude	115°26′55″ W.

GEOLOGY

Type of ore body	Disseminated, replacement.
Origin	Hydrothermal.
Shape of ore body	Tabular.
Ore controls	Bedding, faulting.
Strike and dip of mineralized zone.	N 40° W: 30° E.
Mineralized zone average dimensions, m:	
Length	990.
Width	300.
Thickness	210.
Mineral names	Fluorite, calcite, quartz, vesuvianite, mica, diopside, orthoclase, chlorite.
Host formation	Lincoln Peak.
Geologic age	Cambrian.
Rock relationships	Phyllite, encloses ore, ore in fractures.
	Limestone, encloses ore, replaced by ore.
	Rhyolite, near ore.
	Quartz monzonite, near ore.
	Quartz diorite, near ore.
Size	Large.

DEVELOPMENT

Current status	Inactive-explored prospect.
Type of operation	Surface.
Mining method	Proposed open pit.
Year of discovery	1976.
Discovery method	Ore mineral in place.
Initial production	None.
Distance to water supply	On-site.
Road requirement	<10 km.
Distance to power supply	<50 km.

PUBLISHED RESERVES-RESOURCES

No published reserve-resource information.

REFERENCES

455, 456, 545.

USGS quad maps	Lund, 1:250,000.
	Currant Mountain, 15′.
USBM sequence number	0320230667.

WINDFALL—GOLD

Alternate names: Eureka Windfall Mine, Western-Windfall Project
Ore bodies: Windfall, Rustler, Paroni

Commodities: Au, Ag
(Au-Ag ratio ≈5.7:1)

LOCATION-OWNERSHIP

County	Eureka.	General location	About 6.5 km south of Eureka.
Mining district	Eureka (Pinto).	Meridian	Mount Diablo.
Elevation	2,330 m.	Tract	Sec. 2, T 18 N, R 53 E.
Topography	Rugged.	Latitude	39°27′15″ N.
Domain	Mixed; private and BLM administered.	Longitude	115°58′42″ W.

Owner: Western Mining Services Ltd., Reno, NV (subsidiary of Western Gas, Oil and Mining, Reno, NV) (1982).
Operator: Western-Windfall Ltd., Eureka, NV (operational entity of Western Mining Services Ltd.) (1982).

GEOLOGY

Type of ore body	Disseminated, replacement.
Origin	Hydrothermal, oxidation.
Shape of ore body	Sheeted, wedge-shaped.
Ore controls	Fracturing, faulting, folding, lithology.
Age of mineralization	Late Cretaceous-Tertiary.
Mineralized zone average dimensions, m:	
Length	About 2,000.
Width	30 to 60.
Thickness	>300.
(Rustler ore body—400 m by 200 m by 300 m deep).	
Mineral names	Free gold, silver, iron oxides, arsenopyrite, kaolinite, jasperoid, quartz, calcite.
Host formations	Hamburg Dolomite.
	Dunderberg Shale.
Geologic ages	Mid-Cambrian.
	Upper Cambrian.
Rock relationships	Sanded dolomite, ore in fractures, lies under ore (Windfall ore body).
	Shale, ore in fractures, lies above ore.
	Jasperoid, contains ore (Rustler ore body).
	Oligocene intrusive and extrusive rhyodacite, lies near ore, lies above ore (ore bodies localize along shale-dolomite contact).
Size	Small.

DEVELOPMENT

Current status	Active-producer.
Type of operation	Surface.
Mining method	Open pit; multiple bench (3 m); about 320,000 t/a ore.
Year of discovery	1902 or 1908; rediscovered in 1974 by Idaho Mining Corp.
Discovery method	Geochemical anomaly (1974); drilling.
Initial production	1975.
Last production	1983.
Past production	About 59,000 t ore, 10 g/t Au (1908–19) (*232*); published production of recent years is unavailable.
Annual production rate	Reported 200 kg (5,000 tr oz) Au from leaching about 320,000 t ore (1982)
Distance to water supply	6.5 km to wells.
Distance to power supply	3.2-km electric transmission line installed.
Mill location	On-site.
Mill status	Active.
Milling method	Cyanide heap leach, carbon adsorption, electrolysis, smelting.
Process rate	1,100 t/d (1,250 ton/d) (1980).
Product type	Dore bullion (60% Au, 30% Ag).

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Proven and indicated	3,000,000 tons	0.03 tr oz/ton Au	1975	805

REFERENCES

80, 83, 232, 365, 378, 412, 518, 520, 522, 552, 593, 692, 775, 805.

USGS quad maps	Ely, 1:250,000.
	Pinto Summit, 15′.
USBM sequence number	0320110142.
Mid number	2600891.

Comments: The Hamburg Dolomite is the principal host. The Windfall Mine reopened and shut down again in 1983. As a result of the permeable texture of the Windfall ore, it was not necessary to crush it prior to heap leaching. Pond irrigation (rather than sprinkler irrigation) enables year-round leaching operations. The Windfall ore body is depleted, the Rustler ore body is being mined, and the Paroni ore body is being developed.

YERINGTON—COPPER

Alternate names: Anaconda Copper, Empire Nevada

Commodities: Cu, Mo, Ag, Au

LOCATION-OWNERSHIP

County	Lyon.	General location	About 53 km southeast of Carson City.
Mining district	Mason.	Meridian	Mount Diablo.
Elevation	1,365 m.	Tract	Sec. 16, T 13 N, R 25 E.
Topography	Rolling.	Latitude	38°59'01" N.
Domain	Private.	Longitude	119°11'35" W.

Owner[1] ..... Don Tibbals, Yerington, NV (1985).

GEOLOGY

Type of ore body	Disseminated, stockwork.	Host formation	Yerington Batholith.
Origin	Hydrothermal.	Geologic age	Jurassic.
Shape of ore body	Massive.	Rock relationships	Quartz monzonite, ore in fractures, gangue.
Ore controls	Igneous, fracturing.		Granodiorite, ore in fractures, gangue.
Strike and dip of mineralized zone.	N 60° W: 05° W.	Size	Large.
Mineralized zone average dimensions, m:			
Length	1,650.		
Width	490.		
Thickness	195.		
Depth	60.		

Mineral names ..... Chalcopyrite, bornite, covellite, pyrite, magnetite, chrysocolla, cuprite, tenorite, malachite, chalcocite, copper.

DEVELOPMENT

Current status	Inactive-past producer, abandoned.	Distance to water supply	On-site.
Type of operation	Surface.	Road requirement	None.
Mining method	Open pit.	Distance to power supply	On-site.
		Mill status	Dismantled.
Year of discovery	1865.		
Discovery method	Ore mineral in place.		
Initial production	1953.		
Last production	1978.		
Past production	771,000 t Cu from 144 million t ore (*49*).		

PUBLISHED RESERVES-RESOURCES

Class	*Quantity*	*Grade*	*Year*	*Reference*
1..Not reported in reference	126,900,000 tons	0.343% Cu	1982	49

REFERENCES

25, 49, 126, 128, 140, 286, 295, 320, 360, 453, 467, 567, 574, 575, 666, 695, 822, 824.

USGS quad maps	Walker Lake, 1:250,000. Yerington, 15'.
USBM sequence number	0320190001.
USGS MRDS number	M030104.
Mid number	2600085.

[1]In 1982, Don Tibbals reached an agreement to purchase the Yerington property from the Anaconda Minerals Co., Denver, CO. At that time, Tibbals planned to convert most of the 3,295 ha (8,143 acres) into an industrial park, consisting of about 50 industrial buildings, 170 homes, 20 apartments, recreational buildings, and utilities including a sewage system.

REFERENCES

1. Adair, D. H. Intrusive Igneous Rocks of East Central Nevada, Intermountain Association Petroleum Geology Guidebook to the Geology of East Central Nevada. 11th Annu. Field Conf., UT Geol. Assoc., Salt Lake City, UT, 1960, pp. 229-231.

2. Adkins, A. R., and J. C. Rota. General Geology of the Carlin Gold Mine, Field Trip 1, Sediment-Hosted Gold Deposits. Paper in Exploration for Ore Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, pp. FT1 17-23.

3. Adler, L. Wildlife Official Warns of Mercury Danger. The Nevada State J. (Reno), July 29, 1982, p. C2.

4. Ahern, R., and R. M. Corn. Mineralization Related to the Volcanic Center at Beatty, Nevada. Ch. in Relations of Tectonics to Ore Deposits in the Southern Cordillera, ed. by W. R. Dickinson and W. D. Payne. AZ Geol. Soc. Digest, v. 14, 1981, pp. 283-286.

5. Akhtar, S. Ore and Concentrate Buyers, Custom Mills and Smelters Available to Nevada Mine Operators. NV Bur. Mines and Geol. Spec. Publ. L-2, 1977, 4 pp.

6. Akright, R. L., A. S. Radtke, and D. J. Grimes. Minor Elements as Guides to Gold in the Roberts Mountains Formation, Carlin Gold Mine, Eureka County, Nevada. CO School of Mines Q., v. 64, No. 1, 1969, pp. 49-66.

7. Albers, J. P., and F. J. Kleinhampl. Spatial Relation of Mineral Deposits to Tertiary Volcanic Centers in Nevada. U.S. Geol. Surv. Prof. Paper 700-C, 1970, pp. C1-C10.

8. Albers, J. P., and J. H. Stewart. Geology and Mineral Deposits of Esmeralda County, Nevada. NV Bur. Mines and Geol. Bull. 78, 1972, 80 pp.

9. Allen, G. L., J. H. Jacobs, and J. W. Hunter. Utilization of Three Kids Manganese Ore in Production of Electrolytic Manganese. BuMines RI 3815, 1945, 78 pp.

10. American Iron Ore Association. Iron Ore 1979. Cleveland, OH, 1980, 115 pp.

11. American Metals Market. U. V. Encouraged by New Find of Molybdenum at Nevada Site. V. 86, No. 97, May 19, 1978, 7 pp.

12. _____. Taylor Silver Mine is Shut Indefinitely. V. 90, No. 123, June 24, 1982, p. 6.

13. _____. Nevada Gold, Silver Mill Expanded by Duval. V. 91, No. 87, May 4, 1983, p. 6.

14. _____. Lacana Starts Work on Nevada Gold Mine. V. 92, No. 3, Jan. 5, 1984, p. 6.

15. Amselco Minerals, Inc. Alligator Ridge Mine: Fact Sheet. Handout to Field Trip 2, Sediment-Hosted Precious Metal Deposits. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, 7 pp.

16. Argall, G. O., Jr., and P. Rapalus. United States Open Pit and Underground Mine Tonnage. World Min., v. 34, No. 10, 1981, p. 50.

17. Arizona Pay Dirt (Bisbee, AZ). Of Mines and Men. No. 466, Apr. 1978, p. 59.

18. Arkell, B. D. Net Proceeds of Mine Taxes and Mining Employment and Payroll Data. NV Bur. Mines and Geol. OFR 80-1, 1980, 21 pp.

19. Ashley, R. P. Premineralization Structural History of the Goldfield Mining District, Nevada. Abstr., Econ. Geol. and Bull. Soc. Econ. Geol., v. 67, 1972, p. 1002.

20. _____. Goldfield Mining District. Ch. in Guidebook to the Geology of Four Tertiary Volcanic Centers in Central Nevada. NV Bur. Mines and Geol. Rep. 19, 1974, pp. 49-66.

21. _____. Preliminary Geologic Map of the Goldfield Mining District, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF-681, 1975, scale 1:24,000.

22. _____. Relation Between Volcanism and Ore Deposition at Goldfield, Nevada. Paper in Papers on Mineral Deposits of Western North America. NV Bur. Mines and Geol. Rep. 33, 1979, pp. 77-86.

23. Ashley, R. P., and W. J. Keith. Distribution of Gold and Other Metals in Silicified Rocks of the Goldfield Mining District, Nevada. U.S. Geol. Surv. Prof. Paper 843-B, 1976, 17 pp.

24. Ashley, R. P., and M. L. Silberman. Direct Dating of Mineralization at Goldfield, Nevada, by Potassium-Argon and Fission-Track Methods. Econ. Geol. and Bull. Soc. Econ. Geol., v. 71, 1976, pp. 904-924.

25. Atlantic Richfield Co. Form S-14 Registration Statement. Securities and Exchange Commission, 1976, pp. 60-68.

26. Atlantic Richfield Co.—Anaconda Minerals Co. Merger. Registration Under the Securities Act of 1933, Form S-14. Sept. 1976, pp. 82-83.

27. Bagby, W. C. Sediment-Hosted Disseminated Gold Deposits in Nevada: A Review of Their Geologic Characteristics. Abstr. No. 33,496 in Abstracts With Programs, 1984. 97th Annu. Meeting, Geol. Soc. Am., Nov. 5-8, 1984, Reno, NV, p. 434.

28. Bagby, W. C., W. J. Pickthorn, R. Goldfarb, and R. A. Hill. Application of Rank Sum Analysis to Soil Geochemistry at the Dee Gold Mine, Elko County, Nevada. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, p. 32.

29. Bailey, E. H., and D. A. Phoenix. Quicksilver Deposits in Nevada. NV Bur. Mines and Geol. Bull. 41, v. 38, No. 5, 1944, 206 pp.

30. Baker, A. III, N. L. Archbold, and W. J. Stoll. Forecasts for the Future—Minerals. NV Bur. Mines and Geol. Bull. 82, 1973, 223 pp.

31. Ball, S. H. A Geologic Reconnaissance in Southwestern Nevada and Eastern California. U.S. Geol. Surv. Bull. 308, 1907, 218 pp.

32. Barrett, W. T., and B. J. O'Neill, Jr. Recovery of Lithium From Saline Brines Using Solar Evaporation. Sec. in 3d Symp. on Salt, ed. by J. L. Rau and L. E. Dellwig. Northern OH Geol. Soc., Inc., Cleveland, OH, v. 2, 1970, pp. 47-50.

33. Batchelder, J. N. A Study of Stable Isotopes and Fluid Inclusions at Copper Canyon, Lander County, Nevada. M.S. Thesis, CA State Univ., San Jose, CA, 1973, 92 pp.

34. _____. Light Stable Isotope and Fluid Inclusion Study of the Porphyry Copper Deposit at Copper Canyon, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 72, No. 1, 1977, pp. 60-70.

35. Batchelder, J. N., and D. W. Blake. Geochemical Variations in the Copper Canyon Porphyry Copper Deposits, Lander County, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 70, No. 7, 1975, p. 1318.

36. Batty, J. V., and W. W. Agey. Concentration of Manganese Ores From Boulder Dam Recreational Area, Clark County, Nevada. BuMines RI 4302, 1948, 12 pp.

37. Bauer, H. L., Jr., R. A. Breitrick, J. J. Cooper, and J. A. Anderson. Porphyry Copper Deposits in the Robinson Mining District, Nevada. Intermountain Association Petroleum Geology Guidebook to the Geology of East Central Nevada. 11th Annu. Field Conf., UT Geol. Assoc., Salt Lake City, UT, 1960, pp. 220-228.

38. _____. Porphyry Copper Deposits in the Robinson Mining District, Nevada. Paper in Geology of the Porphyry Copper Deposits in Southwestern North America, ed. by S. R. Titley and C. L. Hicks. Univ. AZ Press, 1966, pp. 233-244.

39. Beall, J. V. Copper in the U.S.—A Position Survey. Min. Eng. (NY), v. 25, No. 4, 1973, pp. 35-47.

40. Bell Mountain Mining Co. Interim Report—Message to Stockholders. Jan. 1, 1982, 2 pp; available from American Pyramid, Inc., Vancouver, B.C., Canada.

41. Bender, F. N., and C. Rampacek. Percolation Leaching of Manganese Ores With Sulfur Dioxide. BuMines RI 5323, 1957, 20 pp.

42. Benson, W. T. Investigation of Mercury Deposits in Nevada and in Malheur County, Oregon. BuMines RI 5285, 1956, 54 pp.

43. Berger, B. R. Trace Element Variations Associated With Disseminated Gold Mineralization at the Getchell Mine, Humboldt County, Nevada. Abstr. Econ. Geol. and Bull. Soc. Econ. Geol., v. 70, 1975, p. 1318.

44. _____.Geology and Geochemistry of the Getchell Disseminated Gold Deposit, Humboldt County, Nevada. Soc. Min. Eng. AIME preprint 75-I-305, 1975, 26 pp.

45. _____. Geological and Geochemical Relationships at the Getchell Mine and Vicinity, Humboldt County, Nevada. SEG-USGS Field Trip Guide to Epithermal Precious Metal Deposits of Northwestern Nevada, 1980, pp. 11-135; available at NV Bur. Mines and Geol., Reno, NV, in district file 136.

46. Berger, B. R., and P. I. Eimon. Comparative Models of Epithermal Silver-Gold Deposits. Pres. at Soc. Min. Eng. AIME Annu. Meeting, Dallas, TX, Feb. 14-18, 1982. Soc. Min. Eng. AIME preprint 82-13, 10 pp.

47. Berger, B. R., and B. E. Taylor. Pre-Cenozoic Normal Faulting in the Osgood Mountains, Humboldt County, Nevada. Geol., v. 8, No. 12, 1980, pp. 594-598.

48. Big Sky Pay Dirt (Bisbee, AZ). Nevada's Historic Candelaria Mining District is Again Producing Silver. Jan. 1981, pp. 28-29.

49. _____. Anaconda Reviewing Bids for Yerington. Nov. 1982, p. 45.

50. Binyon, E. O. Exploration of the Gold, Silver, Lead, and Zinc Properties, Eureka Corporation, Eureka County, Nevada. BuMines RI 3949, 1946, 18 pp.

51. _____. Gibellini Manganese-Zinc-Nickel Deposits, Eureka County, Nevada. BuMines RI 4162, 1948, 9 pp.

52. Binyon, E. O., G. H. Holmes, Jr., and A. C. Johnson. Investigation of the Tem Piute Tungsten Deposit, Lincoln County, Nevada. BuMines RI 4626, 1950, 16 pp.

53. Birak, D. J. Geology of the Enfield Bell Mine and Jerritt Canyon District, Elko County, Nevada. Abstr. No. 33,497 in Abstracts With Programs, 1984. 97th Annu. Meeting, Geol. Soc. Am., Nov. 5-8, 1984, Reno, NV, p. 445.

54. Blake, D. W., and E. L. Kretschmer. Gold Deposits at Copper Canyon, Lander County, Nevada. NV Bur. Mines and Geol. Rep. 36, 1983, pp. 3-10.

55. Blake, D. W., E. L. Kretschmer, and T. G. Theodore. Geology and Mineralization of the Copper Canyon Deposits, Lander County, Nevada. NV Bur. Mines and Geol. Rep. 32, 1978, pp. 45-48.

56. Blake, D. W., T. G. Theodore, J. N. Batchelder, and E. L. Kretschmer. Structural Relations of Igneous Rocks and Mineralization in the Battle Mountain Mining District, Lander County, Nevada. Paper in Papers on Mineral Deposits of Western North America. NV Bur. Mines and Geol. Rep. 33, 1979, pp. 878-889.

57. Blake, D. W., T. G. Theodore, and E. L. Kretschmer. Alteration and Distribution of Sulfide Mineralization at Copper Canyon, Lander County, Nevada. AZ Geol. Soc. Digest 11, 1978, pp. 67-78.

58. Blake, J. W. Geology of the Bald Mountain Intrusive, Ruby Mountains, Nevada. M.S. Thesis, Brigham Young Univ., Provo, UT, 1964, 35 pp.

59. Bloomstein, E. I. Ammonia Alteration is a Geochemical Link in Gold Deposits of the Carlin-Midas Belt. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, March 25-28, 1984, p. 27.

60. Bohn, E. E., Jr., and I. J. Goldstein. Electron Microscopy of Some Disseminated Gold Deposits. 1969, 43 pp.; available upon request from Mackay School of Mines Library, Univ. NV, Reno, NV.

61. Bonham, H. F., Jr. Reserves, Host Rocks, and Ages of Bulk-Mineable Precious Metal Deposits in Nevada. NV Bur. Mines and Geol. OFR 82-9, 1982, 4 pp.

62. Bonham, H. F., Jr., and L. J. Garside. Road Log and Trip Guide, Carver Station—Tonopah District. Guidebook to the Geology of Four Tertiary Volcanic Centers in Central Nevada. NV Bur. Mines and Geol. Rep. 19, 1974, pp. 6-13.

63. _____. Tonopah Mining District and Vicinity. Guidebook to the Geology of Four Tertiary Volcanic Centers in Central Nevada. NV Bur. Mines and Geol. Rep. 19, 1974, pp. 42-48.

64. _____. Geology of the Tonopah, Lone Mountain, Klondike, and Northern Mud Lake Quadrangles, Nevada. NV Bur. Mines and Geol. Bull. 92, 1979, 142 pp.

65. _____. Geochemical Reconnaissance of the Tonopah, Lone Mountain, Klondike, and Northern Mud Lake Quadrangles, Nevada. NV Bur. Mines and Geol. Bull. 96, 1982, 68 pp.

66. Bonham, H. F., Jr., and K. G. Papke. Geology and Mineral Deposits of Washoe and Storey Counties, Nevada. NV Bur. Mines and Geol. Bull. 70, 1969, 140 pp.

67. Brooks, R. A., and B. R. Berger. Relationship of Soil-Mercury Values to Soil Type and Disseminated Gold Mineralization, Getchell Mine Area, Humboldt County, Nevada. J. Geochem. Explor., v. 9, No. 2/3, 1978, pp. 186-194.

68. Burke, D. B. Reinterpretation of the Tobin Thrust: Pre-Tertiary Geology of the Southern Tobin Range, Pershing County, Nevada. Ph.D. Diss., Stanford Univ., Stanford, CA, 1973, 82 pp.

69. Buseck, P. R. Contact Metasomatism and Ore Deposition, Tem Piute, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 62, No. 3, 1967, pp. 331-353.

70. Bushnell, K. O. Geology of the Rowland Quadrangle, Elko County, Nevada. NV Bur. Mines and Geol. Bull. 67, 1967, 38 pp.

71. California Mining Journal. American Pyramid Discovers New Mineralized Zone. V. 51, No. 12, Aug. 1982, p. 46.

72. _____. $24 Million Mine Project to Start in Nevada. V. 52, No. 10, June 1983, p. 66.

73. Callicutt, W. Borealis: The Economic Advantages of a Fast-Track Approach. Heap and Dump Leaching, v. 1, No. 1, Jan. 1984, pp. 3-4, 6.

74. Cameron, E. N. Geology and Mineralization of the Northeastern Humboldt Range, Nevada. Geol. Soc. Am. Bull., v. 50, 1939, pp. 563-634.

75. Carlson, G. N., and R. A. Bauer. Hibbing Taconite Story—Pelletizing. Skillings' Mine Rev., v. 69, No. 12, Mar. 22, 1980, pp. 10-13.

76. Castelli, A. V. Barite—113th Annual Survey and Outlook. Eng. and Min. J., v. 183, No. 3, 1982, p. 135.

77. _____. Barite—U.S. Production Continues Strong, Sets Record at 2.4 Million S.T. Eng. and Min. J., v. 183, No. 3, 1982, pp. 135-136.

78. _____. Barite—114th Annual Survey and Outlook. Eng. and Min. J., v. 184, No. 3, 1983, p. 113.

79. Cavender, W. S. Integrated Mineral Exploration in the Osgood Mountains, Humboldt County, Nevada. Ph.D. Diss., Univ. CA, Berkeley, CA, 1963, 225 pp.

80. Chaffee, M. A., C. L. Forn, J. R. Hassemer, J. D. Hoffman, E. L. Moiser, J. M. Nishi, R. M. O'Leary, D. F. Siems, R. L. Turner, E. P. Welsh, and G. Van Trump. Geochemical Analyses of Rock and Soil Samples, Eureka Mining District and Vicinity, Eureka and White Pine Counties. U. S. Geol. Surv. OFR 78-790, 1978, 117 pp.

81. Chamberlain, C. C. Mining Methods With Emphasis on Cost Records at Getchell Mine. Min. Congr. J., v. 49, No. 10, 1963, pp. 93-96.

82. Chamberlain, P. D. Heap Leaching and Pilot Testing of Gold and Silver Ores. Paper in Papers Given at the Precious-Metals Symposium, Sparks, NV, Nov. 17-19, 1980. NV Bur. Mines and Geol. Rep. 36, 1983, pp. 77-83.

83. Chamberlain, P. G., and M. G. Pojar. Gold and Silver Leaching Practices in the United States. BuMines IC 8969, 1984, 47 pp.

84. Chender, M. (ed.). Gold Projects in the United States: A Minesearch Report. Met. Econ. Group, Boulder, CO, 1983, 142 pp.

85. Churkin, M., Jr., and M. Kay. Graptolite-Bearing Ordovician Siliceous and Volcanic Rocks, Northern Independence Range, Nevada. Geol. Soc. Am. Bull., v. 78, 1967, pp. 651-668.

86. Clark, C. W. Geology and Ore Deposits of the Santa Fe District, Mineral County, Nevada. Univ. CA Publ., Bull. Dept. Geol. Sci., v. 14, No. 1, 1922, pp. 1-74.

87. Clarke, G. (ed.). Barytes in Nevada—Back to Pre-1974 Levels. Ind. Min. (London), No. 200, May 1984, pp. 53-61.

88. Clement, S. C. Mineralogy and Petrology of the Copper Canyon Quartz Monzonite Porphyry, Battle Mountain, Nevada. Ph.D. Diss., Cornell Univ., Ithaca, NY, 1964, 108 pp.

89. _____. Supergene Copper Concentration in Altered Plagioclase Feldspar, Copper Canyon, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 63, No. 4, 1968, pp. 401-408.

90. Clisby, H. Nevada's Precious Metals Picture Looking Better All the Time. Big Sky Paydirt (Bisbee, AZ), No. 36, Sept. 1983, pp. 21A-25A.

91. Coats, R. R., and E. H. McKee. Ages of Plutons and Types of Mineralization, Northwestern Elko County, Nevada. U.S. Geol. Surv. Prof. Paper 800-C, 1972, pp. C165-C168.

92. CoCa Mines, Inc. Annual Report, 1982. 1983, 8 pp.

93. Coeur d'Alene Mines Corp. Press release. Dec. 19, 1983, 1 p.

94. _____. Annual Report, 1983. 1984, p. 6.

95. Coope, B. M. (ed.). World Barytes Producers—A Review. Ind. Min. (London), No. 130, 1978, pp. 39-40.

96. Cooper, J. J. Total Mercury in Fishes and Selected Biota in

Lahontan Reservoir, Nevada: 1981. Environ. Contam. Toxicol., Bull. 31, 1983, pp. 9–17.

97. Cornwall, H. R. Geology and Mineral Deposits of Southern Nye County, Nevada. NV Bur. Mines and Geol. Bull. 77, 1972, 49 pp.

98. Cornwall, H. R., and F. J. Kleinhampl. Geology of the Bare Mountain Quadrangle, Nevada. U.S. Geol. Surv. Quad. Map GQ–157, 1961, scale 1:62,500.

99. _____. Geology of Bullfrog Quadrangle and Ore Deposits Related to Bullfrog Hills Caldera, Nye County, Nevada, and Inyo County, California. U.S. Geol. Surv. Prof. Paper 454–J, 1964, 25 pp.

100. Cortez Gold Mines. Company Report (Description of the Cortez Mining District Operations). Sept. 1983, 6 pp.

101. Cotter, N. Asamera in High Gear at Gooseberry Mine. The Northern Miner (Toronto), v. 69, No. 25, Aug. 25, 1983, pp. 1–2.

102. Cox. J. W. Geology and Mineralization of the Atlanta District, Lincoln County, Nevada. M. S. Thesis, Univ. NV, Reno, NV, 1981, 83 pp.

103. Crowder, D. F., P. T. Robinson, and D. L. Harris. Geologic Map of the Benton Quadrangle, Mono County, California, and Esmeralda and Mineral Counties, Nevada. U.S. Geol. Surv. Quad. Map GQ–1013, 1972 (1973), scale 1:62,500.

104. Curry, D. L. The Geology of the Cordero Quicksilver Mine Area, Humboldt County, Nevada. M. S. Thesis, Univ. OR, Eugene, OR, 1960, 60 pp.

105. Curtis, J. S. Silver–Lead Deposits of Eureka, Nevada. U.S. Geol. Surv. Monograph 7, 1884, 200 pp.

106. Dahl, A. J. Natural Gas in Transition (Part II). Nevada Review of Business & Economics, Spring 1983. Bureau of Business and Econ. Res., College of Business Administration, Univ. NV, Reno, NV, v. 7, No. 1, 1983, pp. 1–11.

107. Davidoff, R. L., and R. J. Hurdelbrink. Taxation and the Profitability of Mineral Operations in Seven Mountain States and Wisconsin: A Hypothetical Study. BuMines Mineral Issues, 1983, 32 pp.

108. Davidson, C. F. Recovery of Lithium From Clay by Selective Chlorination. BuMines RI 8523, 1981, 19 pp.

109. Davis, J. R., and J. D. Vine. Stratigraphic and Tectonic Setting of the Lithium Brine Field, Clayton Valley, Nevada. Sec. in 1979 Basin and Range Symposium, ed. by G. W. Newman and H. D. Goode. Rocky Mountain Assoc. Geol., Denver, CO, and UT Geol. Assoc., Salt Lake City, UT, 1979, pp. 421–430.

110. Davis, L. E., and R. Y. Ashizawa. The Mineral Industry of Nevada. Ch. in BuMines Minerals Yearbook, 1964, v. 3, pp. 641–662.

111. De Mull, T. J., and R. A. Womack. Heap Leaching at Alligator Ridge. Soc. Min. Eng. AIME preprint 83–403, 1983, 11 pp.

112. Desborough, G. A., F. G. Poole, R. K. Hose, and A. S. Radtke. Metals in Devonian Kerogenous Marine Strata at Gibellini and Bisoni Properties in Southern Fish Creek Range, Eureka County, Nevada. U.S. Geol. Surv. OFR 79–530, 1979, 31 pp.

113. Desy, D. H. Iron and Steel. Ch. in Mineral Facts and Problems, 1980 Edition. BuMines B 671, 1981, pp. 455–480.

114. Dickson, F. W. Physical Chemical Processes Affecting Deposition of Silica in Carlin–Type Gold Deposits. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25–28, 1984, p. 27.

115. Dickson, F. W., R. O. Rye, and A. S. Radtke. The Carlin Gold Deposit as a Product of Rock–Water Interactions. NV Bur. Mines and Geol. Rep. 33, 1979, pp. 101–108.

116. Dillard, G. Nevada Gold Production Continuing Upward, Setting Records. Intermountain Pay Dirt (Bisbee, AZ), No. 42, Mar. 1983, p. 7A.

117. Dole, R. B. Exploration of Salines in Silver Peak Marsh, Nevada. U.S. Geol. Surv. Bull. 530, 1913, pp. 330–345.

118. Dott, R. H., Jr. Pennsylvanian Stratigraphy of Elko and Northern Diamond Ranges, Northeastern Nevada. Am. Assoc. Petroleum Geol. Bull., v. 39, No. 11, 1955, p. 2211.

119. Drewes, H. Structural Geology of the Southern Snake Plains, Nevada. Geol. Soc. Am. Bull., v. 69, No. 2, 1958, pp. 221-240.

120. _____.Stratigraphic and Structural Controls of Mineralization in the Taylor Mining District Near Ely, Nevada. Paper in Short Papers in Geology, Hydrology, and Topography. U.S. Geol. Surv. Prof. Paper 450–B, 1962, pp. B1–B3.

121. _____.Geology of the Connors Pass Quadrangle, Schell Creek Range, East–Central Nevada. U.S. Geol. Surv. Prof. Paper 557, 1967, 93 pp., scale 1:48,000.

122. Drewes, H., and A. R. Palmer. Cambrian Rocks of Southern Snake Range, Nevada. Am. Assoc. Petroleum Geol. Bull., v. 41, No. 1, 1957, pp. 104–120.

123. Dunham, A. C., and J. S. Hanor. Controls on Barite Mineralization in the Western United States. Econ. Geol. and Bull. Soc. Econ. Geol., v. 62, No. 1, 1967, pp. 82–94.

124. Earnest, D. F. Geology of the Sixteen-to-One Mine, Esmeralda County, Nevada. Abstract in Abstr. Booklet, Northwest Min. Assoc., 89th Annu. Conv., Spokane, WA, Dec. 1–3, 1983, p. 10.

125. Edlund, V. E. Lime–Gypsum Processing of McDermitt Clay for Lithium Recovery. BuMines RI 8832, 1983, 15 pp.

126. Einaudi, M. Description of Skarns Associated With Porphyry Copper Plutons. Paper in Advances in Geology of the Porphyry Copper Deposits, Southwestern North America, ed. by S. R. Titley. Univ. AZ Press, Tucson, AZ, 1982, pp. 145–148.

127. _____.General Features and Origins of Skarns Associated With Porphyry Copper Plutons. Paper in Advances in Geology of the Porphyry Copper Deposits, Southwestern North America, ed. by S. R. Titley. Univ. AZ Press, Tuscon, AZ, 1982, pp. 185–209.

128. _____.Yerington Skarns; Field Trip 10, Skarn Deposits. Paper in Exploration for Ore Deposits of the North American Cordillera. Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25–28, 1984, pp. 31–39.

129. Ekburg, C. Geochemistry and Alteration Studies at Carlin Gold's Maggie Creek Deposit. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25–28, 1984, pp. 32–33.

130. Ekren, E. B. Stratigraphy, Preliminary Petrology, and Some Structural Features of Tertiary Volcanic Rocks in the Gabbs Valley and Gillis Ranges, Mineral County, Nevada. U.S. Geol. Surv. Bull. 1464, 1980, 54 pp.

131. Elevatorski, E. A. Nevada Industrial Minerals. Minobras, 1973, 62 pp.

132. _____. Disseminated/Replacement Gold Deposits. Minobras, 1981, 114 pp.

133. Elko (NV) Daily Free Press. Nevada Mines Acquired by NERCO, Inc. Feb. 11, 1983, p. 11.

134. _____. Magazine Describes Deal Arranged at Gold Quarry. Feb. 22, 1983, p. 1.

135. _____. $12 Million Gold Project Announced at Buckhorn. Sept. 19, 1983, p. 12.

136. Emmons, W. H., and G. H. Garrey. Notes on the Manhattan District. Paper in Preliminary Account of Goldfield, Bullfrog, and Their Districts in Southeast Nevada. U.S. Geol. Surv. Bull. 303, 1907, pp. 84–93.

137. Engel, A. L. Treatment Tests of Scheelite Ores and Tailings. BuMines RI 4867, 1952, 11 pp.

138. _____. Preliminary Tests of Nevada Oxidized Copper Ores. BuMines RI 4952, 1953, 6 pp.

139. Engel, A. L., and E. S. Shedd. Treatment Tests of Scheelite Ores From California, Nevada, and Utah. BuMines RI 5087, 1954, 24 pp.

140. Engineering and Mining Journal. Yerington Mine Starts Production. V. 155, No. 1, 1954, pp. 112–113, 166, 168.

141. _____. Duval Corp. V. 166, No. 7, 1965, pp. 118–119.

142. _____. News Briefs/Nevada—Duval Corp. V. 166, No. 9, 1965, p. 186.

143. _____. Duval Corp. V. 167, No. 1, 1966, p. 128.

144. _____. This Month in Mining: Duval Expects Full Production at Nevada Property in 1967. V. 167, No. 7, 1966, p. 100.

145. _____. This Month in Mining: Phillips and Silver King Discover Second Cu-Zn-Ag Ore Zone in Nevada. V. 170, No. 11, 1969, p. 111.

146. _____. Silver Peak Gives Bright Look to Foote Minerals Company Lithium Picture. V. 171, No. 4, 1970, pp. 71–73.

147. _____. Firms Developing a Large Tungsten Deposit in Elko County, Nevada. V. 171, No. 12, 1970, p. 96.

148. _____. International Directory of Mining and Mineral Processing Operations: Section 2A—United States Mine/Plant Units. 1971, p. 119.

149. _____. This Month in Mining: Duval Gets Independent Study of Copper Process. V. 173, No. 5, 1972, p. 24.
150. _____. North American Iron Ore—Part I. V. 175, No. 11, 1974, pp. 83–162.
151. _____. Duval and Cyprus Testing Ferric Chloride Leaches. V. 176, No. 6, 1975, p. 134.
152. _____. International Directory of Mining and Mineral Processing Operations: Section 2A—United States Mine/Plant Units, 1977, p. 205.
153. _____. News Briefs/In the U.S.—Nevada. V. 178, No. 10, 1977, p. 150.
154. _____. Survey of Mine and Plant Expansion. V. 179, No. 1, 1978, p. 75.
155. _____. Placer Amex Finds Uranium in Tertiary Caldera. V. 180, No. 2, 1979, pp. 29–31.
156. _____. Exploration Roundup—U.S.: U. V. Industries. V. 180, No. 2, 1979, p. 184.
157. _____. New Briefs/In the U.S.—Nevada. V. 180, No. 5, 1979, p. 192.
158. _____. This Month in Mining: U.S.—Nevada. The Candelaria Silver Properties. V. 181, No. 1, 1980, p. 158.
159. _____. Exploration Roundup. Ongoing Projects: U.S.—Asarco, Inc. V. 181, No. 1, 1980, p. 170.
160. _____. This Month in Mining: Kennecott Will Recover Copper From Tailings Area. V. 181, No. 2, 1980, p. 48.
161. _____. This Month in Mining: Anaconda's Nevada Moly Project To Go On Stream in Fall of 1981. V. 181, No. 3, 1980, pp. 39, 43.
162. _____. Exploration Roundup. High Gold Prices Spur Frantic Exploration, the Nevada Discoveries. V. 181, No. 10, 1980, p. 31.
163. _____. This Month in Mining: U.S.—Nevada–Alligator Ridge Uses Heap Leaching To Produce Gold Bullion Ores. V. 182, No. 8, 1981, pp. 35–37.
164. _____. Exploration Roundup. Ongoing Projects—U.S. V. 182, No. 12, 1981, p. 31.
165. _____. 45 Top U.S. Silver Mines and 27 Leading U.S. Silver Mining Companies. V. 183, No. 6, 1982, p. 15.
166. _____. This Month in Mining: Silver King Will Place Ward Property Into Production in 1985. V. 183, No. 7, 1982, p. 49.
167. _____. News Brief/In the U.S.—Nevada. V. 183, No. 11, 1982, pp. 168–169.
168. _____. International Directory of Mining and Mineral Processing Operations: Section 2A—United States Mine/Plant Units. 1982, p. 221.
169. _____. This Month in Mining: Nevada. V. 184, No. 6, 1983, pp. 45, 119.
170. _____. This Month in Mining: Cortez Gold Mines. V. 184, No. 6, 1983, p. 119.
171. _____. Sunshine's New Sixteen-to-One Silver Mine: Mass Production Systems Applied to a Small Mine at a Remote Nevada Location. V. 185, No. 5, 1984, pp. 46–52.
172. _____. This Month in Mining: Gold and Silver Projects Dominate Recovering U.S. Mining Scene. V. 185, No. 6, 1984, p. 21.
173. _____. Book of Flowsheets. McGraw-Hill, 1984, 207 pp.
174. Erickson, R. L., A. P. Marranzino, U. Oda, and W. W. Janes. Geochemical Exploration Near the Getchell Mine, Humboldt County, Nevada. U.S. Geol. Surv. Bull. 1198–A, 1964, 26 pp.
175. Erickson, R. L., and S. P. Marsh. Geochemical, Aeromagnetic, and Generalized Geologic Maps Showing Distribution and Abundance of Mercury and Arsenic, Golconda and Iron Point Quadrangles, Humboldt County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF–312, 1971, scale 1:24,000.
176. _____. Geochemical, Aeromagnetic, and Generalized Geologic Maps Showing Distribution and Abundance of Antimony and Tungsten, Golconda and Iron Point Quadrangles, Humboldt County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF–313, 1971, scale 1:24,000.
177. _____. Geochemical, Aeromagnetic, and Generalized Geologic Maps Showing Distribution and Abundance of Gold and Copper, Golconda and Iron Point Quadrangles, Humboldt County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF–314, 1971, scale 1:24,000.
178. _____. Geochemical, Aeromagnetic, and Generalized Geologic Maps Showing Distribution and Abundance of Lead and Silver, Golconda and Iron Point Quadrangles, Humboldt County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF–315, 1971, scale 1:24,000.
179. _____. Geochemical, Aeromagnetic, and Generalized Geologic Maps Showing Distribution and Abundance of Molybdenum and Zinc, Golconda and Iron Point Quadrangles, Humboldt County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF–345, 1972, scale 1:24,000.
180. _____. Geologic Map of the Golconda Quadrangle, Humboldt County, Nevada. U.S. Geol. Surv. Geol. Quad. Map GQ-1174, 1974, scale 1:24,000.
181. Ervine, W. B. The Geology and Mineral Zoning of the Spanish Belt Mining District, Nye County, Nevada. Ph.D. Diss., Stanford Univ., Stanford, CA, 1972, 258 pp.
182. Evans, J. G. Geologic Map of the Rodeo Creek NE Quadrangle, Eureka County, Nevada. U.S. Geol. Surv. Geol. Quad. Map GQ–1116, 1974, scale 1:24,000.
183. _____. Geology of the Rodeo Creek NE and Welches Canyon Quadrangles, Eureka County, Nevada. U.S. Geol. Surv. Bull. 1473, 1980, 81 pp.
184. Evans, J. G., and L. D. Cress. Preliminary Geologic Map of the Schroeder Mountain Quadrangle, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF–324, 1972, scale 1:24,000.
185. Evans, J. G., and K. B. Ketner. Geologic Map of the Swales Mountain Quadrangle and Part of the Adobe Summit Quadrangle, Elko County, Nevada. U.S. Geol. Surv. Map I–667, 1971, scale 1:24,000.
186. Evans, J. G., and T. E., Mullens. The Bootstrap Window, Elko and Eureka Counties, Nevada. U.S. Geol. Surv. J. Res., v. 4, No. 1, 1975, pp. 119–125.
187. Evans, K. J. Smokey Valley Open Pit Gold Mine. The Min. Record (Denver), v. 94, No. 33, Aug. 18, 1982, p. 3.
188. Everett, F. D. Reconnaissance of Tellurium Resources in Arizona, Colorado, New Mexico and Utah—Including Selected Data From Other Western States and Mexico. BuMines RI 6350, 1964, pp. 15, 20–21.
189. Everson, R. A., B. G. Quinn, and R. G. Warnock. Mercury Contamination of the Carson River and Lahontan Reservoir, Nevada. Westminster Studies Series. Westminster Series, Westminster College, Salt Lake City, UT, July 1982, 13 pp.
190. Fagan, J. J. Carboniferous Cherts, Turbidites, and Volcanic Rocks, Northern Independence Range, Nevada. Geol. Soc. Am. Bull., v. 73, 1962, pp. 595-612.
191. Ferguson, H. G. Placer Deposits of the Manhattan District, Nevada. Ch. in Contributions to Economic Geology. U.S. Geol. Surv. Bull. 640, 1916, pp. 163-193.
192. _____. The Limestone Ores of Manhattan, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 16, No. 1, 1921, pp. 1-36.
193. _____. The Round Mountain District, Nevada, U.S. Geol. Surv. Bull. 725, 1921, pp. 383-406.
194. _____. Geology and Ore Deposits of the Manhattan District, Nevada, U.S. Geol. Surv. Bull. 723, 1924, 163 pp.
195. Ferguson, H. G., and S. H. Cathcart. Geology of the Round Mountain Quadrangle, Nevada. U. S. Geol. Surv. Geol. Quad. Map GQ-40, 1954, scale 1:125,000.
196. Ferguson, H. G., and S. W. Muller. Structural Geology of the Hawthorne and Tonopah Quadrangles, Nevada. U.S. Geol. Surv. Prof. Paper 216, 1949, 55 pp.
197. Ferguson, H. G., S. W. Muller, and S. H. Cathcart. Geology of the Mina Quadrangle, Nevada. U.S. Geol. Surv. Geol. Quad. Map GQ-45, 1954, scale 1:250,000.
198. Ferguson, H. G., R. J. Roberts, and S. W. Muller. Geology of the Golconda Quadrangle, Nevada. U.S. Geol. Surv. Geol. Quad. Map GQ-15, 1952, scale 1:125,000.
199. Fiannaca, M., and J. McKee. Geology and Development of the Relief Canyon Gold Deposit, Pershing County, Nevada. Paper Pres. at Northwest Min. Assoc., 89th Annu. Conv., Dec. 1-3, 1983, Spokane, WA, 20 pp.; available upon request from Northwest Min. Assoc., 633 Peyton Bldg., Spokane, WA 99201.
200. Fieberling, P. State and Federal Permits Required in Nevada Before Mining or Milling Can Begin. NV Bur. Mines and Geol. Spec. Publ. L-6, May 1981, 6 pp.
201. First Mississippi Corp. Annual Report, 1983. 1984, 48 pp.
202. Fisk, E. L. Cordero Mine, Opalite Mining District. Ch. 75

in Ore Deposits of the United States, 1933-1967, ed. by J. D. Ridge. AIME, v. II, 1968, pp. 1573-1591.

203. Gage, H. L. Some Foreign and Domestic Lead-Zinc Mines That Could Supply Zinc Concentrates to a Pacific Northwest Electrolytic Zinc Industry. The Lead-Zinc Mines of Nevada. Bonneville Power Administration, Portland, OR, 1941, pp. 662-666.

204. Galli, P. E., J. S. Livermore, and L. G. Reeve. Pinson and Preble Gold Deposits Near Golconda, Humboldt County, Nevada. Abstract in Geology and Exploration Aspects of Fine-Grained, Carlin-Type Gold Deposits. Geol. Soc. NV and Mackay School of Mines Symp., Reno, NV, 1976, p. 3; available at Mackay School of Mines, Univ. NV, Reno, NV.

205. Gardner, D. H. Structure and Stratigraphy of the Northern Part of the Snake Mountains, Elko County, Nevada. Ph.D. Diss., Univ. OR, Eugene, OR, 1968, 222 pp.

206. Garner, E. D., and J. F. Johnson. Shaft-Sinking Practices and Costs. BuMines B 357, 1932, pp. 1, 98.

207. Garside, L. J. Radioactive Mineral Occurrences in Nevada. NV Bur. Mines and Geol. Bull. 81, 1973, 121 pp.

208. Garside, L. J., and H. F. Bonham, Jr. Road Log/Trip Guide: Candelaria Mine, Goldfield District, Tonopah District and Bell Mountain Mine, Field Trip 4, Precious Metal Districts in West-Central Nevada. Paper in Exploration for Ore Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, pp. FT4 1-27.

209. _____. Road Log/Trip Guide: Sterling Mine, Goldfield District, Hasbrouck Mountain (Divide District), Tonopah District, and Borealis Mine, Field Trip 3, Precious Metal Districts in Southern and Western Nevada. Paper in Exploration for Ore Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, pp. FT3 1-31.

210. Garside, L. J., and J. V. Tingley. Field Examination of Sterling Mine, Nye County, Nevada. NV Bur. Mines and Geol., Mar. 25, 1982, 3 pp.; available at NV Bur. Mines and Geol., Reno, NV.

211. _____. Field Examination of Divide Mine and Tonopah Hasbrouck Mines, Esmeralda County, Nevada. NV Bur. Mines and Geol., Mar. 26, 1982, 7 pp.; available at NV Bur. Mines and Geol., Reno, NV.

212. Gates, R. W. Basic Incorporated, Gabbs, Nevada Operations. Ch. in Papers Presented at the AIME Pacific Southwest Mineral Industry Conference (Sparks, NV, May 5-7, 1965). Part B—Industrial Minerals Session. NV Bur. Mines and Geol. Rep. 13, 1965, pp. 39-44.

213. Geehan, R. W. Exploration of the Crowell Fluorspar Mine, Nye County, Nevada. BuMines RI 3954, 1946, 9 pp.

214. _____. Investigation of the Dayton Iron Deposit, Lyon and Storey Counties, Nevada. BuMines RI 4561, 1949, 34 pp.

215. Geehan, R. W., and R. R. Trengove. Investigation of Nevada Scheelite, Inc., Deposit, Mineral County, Nevada. BuMines RI 4681, 1950, 13 pp.

216. Gemmill, P. The Geology of the Ore Deposits of the Pioche District, Nevada. Ch. 54 in Ore Deposits of the United States, 1933-1967, ed. by J. D. Ridge. V. II, 1st (Graton-Sales) ed., AIME, 1968, pp. 1128-1147.

217. Gillson, J. L. Fluorspar Deposits in the Western States. AIME Tech. Publ. 1783, 1943, 20 pp.

218. Gilluly, J., and O. Gates. Tectonic and Igneous Geology of the Northern Shoshone Range, Nevada. U.S. Geol. Surv. Prof. Paper 465, 1964, 153 pp.

219. Gilluly, J., and H. Masursky. Geology of the Cortez Quadrangle, Nevada. U.S. Geol. Surv. Bull. 1175, 1965, 117 pp.

220. Gilmour, P. Grades and Tonnages of Porphyry Copper Deposits. Paper in Advances in Geology of the Porphyry Copper Deposits, Southwestern North America, ed. by S. R. Titley. Univ. AZ Press, Tucson, AZ, 1982, p. 14.

221. Glanzman, R. K., J. H. McCarthy, Jr., and J. J. Rytuba. Lithium in the McDermitt Caldera, Nevada and Oregon. Energy, v. 3, 1978, pp. 347-353.

222. Goldstein, I. J. Gold Mineralization at the Northumberland Gold Mine, Nye County, Nevada. Geol. Soc. Am. Abstr. With Programs, v. 5, No. 1, 1973, p. 48.

223. Grabher, D. E. Union Carbide's Pilot Mountain Project: Geologic Setting and Field Trip Guide, Field Trip 10, Skarn Deposits. Paper in Exploration for Ore Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, pp. 5-24.

224. Grace, K. A. Exploration and Development in 1982. World Min. (Yearbook), v. 36, No. 8, 1983, pp. 60-61.

225. Graney, J. R. Controls of Alteration and Precious-Metal Mineralization in a Fossil Hydrothermal System, Hasbrouck Mountain, Nevada. Abstr. No. 51,024 in Abstracts With Programs, 1984. 97th Annu. Meeting, Geol. Soc. Am., Nov. 5-8, 1984, Reno, NV, p. 523.

226. Granger, A. E., M. M. Bell, G. C. Simmons, and F. Lee. Geology and Mineral Resources of Elko County, Nevada. NV Bur. Mines and Geol. Bull. 54, 1957, 190 pp.

227. Greely, M. Alligator Ridge Looking for Prospects to Extend Life of White Pine Gold Mine. Ely (NV) Daily Times, Mar. 16, 1983, pp. 4, 6.

228. Green, W. R. Structural Control of Mineralization at the Aurora Mining District, Mineral County, Nevada. M.S. Thesis, Univ. NV, Reno, NV, 1964, 41 pp.

229. Greene, R. C. Preliminary Geologic Map of Jordan Meadow Quadrangle, Nevada-Oregon. U.S. Geol. Surv. Misc. Field Studies Map MF-341, 1972, scale 1:48,000.

230. Gries, J. P. Carlin Gold Deposit. Paper in Providing New Sources of Mineral Supply. BuMines IC 8789, 1979, pp. 4-6.

231. Griffith, R. F. Tungsten. Ch. in Mineral Facts and Problems, 1970 Edition. BuMines B 650, 1970, pp. 399-415.

232. Grove, G. R. A Study of the Fine-Grained Disseminated Gold Ore of the Windfall Mine, Eureka County, Nevada. M. A. Thesis, Univ. CA, Santa Barbara, CA, 1979, 98 pp.

233. Guay, W. J. How Carlin Treats Gold Ores by Double Oxidation. World Min., v. 33, No. 3, 1980, pp. 47-49.

234. Guay, W. J., and D. G. Peterson. Recovery of Gold From Carbonaceous Ores at Carlin, Nevada. AIME Trans., v. 254, 1974, p. 102.

235. Guider, J. W. Iron Ore Beneficiation—Key to Modern Steelmaking. Min. Eng. (NY), v. 33, No. 4, 1981, pp. 410-413.

236. Guild, P. W. Preliminary Metallogenic Map of North America: A Numerical Listing of Deposits. U. S. Geol. Surv. Circ. 858-A, 1981, p. A4.

237. Guzzardi, W. The Huge Find in Roy Ash's Backyard. Fortune Magazine, v. 106, No. 13, 1982, pp. 48-65.

238. Hague, A. Geology of the Eureka District. U. S. Geol. Surv. Monograph 20, 1982, 419 pp.

239. Hall, R. B. World Nonbauxite Aluminum Resources—Alunite. U.S. Geol. Surv. Prof. Paper 1076A, 1978, 35 pp.

240. Hardie, B. S. Carlin Gold Mine, Lynn District, Nevada. Paper in NV Bur. Mines and Geol. Rep. 13-A, 1966, pp. 73-83.

241. Hardisty, R. S. The Tonkin Springs Gold Deposit, Nevada; Aspects of the Geology and Geochemistry. Pres. at Northwest Min. Assoc., 89th Annu. Conv., Dec. 2, 1983, Spokane, WA; available from Northwest Min. Assoc., 633 Peyton Bldg., Spokane, WA 99201.

242. Hardy, R. A. The Getchell Mine New Gold Producer of Nevada. Eng. and Min. J., v. 139, No. 11, 1938, pp. 29-31.

243. _____. The Geology of the Getchell Mine. Trans. Soc. Min. Eng. AIME, v. 144, 1941, pp. 147-150.

244. Hargrove, H. R. Geology of the Southern Portion of the Montana Mountains, McDermitt Caldera, Nevada. M.S. Thesis, AZ St. Univ., Tempe, AZ, 1983, 97 pp.

245. Harris, M., and A. S. Radtke. Statistical Study of Selected Trace Elements With Reference to Geology and Genesis of the Carlin Gold Deposit, Nevada. U. S. Geol. Surv. Prof. Paper 960, 1976, 21 pp.

246. Harvey, R. D., and C. J. Vitaliano. Wall-Rock Alteration in the Goldfield District, Nevada. J. Geol., v. 72, No. 5, 1964, pp. 564-579.

247. Hausen, D. M. Fine Gold Occurrences at Carlin, Nevada. Ph.D. Diss., Columbia Univ., New York, NY, 1967, 166 pp.

248. Hausen, D. M., and P. F. Kerr. Fine Gold Occurrence at Carlin, Nevada. Ch. 46 in Ore Deposits of the United States, 1933-1967, v. I (Graton-Sales), AIME, New York, 1968, pp. 909-940.

249. Havens, R., and W. I. Nissen. Laboratory Continuous Flota-

tion of Bertrandite and Phenacite From Mount Wheeler, Nevada, Beryllium Ores. BuMines RI 6386, 1964, 18 pp.

250. Havens, R., W. I. Nissen, and J. B. Rosenbaum. Flotation of Bertrandite and Phenacite From Mount Wheeler, Nevada, Beryllium Ore. BuMines RI 5875, 1961, 14 pp.

251. Havenstrite, S. R. Geology and Ore Deposits of the Taylor Mining District, White Pine County, Nevada. Pres. at Precious-Metals Symposium (Sparks, NV, Nov. 17-19, 1980). NV Bur. Mines and Geol. Rep. 36, 1983, pp. 14-26.

252. _____. Geology and Ore Deposits of the Taylor Silver District, Field Trip 2, Sediment-Hosted Precious Metal Deposits. Paper in Exploration for Ore Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, pp. 37-45.

253. Hawkins, R. B. The Geology and Mineralization of the Jerritt Creek Area, Northern Independence Mountains, Nevada. M. S. Thesis, Univ. ID, Moscow, ID, 1973, 104 pp.

254. _____. Discovery of the Bell Gold Mine—Jerritt Canyon District, Elko County, Nevada. Min. Congr. J., v. 68, No. 2, 1982, pp. 28-32.

255. Hecla Mining Co. Annual Report for the Year Ended December 31, 1975. 1975, p. 5.

256. _____. Annual Report, Form 10-K, Fiscal Year 1975. Securities and Exchange Commission, 1976, p. 12.

257. _____. Annual Report, Form 10-K, Fiscal Year 1976. Securities and Exchange Commission, 1977, p. 14.

258. Heidrick, T. L. Geology and Ore Deposits of the Ward Mining District, White Pine County, Nevada. M. S. Thesis, Univ. CO, Boulder, CO, 1965, 154 pp.

259. Heizer, O. F. Methods and Costs of Concentrating Tungsten Ore at the Nevada-Massachusetts Mill, Mill City, Nevada. BuMines IC 6280, 1930, 10 pp.

260. _____. Method and Cost of Mining Tungsten Ore at the Nevada-Massachusetts Co. Mines, Mill City, Nevada. BuMines IC 6284, 1930, 13 pp.

261. Hendricks, R. S. How Hecla Diamond Drilled Fractured Dolomite Under High-Pressure Water. World Min., v. 2, No. 2, 1966, pp. 18-22.

262. Henn, J. J., R. C. Kirby, and L. D. Norman, Jr. Review of Major Proposed Processes for Recovery of Manganese From U.S. Resources. BuMines IC 8368, 1968, 36 pp.

263. Hess, F. L., and E. S. Larson, Jr. Contact-Metamorphic Tungsten Deposits of the United States. U. S. Geol. Surv. Bull. 725-D, 1921, pp. 245-309.

264. Hett, P. Deep Ruth Approaches Production Despite High Costs and Obstacles to Shaft Sinking. Min. Eng. (NY), v. 7, No. 4, 1955, pp. 364-366.

265. Hewett, D. F. Carnotite in Southern Nevada. Eng. and Min. J., v. 115, No. 5, 1923, pp. 232-235.

266. Hewett, D. F., E. Callaghan, B. N. Moore, T. B. Nolan, W. W. Rubey, and W. T. Schaller. Mineral Resources of the Region Around Boulder Dam. U.S. Geol. Surv. Bull. 871, 1936, 197 pp.

267. Hewett, D. F., and B. N. Webber. Bedded Deposits of Manganese Oxides Near Las Vegas, Nevada. NV Bur. Mines and Geol. Bull. 13, 1931, 17 pp.

268. Hill, J. M. Notes on Some Mining Districts in Eastern Nevada. U. S. Geol. Surv. Bull. 648, 1916, 214 pp.

269. Hobbs, S. W. Geology of the Northern Part of the Osgood Mountains, Humboldt County, Nevada. Ph.D. Diss., Yale Univ., New Haven, CT, 1948, 97 pp.

270. Hobbs, S. W., and S. E. Clabaugh. Tungsten Deposits of the Osgood Range, Humboldt County, Nevada. NV Bur. Mines and Geol. Bull. 44, 1946, 31 pp.

271. Hobbs, S. W., and J. E. Elliott. Tungsten. Ch. in United States Mineral Resources, ed. by D. A. Brobst and W. P. Pratt. U.S. Geol. Surv. Prof. Paper 820, 1973, pp. 667-678.

272. Holmes, G. H., Jr. Exploration of the Riley Tungsten Mine, Humboldt County, Nevada. BuMines RI 3945, 1946, 7 pp.

273. _____. Mining Methods at the Brucite Deposit, Basic Refractories, Inc., Gabbs, Nye County, Nevada. BuMines IC 7543, 1949, 10 pp.

274. _____. Mining and Milling Methods at the Caselton Mine, Combined Metals Reduction Company, Pioche, Lincoln County, Nevada. BuMines IC 7586, 1950, 24 pp.

275. _____. Beryllium Investigations in California and Nevada, 1959-62. BuMines IC 8158, 1963, 19 pp.

276. _____. Mercury in Nevada. Ch. in Mercury Potential of the United States. BuMines IC 8252, 1965, pp. 215-300.

277. _____. Nevada. Section in Potential Sources of Aluminum. BuMines IC 8335, 1967, pp. 90-91.

278. Hope, R. A., and R. R. Coats. Preliminary Geologic Map of Elko County, Nevada. U.S. Geol. Surv. Open File Map 76-779, 6 sheets, 1976, scale 1:100,000.

279. Horton, F. W. Molybdenum: Its Ores and Their Concentration. BuMines B 3, 1916, pp. 1-132.

280. Horton, R. C. History of the Mineral Industry in the White Pine County Area. Intermountain Association Petroleum Geology Guidebook to the Geology of East Central Nevada. 11th Annu. Field Conf., UT Geol. Assoc., Salt Lake City, UT, 1960, pp. 210-219.

281. _____. An Inventory of Fluorspar Occurrences in Nevada. NV Bur. Mines and Geol. Rep. 1, 1961, 31 pp.

282. _____. Iron Ore Occurrences in Nevada. NV Bur. Mines and Geol. Map 5, 1962, scale 1:1,000,000.

283. _____. An Inventory of Barite Occurrences in Nevada. NV Bur. Mines and Geol. Rep. 4, 1963, 19 pp.

284. Hose, R. K., M. C. Blake, and R. M. Smith. Geology and Mineral Resources of White Pine County, Nevada. NV Bur. Mines and Geol. Bull. 85, 1976, 105 pp.

285. Hotz, P. E., and R. Willden. Geology and Mineral Deposits of the Osgood Mountains Quadrangle, Humboldt County, Nevada. U.S. Geol. Surv. Prof. Paper 431, 1964, 128 pp.

286. Howard, K. L., Jr. Geology of the Yerington Mine, Lyon County, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 71, No. 3, 1976, p. 700.

287. Huang, C. Biogeochemical and Soil Geochemical Studies at the Borealis Mine, Mineral County, Nevada, U.S.A. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25–28, 1984, p. 24.

288. Hulse, P. Gold Operations at the Atlanta Mine. Min. Eng., v. 30, No. 9, 1978, pp. 1299–1301.

289. _____. Gold Operations at the Atlanta Mine. Abstr., Pacific Northwest Met. and Miner. Conf., Portland, OR, May 15–17, 1978, 1 p.; available at BuMines, Western Field Operations Center, Spokane, WA.

290. Humboldt Sun (Winnemucca, NV). Pinson Pours Gold Mine's 100th 1,000–Oz. Bar. July 27, 1982, p. 1.

291. Hunt, C. B., V. E. McKelvey, and J. H. Wiese. The Three Kids Manganese District, Clark County, Nevada. U.S. Geol. Surv. Bull. 936–L, 1942, pp. 293–319.

292. Huttl, J. B. How Getchell Mine and Mill Prepare for Greater Output. Eng. and Min. J., v. 151, No. 7, 1950, pp. 60–62.

293. _____. New Copper Projects in Nevada Will Open More Ore for Kennecott. Eng. and Min. J., v. 153, No. 10, 1952, pp. 92–93.

294. _____. Bringing Deep Ruth Into Production. Eng. and Min. J., v. 158, No. 5, 1957, pp. 82–87.

295. _____. Anaconda Adds 5,000-TPD Concentrator to Yerington Enterprise at Weed Heights. Eng. and Min. J., v. 163, No. 3, 1962, pp. 75–85.

296. _____. The Standard Slag Co. Tops Nevada Iron, Upgrades Magnetite Ore for Export. Eng. and Min. J., v. 164, No. 12, 1963, pp. 84–87.

297. Ikramuddin, M., L. Besse, and P. M. Nordstrom. The Relation Between Ti, Rb, and K in the Carlin–Type Gold Deposits. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of the Assoc. of Expl. Geochem., Reno, NV, Mar. 25–28, 1984, p. 37.

298. Ilchik, R. P. Hydrothermal Maturation of Organic Matter at the Alligator Ridge Gold Deposits, Nevada. Abstr. No. 53,039 in Abstracts With Programs, 1984. 97th Annu. Meeting, Geol. Soc. Am., Nov. 5–8, 1984, Reno, NV, p. 548.

299. Intermountain Paydirt (Bisbee, AZ). Exploration, Higher Gold Prices Double Jerritt Canyon Reserves. Feb. 1980, pp. 1, 4–5.

300. _____. Nevada's Historic Candelaria Mining District is Again Producing Silver. No. 15, Dec. 1980, pp. 6, 12.

301. _____. Smoky Valley Gold Output to Climb to 200,000 Ounces by 1984. No. 31, Apr. 1981, p. 28.

302. _____. Freeport—Government Cooperation Reduced Jerritt Canyon Permitting Time. No. 22, July 1981, pp. 12–13.

303. _____. LL & E Reports Huge Gold and Silver Reserve. No. 28, Jan. 1982, p. 72.
304. _____. Eisenman Says It Had "Hand Shake" Deal on Half Interest in Ore. No. 29, Feb. 1982, p. 6.
305. _____. Oxymin Shuts Down Candelaria Mine as Silver Drops Below $6. No. 32, May 1982, p. 1.
306. _____. Jerritt Canyon Helps Freeport-McMoran Through Rough Quarter. No. 32, May 1982, pp. 61-63.
307. _____. Sunshine's New 16 to 1 Nevada Silver Mine is Nearing Capacity. No. 34, July 1982, p. 1, 33-40.
308. _____. Conoco Winding Down Mineral Operations; Closure Set June 30th. No. 44, May 1983, p. 21A.
309. _____. Electra North West Aims for Production at Aurora Mine in July. No. 45, June 1983, p. 6A.
310. _____. Anaconda to Gamble, Plans to Restart Tonopah Moly Operation. No. 45, June 1983, p. 16A.
311. _____. HIMCO Bringing Manhattan Back on Line. No. 45, June 1983, p. 21A.
312. _____. Homestake Expanding With Felmont Oil Purchase: Also Gets 25 Percent Interest in Smoky Valley Gold Property in Nevada. No. 55, Apr., 1984, p. 3A.
313. _____. Of Mines and Men. No. 56, May, 1984, p. 15A.
314. Jackson, C. F., and E. D. Gardner. Stoping Methods and Costs. BuMines B 390, 1937, pp. 92-94.
315. Jackson, D. New Plants Move IMCO Services Into Front Ranks of Nevada Barite Producers. Eng. and Min. J., v. 178, No. 7, 1977, pp. 73-75.
316. _____. Jerritt Canyon Project. Eng. and Min. J., v. 183, No. 7, 1982, pp. 54-58.
317. _____. How Duval Transformed Its Battle Mountain Properties From Copper to Gold Production. Eng. and Min. J., v. 183, No. 10, 1982, pp. 95, 97, 99.
318. _____. Pinson Gold. Eng. and Min. J., v. 183, No. 8, 1982, pp. 64-68.
319. _____. Carlin Gold, A Newmont Money Generator Keeps on Renewing Itself After Sparking the Rebirth of Gold Mining in Nevada. Eng. and Min. J., v. 184, No. 7, 1983, pp. 38-43.
320. Jacky, W. Copper Precipitation Methods at Weed Heights. Min. Eng., v. 19, No. 6, 1967, pp. 70-74.
321. James, L. P. Zoned Alteration in Limestone at Porphyry Copper Deposits, Ely, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 71, 1976, pp. 488-512.
322. James, L. P., and L. H. Knight. Stratabound Lead-Zinc-Silver Ores of the Pioche District, Nevada—Unusual "Mississippi Valley" Deposits. Paper in Proceedings of Rocky Mountain Association of Geologists/Utah Geological Association Basin and Range Symposium and Great Basin Field Conference (Las Vegas, NV, Oct. 7-11, 1979), ed. by G. W. Newman and H. D. Goode. RMAG, 1979, pp. 389-396.
323. Jenney, C. P. Geology of the Central Humboldt Range, Nevada. NV Bur. Mines and Geol. Bull. 24, 1935, 73 pp.
324. Jennings, O. R. Economics of Nevada Iron Ores: A Market Study. M. S. Thesis, Univ. NV, Reno, NV, 1967, 116 pp.
325. Jensen, M. L., R. P. Ashley, and J. P. Albers. Primary and Secondary Sulfates at Goldfield, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 66, 1971, pp. 618-626.
326. Johnson, A. C. Shaft-Sinking Methods and Costs at the T. L. Shaft, Eureka Corp., Ltd., Eureka, Nevada. BuMines IC 7835, 1958, 25 pp.
327. Johnson, A. C., and R. R. Trengove. The Three Kids Manganese Deposit, Clark County, Nev.: Exploration, Mining, and Processing. BuMines RI 5209, 1956, 31 pp.
328. Johnson, M. G. Placer Gold Deposits of Nevada. U.S. Geol. Surv. Bull. 1356, 1973, 118 pp.
329. _____. Geology and Mineral Deposits of Pershing County, Nevada. NV Bur. Mines and Geol. Bull. 89, 1977, 115 pp.
330. Johnson, O. M., and P. C. Wells. Marketing of Industrial Minerals for Oil Fields and Foundries. Pres. at Soc. Min. Eng. AIME Annu. Meeting, Las Vegas, NV, Feb. 24-28, 1980. Soc. Min. Eng. AIME preprint 80-92, 5 pp.
331. Jones, A. Lacana in Nevada Gold Bet With 2-Stage Drill Program. The Northern Miner (Toronto), v. 68, No. 48, Feb. 3, 1983, pp. 1-2.
332. Jones, G. K. Iron Ore Pelletization. Ind. Miner. (London), v. 138, Mar. 1979, pp. 61-73.
333. Jones, R. B. Lead Deposits and Occurrences in Nevada. NV Bur. Mines and Geol. Map 78, 1983, scale 1:1,000,000.
334. Joralemon, P. The Occurrence of Gold at the Getchell Mine, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 46, No. 3, 1951, pp. 267-310.
335. _____. K-Ar Relations of Granodiorite Emplacement and Tungsten and Gold Mineralization Near the Getchell Mine, Humboldt County, Nevada, Discussion. Econ. Geol. and Bull. Soc. Econ. Geol., v. 70, No. 2, 1975, pp. 405-409.
336. _____. A Major Gold Belt Takes Shape in Nevada. Min. Eng. (NY), v. 30, No. 7, 1978, pp. 759-762.
337. Kaczmarowski, J. Final Geology Report on Victoria Mine. 1977, 46 pp.; available at NV Bur. Mines and Geol., Reno, NV.
338. Kay, M., and J. P. Crawford. Paleozoic Facies From the Miogeosynclinal to the Eugeosynclinal Belt in Thrust Slices, Central Nevada. Geol. Soc. Am. Bull., v. 75, No. 5, 1964, pp. 425-454.
339. Keith, W. J. Preliminary Geologic Map of the Red Mountain Mining District, Nevada. U.S. Geol. Surv. Open File Map, 1972, scale 1:12,000.
340. Keith, W. J., L. Calk, and R. P. Ashley. Crystals of Coexisting Alunite and Jarosite, Goldfield, Nevada. U.S. Geol. Surv. Prof. Paper 1124-C, 1979, pp. C1-C5.
341. Kennecott Copper Corp. Annual Report, Form 10-K. Securities and Exchange Commission, 1976, pp. 5-6.
342. Kerr, P. F. Geology of the Tungsten Deposits Near Mill City, Nevada. NV Bur. Mines and Geol. Bull. 21, 1934, 46 pp.
343. _____. Tungsten Mineralization in the United States. Geol. Soc. Am. Memoir 15, 1946, 241 pp.
344. Kerr, W. Paleozoic Sequences and Thrust Slices of the Seetoya Mountains, Independence Range, Elko County, Nevada. Geol. Soc. Am. Bull., v. 73, 1962, pp. 439-460.
345. Kesler, T. L. Raw Lithium Supplies. Min. Eng. (NY), v. 30, 1978, pp. 283-284.
346. Ketner, K. B. Bedded Barite Deposits of the Shoshone Range, Nevada. Ch. 11 in Short Papers in Geology and Hydrology Articles 1-59. U.S. Geol. Surv. Prof. Paper 475-B, 1963, pp. B38-B41.
347. _____. Economic Geology Section in Tectonic and Igneous Geology, Northern Shoshone Range. U.S. Geol. Surv. Prof. Paper 465, 1965, pp. 138-144.
348. _____. Stratigraphic Sequence of Paleozoic and Mesozoic Rocks Exposed in Central Elko County, Nevada. U.S. Geol. Surv. OFR 75-213, 1975, 120 pp.
349. Ketner, K. B., J. G. Evans, and T. D. Hessin. Geochemical Anomalies in the Swales Mountain Area, Elko County, Nevada. U.S. Geol. Surv. Circ. 588, 1968, 13 pp.
350. Ketner, K. B., and J. F. Smith, Jr. Mid-Paleozoic Age of the Roberts Thrust Unsettled by New Data From Northern Nevada. Geol., v. 10, No. 6, June 1982, pp. 298-303.
351. Kilgore, C. C., and P. R. Thomas. Manganese Availability—Domestic. A Minerals Availability System Appraisal. BuMines IC 8889, 1982, 14 pp.
352. King, W. H., and G. H. Holmes, Jr. Investigation of Nevada-Massachusetts Tungsten Deposits, Pershing County, Nevada. BuMines RI 4634, 1950, 6 pp.
353. King, W. H., J. H. Soule, and R. R. Trengove. Investigation of Virgin River Manganese Deposit, Clark County, Nevada. BuMines RI 4471, 1949, 6 pp.
354. King, W. H., and R. R. Trengove. Investigation of the Fannie Ryan and Boulder City Manganese Deposits, Clark County, Nevada. BuMines RI 4712, 1950, 8 pp.
355. Kirkemo, H., C. A. Anderson, and S. C. Creasey. Investigations of Molybdenum Deposits in the Conterminous United States, 1942-1960. U.S. Geol. Surv. Bull. 1182-E, 1965, pp. E73-E78.
356. Kleinhampl, F. J., W. E. Davis, M. L. Chesterman, C. W. Chesterman, R. H. Chapman, and C. H. Gray, Jr. Aeromagnetic and Limited Gravity Studies and Generalized Geology of the Bodie Hills Region, Nevada and California. U.S. Geol. Surv. Bull. 1384, 1975, 38 pp.
357. Kleinhampl, F. J., and J. I. Ziony. Preliminary Geologic Map of Nothern Nye County, Nevada. U.S. Geol. Surv. Open File Map, 1967, scale 1:200,000.

358. Klessig, P. J. History and Geology of the Alligator Ridge Gold Mine, White Pine County, Nevada; Field Trip 2, Sediment-Hosted Precious Metal Deposits. Paper in Exploration for Ore Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, pp. FT2 27-35.

359. Kluender, S. E. Mineral Investigation of the Wheeler Peak Roadless Area, White Pine County, Nevada. BuMines MLA 56-83, 1983, 28 pp.

360. Knopf, A. Geology and Ore Deposits of the Yerington District, Nevada. U.S. Geol. Surv. Prof. Paper 114, 1918, pp. 64-65.

361. _____. The Divide Silver District, Nevada. U.S. Geol. Surv. Bull. 715-K, 1921, pp. 146-170.

362. _____ . Geology and Ore Deposits of the Rochester District, Nevada. U.S. Geol. Surv. Bull. 762, 1924, 78 pp.

363. Knutsen, G. C. Geology of the Rain Gold Deposit, Elko County, Nevada. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, p. 32.

364. Koch, G. S., Jr., and R. F. Link. A Statistical Interpretation of Sample Assay Data From the Getchell Mine, Humboldt County, Nevada. BuMines RI 7383, 1970, 23 pp.

365. Koschmann, A. H., and M. H. Bergendahl. Principal Gold Producing Districts of the United States. U.S. Geol. Surv. Prof. Paper 610, 1968, 283 pp.

366. Kral, V. E. Modarelli Iron Deposit, Eureka County, Nevada. BuMines RI 4005, 1947, 7 pp.

367. _____. Buena Vista Iron Deposit, Churchill County, Nevada. BuMines RI 4094, 1947, 5 pp.

368. _____. Mineral Resources of Nye County, Nevada. NV Bur. Mines and Geol. Bull. 50, 1951, 223 pp.

369. Kunasz, I. A. Geology and Geochemistry of the Lithium Deposit in Clayton Valley, Esmeralda County, Nevada. Ph.D. Diss., PA State Univ., University Park, PA, 1970, 128 pp.

370. _____. Lithium Occurrence in the Brines of Clayton Valley, Esmeralda County, Nevada. Sec. in Fourth Symposium on Salt, ed. by A. H. Coogan. Northern OH Geol. Soc. Inc., Cleveland, OH, v. 1, 1974, pp. 57-66.

371. _____. Lithium Raw Materials. Sec. in Industrial Minerals and Rocks, ed. by S. L. Lefond. AIME, New York, 4th ed., 1975, pp. 791-803.

372. Lacana Mining Corp. Annual Report, 1982. 1983, p. 3.

373. Ladoo, R. B. Fluorspar: Its Mining, Milling and Utilization. BuMines B 244, 1927, 185 pp.

374. Langenheim, R. L., Jr. Early and Middle Mississippian Stratigraphy of the Ely Area. Intermountain Association of Petroleum Geology Guidebook to the Geology of East Central Nevada, 11th Annu. Field Conference. UT Geol. Assoc., Salt Lake City, UT, 1960, pp. 72-80.

375. Langenheim, R. L., Jr., and E. R. Larson. Correlation of Great Basin Stratigraphic Units. NV Bur. Mines and Geol. Bull. 72, 1973, 36 pp.

376. Lawrence, E. F. Antimony Deposits in Nevada. NV Bur. Mines and Geol. Bull. 61, 1963, 248 pp.

377. Lebauer, L. R. Wall Rock Alteration in the Big Divide District, Esmeralda County, Nevada. M. S. Thesis, Indiana Univ., Bloomington, IN, 1958, 37 pp.

378. Lewis, A. Leaching and Precipitation Technology for Gold and Silver Ores. Eng. and Min. J., v. 184, No. 6, 1983, pp. 48-56.

379. Lien, R. H. Recovery of Lithium From Clay by a Roast-Leach-Precipitation Process. Pres. at 35th Southeastern Regional Meeting, Am. Chem. Soc., Charlotte, NC, Nov. 9-11, 1983, 15 pp; available from BuMines Salt Lake City Research Center, Salt Lake City, UT.

380. Lightner, F. H., R. L. Faverty, and W. E. Coughlin. The Borealis Project: A Fast-Track Approach to Mine Development. Min. Eng., v. 35, No. 11, Nov. 1983, pp. 1564-1565.

381. Lincoln, F. C. Mining Districts and Mineral Resources of Nevada. NV Newsletter Publ. Co., Reno, NV, 1923, 280 pp.

382. Lincoln, F. R., and R. C. Horton. Outline of Nevada Mining History. NV Bur. Mines and Geol. Rep. 7, 1964, 27 pp.

383. Lockard, D. W., and J. H. Schilling. The Mineral Industry of Nevada. Ch. in BuMines Minerals Yearbook, v. 2, 1981, pp. 322-323.

384. Loeltz, O. J., and G. T. Malmberg. The Ground-Water Situation in Nevada, 1960. NV Dep. Conserv. and Nat. Resour., Ground-Water Resour.-Inf. Series, Rep. 1, 1961, 13 pp.

385. Long, J. R. Mountain Springs, Greystone, and Argenta Mines, Field Trip 9, Bedded Barite Deposits. Paper in Exploration for Ore Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, 4 pp.

386. Longwell, C. R., E. H. Pampeyan, B. Bowyer, and R. J. Roberts. Geology and Mineral Deposits of Clark County, Nevada. NV Bur. Mines and Geol. Bull. 62, 1965, 218 pp.

387. Louisiana Land and Exploration Co. Annual Report, 1981, Form 10-K. Securities and Exchange Commission. 1982, p. 17.

388. _____. Annual Report, 1981. 1982, pp. 3, 12-13, 33.

389. Love, W. H. The Ruby Hill Project, Eureka, Nevada. Exploration and Mine Development in Nevada. NV Bur. Mines and Geol. Rep. 13, pt. 1, 1966, pp. 85-107.

390. Lovering, T. G., and A. V. Heyl. Jasperoid as a Guide to Mineralization in the Taylor Mining District and Vicinity Near Ely, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 69, 1974, pp. 46-58.

391. Lowell, J. D. Trends and Techniques in Southwest Porphyry Exploration. World Min., v. 29, No. 11, 1976, pp. 55-59.

392. Mahoney, S. R. Barite Industry Cuts Back, Faces Seven Negative Factors. NV Min. Assoc. Bull., v. 6, No. 3, 1982, pp. 4-5.

393. Marvin, R. F., H. H. Mehnert, and E. H. McKee. A Summary of Radiometric Ages of Tertiary Volcanic Rocks in Nevada and Eastern California. Part III: Southeastern Nevada. Isochron/West, No. 6, 1973, pp. 1-29.

394. Mason Valley News (Yerington, NV). Buckskin Mine Plant Construction Work Planned. June 24, 1983, p. 1.

395. Matson, E. J. Exploration of the Mount Hope Mine, Eureka County, Nevada. BuMines RI 3728, 1946, 7 pp.

396. May, J. T., C. F. Davidson, and V. E. Edlund. Extracting Lithium From McDermitt Clay. Pres. at TMS/AIME Light Metals Committee Annu. Meeting, Dallas, TX, Feb. 15-19, 1982, TMS/AIME preprint, 1982, 11 pp.

397. May, J. T., D. S. Witkowsky, and D. C. Seidel. Extracting Lithium From Clays by Roast-Leach Treatment. BuMines RI 8432, 1980, 16 pp.

398. McBeth, J. D. Mining Practice at Carlin Gold Mining Company. Paper in Proceedings From a Symposium on Gold (Apr. 21-24, 1980, Reno, NV). Univ. NV, Reno, NV, 1980, pp. IV-1-IV-11.

399. McCarroll, S. J. Upgrading Manganese Ore: Three Kids Mine, Nevada. Min. Eng., v. 6, No. 3, 1954, pp. 289-293.

400. McClelland, G. E., D. L. Pool, and J. A. Eisele. Agglomeration-Heap Leaching Operations in the Precious Metals Industry. BuMines IC 8945, 1983, pp. 10-16.

401. McCready, D. K. Froth Flotation of the Daisy Mine Fluorite Ores, Nye County, Nevada. M. S. Thesis, Univ. NV, Reno, NV, 1965, 66 pp.

402. McInnis, W. Molybdenum—A Materials Survey. BuMines IC 7784, 1957, pp. 1-77.

403. McKee, E. H. Northumberland Caldera and Northumberland Tuff Chapter in Guidebook to the Geology of Four Tertiary Volcanic Centers in Central Nevada. NV Bur. Mines and Geol. Rep. 19, 1974, pp. 35-41.

404. _____. Geology of the Northern Part of the Toquima Range, Lander, Eureka, and Nye Counties, Nevada. U.S. Geol. Surv. Prof. Paper 931, 1976, 49 pp.

405. McKee, E. H., and R. J. Ross, Jr. Stratigraphy of Eastern Assemblage Rocks in a Window in Roberts Mountain Thrust, Northern Toquima Range, Central Nevada. Am. Assoc. of Petrol. Geol. Bull., v. 53, No. 2, 1969, pp. 421-429.

406. _____. Origin of the McDermitt Caldera in Nevada and Oregon and Its Related Mercury Deposits. Econ. Geol. and Bull. Soc. Econ. Geol., v. 71, No. 3, 1976, p. 701.

407. McKelvey, V. E., J. H. Wiese, and V. H. Johnson. Preliminary Report on the Bedded Manganese of the Lake Meade Region, Nevada and Arizona. U.S. Geol. Surv. Bull. 948-D, 1949, pp. 83-101.

408. McMillan, D. Get the Gold? Then Just Move the Town. Reno (NV) Gazette J., Oct. 10, 1982, pp. 1A, 21A.

409. McQuiston, F. W., Jr., and R. W. Hernlund. Newmont's

Carlin Gold Project. Min. Congr. J., v. 52, No. 11, 1965, p. 26, 30, 32, 38–39.

410. McQuiston, F. W., Jr., and R. S. Shoemaker. Gold and Silver Cyanidation Plant Practice. V. I., AIME, 1975, pp. 19–27.

411. _____. Carlin Gold Mining Company, Carlin, Nevada. Paper in Primary Crushing Plant Design. Soc. Min. Eng. AIME, New York, NY, 1978, pp. 195–197.

412. _____. Gold and Silver Cyanidation Plant Practice. V. II., AIME, 1981, 263 pp.

413. Merica, J. Tailings Project Detailed Engineering Approved. Ely (NV) Times, Mar. 20, 1979, p. 2.

414. _____. Silver King Open–Pits Low Grade Silver From 1880's Camp. NV Min. Assoc. Bull., v. 5, No. 3, July 1981, pp. 6–8.

415. Metals Week. Precious Metals: The Jerritt Canyon Mine Produced More Gold. V. 54, No. 6, Feb. 7, 1983, p. 8.

416. _____. Gold Output Should Increase by 22% to 93,000 Oz. V. 54, No. 8, May 2, 1983, p. 6.

417. _____. Precious Metals: Newmont's Gold Quarry Onstream in 1985. V. 55, No. 5, Jan. 30, 1984, p. 8.

418. _____. Precious Metals: Freeport Gold's Output Fell 12% to 44,000 Oz. V. 55, No. 21, May 21, 1984, p. 6.

419. Michaelson, S. D., and J. K. Hammes. Copper Ore Mining. Paper in Surface Mining, ed. by E. P. Pfleider. AIME, Mudd Series, 1968, pp. 874–896.

420. Michell, W. D. Oxidation in a Molybdenite Deposit, Nye County, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 40, 1945, pp. 99–114.

421. Middlebrook, J. Geology at Tungsten, Nevada, Emphasizing Structural Aspects. M. S. Thesis, Univ. NV, Reno, NV, 1957, 41 pp.

422. Mills, B. A. Geology of the Round Mountain Gold Deposit, Nye County, Nevada. Paper Pres. at 88th Annu. Northwest Min. Assoc. Conv., Spokane, WA, Dec. 10, 1982, 13 pp.; available from Northwest Min. Assoc., 633 Peyton Bldg., Spokane, WA 92201.

423. Mining Activity Digest. New Development Highlights, The Contribution of Metals Operations. Eng. and Min. J. Int. Directory, v. 9, No. 2, 1982, p. 1.

424. _____. New Development Highlights, Silver King Mines Has Started Mine Development of the Ward Property. Eng. and Min. J. Int. Directory, v. 9, No. 2, 1982, p. 1.

425. _____. Exploration Briefs, U.S.: Conoco Inc. Eng. and Min. J. Int. Directory, v. 9, No. 5, 1982, p. 3.

426. _____. U.S. Mine/Plant Activity—Nevada: Placer Amex, Inc. Eng. and Min. J. Int. Directory, v. 9, No. 8, 1983, p. 4.

427. _____. New Development Highlights: Ceremonies Took Place October 7 to Mark the Reopening of the Candelaria Silver Mine. Eng. and Min. J. Int. Directory, v. 10, No. 6, 1983, p. 2.

428. Mining Congress Journal. Mining is Being Resumed in the Taylor Mining District Near Ely, Nev., by Silver King Mines. V. 65, No. 12, 1979, p. 9.

429. _____. Silver King Mines, Inc., Has Dedicated Its Taylor Silver Mine Near Ely, Nev. V. 67, No. 8, 1981, p. 11.

430. _____. Construction of the Jerritt Canyon, Nev., Gold Project. V. 67, No. 10, 1981, pp. 9–10.

431. _____. Louisiana Land Has Gold Reserve Estimates. V. 68, No. 3, 1982, p. 9.

432. Mining Engineering (NY). Kennecott's Nevada Mines Division Closes for Indefinite Period. V. 28, No. 3, 1976, p. 14.

433. _____. U.V. Drills Molybdenum. V. 31, No. 5, 1979, p. 488.

434. _____. Duval Corp., U.S. and International Mineral News Briefs. V. 35, No. 7, 1983, p. 717.

435. Mining Journal (London). New Gold Horizons. V. 300, No. 7702, 1983, pp. 201–202.

436. _____. Mining Week. United States. Official Reopening of Candelaria Silver Mine. V. 301, No. 7731, 1983, p. 294.

437. _____. Mining Activity in the Western World. Table C—Major New Projects and Expansion Programmes. V. 136, No. 6, 1977, pp. 487–501.

438. _____. Processing of Copper Sulphide Ores: Froth Flotation Reagents—A Review. V. 138, No. 4, 1978, pp. 332–339.

439. _____. Pinson, Nevada—A New Open Pit Gold Mine. V. 145, No. 1, 1981, p. 5.

440. Mining Record (Denver). Occidental Minerals Developing Two Nevada Silver Properties. V. 92, No. 20, 1980, p. 3.

441. _____. Silver King Opens the Taylor Silver Mine and Plant. V. 93, No. 23, 1981, p. 2.

442. _____. Silver King in Full Production. V. 93, No. 25, 1981, p. 1.

443. _____. Pinson Gold Mine and Invisible Gold. V. 93, No. 49, 1981, pp. 1, 3.

444. _____. Merger of Electra Resources and Pacific Northwest. V. 94, No. 2, 1982.

445. _____. Nevada Silver Mine Closed. V. 94, No. 26, 1982, p. 6.

446. _____. Silver Prices Force Shutdown of Nevada Silver Mine. V. 94, No. 27, 1982, p. 6.

447. _____. Nevada's Open Pit Gold Mines Making a Profit. V. 94, No. 52, 1982, p. 5.

448. Missallati, A. A. Geology and Ore Deposits of the Mount Hope Mining District, Eureka County, Nevada. Ph.D. Diss., Stanford Univ., Stanford, CA, 1973, 160 pp., map scale 1:4,800.

449. Mitchell, A. W. Geology of Some Bedded Barite Deposits in North Central Nevada. M. S. Thesis, Univ. NV, Reno, NV, 1977, 58 pp.

450. Mitchell, G. W. Mine Drainage at Eureka Corporation Ltd., Eureka, Nevada. Min. Eng., v. 5, No. 8, 1953, pp. 812–817.

451. Mitchell, G. W., and A. C. Johnson. Shaft-Sinking Methods and Costs and Cost of Plant and Equipment at the Fad Shaft, Eureka Corporation Ltd., Eureka, Nevada. BuMines IC 7495, 1949, 17 pp.

452. Monroe, S. C. Geology and Geochemistry of the Buckhorn Mine, Eureka County, Nevada. Abstr. No. 33, 495 in Abstracts With Programs, 1984. 97th Annu. Meeting, Geol. Soc. Am., Nov. 5–8, 1984, Reno, NV, p. 599.

453. Moore, J. G. Geology and Mineral Deposits of Lyon, Douglas, and Ormsby Counties, Nevada. NV Bur. Mines and Geol. Bull. 75, 1969, 45 pp.

454. Moore, L. Economic Evaluation of California–Nevada Iron Resources and Iron Ore Markets. BuMines IC 8511, 1971, 207 pp.

455. Moores, E. M., R. B. Scott, and W. W. Lumsden. Tertiary Tectonics of the White Pine–Grant Range Region, East Central Nevada, and Some Regional Implications. Geol. Soc. Am. Bull., v. 79, No. 12, 1968, p. 1703.

456. _____. Tertiary Tectonics of the White Pine–Grant Range Region, East–Central Nevada, and Some Regional Implications—Reply. Geol. Soc. Am. Bull., v. 81, No. 2, 1970, p. 323.

457. Morris, J. M. Engineering and Design of the Pyro–Metallurgical Plant, Three Kids Mine, Henderson, Nevada. Met. E. Thesis, Univ. NV, Reno, NV, 1954, 51 pp.

458. Morrissey, F. R. Turquoise Deposits of Nevada. NV Bur. Mines and Geol. Rep. 17, 1968, 30 pp.

459. Morros, P. G. Summary of Statutory Procedures in Making Application for a Water Right and Fees Set by Statute. State of NV, Dep. Conserv. and Nat. Resourc., Div. of Water Resourc., 1983, 12 pp.

460. Morrow, A. B. Geology of the Goldstrike Mine, Elko County, Nevada. Pres. at the 88th Annu. Northwest Min. Assoc. Conv., Spokane, WA, Dec. 10, 1982, 4 pp.; available upon request from Northwest Min. Assoc., 633 Peyton Bldg., Spokane, WA 99201.

461. Motter, J. W. and P. E. Chapman. Northumberland Gold Deposit, Nye County, Nevada, Field Trip 2, Sediment–Hosted Precious Metal Deposits. Paper in Exploration for Ore Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25–28, 1984, pp. FT2 9–25.

462. Muffler, L. J. P. Geology of the Frenchie Creek Quadrangle, North–Central Nevada. U.S. Geol. Surv. Bull. 1179, 1964, 99 pp. map scale 1:62,500.

463. Muller, S. W., and H. G. Ferguson. Mesozoic Stratigraphy of the Hawthorne and Tonopah Quadrangles, Nevada. Geol. Soc. Am. Bull., v. 20, 1939, pp. 1573–1624.

464. Muller, S. W., H. G. Ferguson, and R. J. Roberts. Geologic Map of the Mount Tobin Quadrangle. U.S. Geol. Surv. Geol. Quad. Map GQ–7, 1951, scale 1:125,000.

465. Nash, J. T., and T. G. Theodore. Ore Fluids in the Porphyry Copper Deposit at Copper Canyon, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 66, No. 3, 1971, pp. 385–399.

466. Nevada Mining Association (Reno). Newsletter. No. 267, June 15, 1975, pp. 1–2.

467. _____. Newsletter. No. 291, June 15, 1977, pp. 1–2.
468. _____. Nevada Mercury Mine Increases '77 Output. Bull., v. 2, No. 5, 1978, p. 13.
469. _____. Anaconda's Moly Property Gets Another Evaluation. Bull., v. 2, No. 7, 1978, p. 11.
470. _____. Nevada's Gooseberry Mine is Profiled by Mine Geologist. Bull., v. 2, No. 7, 1978, pp. 12–13.
471. _____. Gulf Oil Drills Ward Mountain for Copper–Silver–Zinc. Bull., v. 2, No. 10, 1978, p. 11.
472. _____. U.V. Industries, Colby Mines Drill for Moly Mineralization. Bull., v. 2, No. 10, 1978, pp. 12–13.
473. _____. Kennecott Starts Engineering To Recover Copper From Tails. Bull., v. 3, No. 3–4, 1979, p. 9.
474. _____. Mercury Mine: Depressed Market; But Safety Standards High. Bull., v. 3, No. 5–6, 1979, p. 9.
475. _____. FTC Move Huge Nevada 'Moly' Mine Closer to Reality. Bull., v. 3, No. 7, 1979, pp. 3–4.
476. _____. Day Mines Will Re-Activate Elko Underground Copper Mine. Bull., v. 3, No. 7, 1979, p. 5.
477. _____. Kennecott Budgets $12–$15 Million for Recovery of Tailings. Bull., v. 3, No. 7, 1979, p. 11.
478. _____. G.E. to Re-Open Tungsten Mine in Pershing County. Bull., v. 3, No. 8, 1979, pp. 1–2.
479. _____. Freeport Reserves Expanded; Milling Upped to 2,750 tpd. Bull., v. 4, 1980, pp. 4–7.
480. _____. Cyprus to Put Northumberland Gold Mine Into Production. Bull., v. 4, Aug.–Oct. 1980, p. 16.
481. _____. List, Santini Welcomes Amselco's New Gold "Heap Leach" Mine. Bull., v. 5, No. 2, 1981, pp. 1–2.
482. _____. Pinson Gold Mine in Production With Efficient, Automated Mill. Bull., v. 5, No. 2, 1981, pp. 2–3.
483. _____. Sunshine's Silver Peak Mine Unlike Famed Silver Lode in Idaho. Bull., v. 5, No. 2, 1981, pp. 4–5.
484. _____. Duval Corporation Discovery Boosts Open Pit Gold Reserves in Lander. Bull., v. 5, No. 6, 1981, p. 8.
485. _____. Santini, HIMCO Officials Join Dedication of New Borealis Mine. Bull., v. 5, No. 6, 1981, pp. 10–11.
486. _____. Energy Reserves Group Finds Gold Mineralization in Eureka County. Bull., v. 5, No. 6, 1981, p. 16.
487. _____. Santini Lauds Opening of Silver Peak Underground Silver Mine. Bull., v. 6, No. 1, 1982, pp. 14–15.
488. _____. HIMCO's Borealis Gold Mine Geology Described in Report. Bull., v. 6, No. 2, 1982, pp. 14-15.
489. _____. Sunshine Sixteen-To-One Mine Opens in Silver Peak; Bucks Trend. Bull., v. 6, No. 3, 1982, pp. 6-7.
490. _____. Silver King's Ward Mine Near Ely Gearing for Production. Bull., v. 6, No. 4, 1982, p. 15.
491. _____. NERCO Makes Bid for Two Large Precious Metal Mines in Nevada. Bull., v. 7, No. 1, 1983, pp. 12-13.
492. _____. Smoky Valley Mine Benefits Told; Land Ownership Disputed. Bull., v. 7, No. 1, 1983, pp. 16-17, 20.
493. _____. Dee Gold Mine Gears Up; Bids Out for Construction of Mill. Bull., v. 7, No. 3, 1983, p. 5.
494. _____. Tenneco Restarts Open-Pit Gold Mine at Historic Manhattan. Bull., v. 7, No. 3, 1983, p. 8.
495. _____. Placer Amex Test Run of New Open-Pit Gold Mine. Bull., v. 7, No. 3, 1983, p. 10.
496. _____. Lacana Constructs Test "Heaps" for Relief Canyon Mine. Bull., v. 7, No. 3, 1983, p. 14.
497. _____. Goldfield May Be Scene of Joint Venture Open-Pit Mine. Bull., v. 7, No. 3, 1983, p. 18.
498. _____. NERCO Reopens Nation's Largest Open Pit Silver Mine. Bull., v. 8, No. 1, 1984, p. 15.
499. _____. Placer Development Targets U.S. Activities on Precious Metals. Bull., v. 8, No. 2, 1984, p. 4.
500. _____. Fortitude Gold-Silver Mine Boosts Duval's Nevada Production. Bull., v. 8, No. 2, 1984, p. 9.
501. _____. Industrial Development Bonds Used To Help Finance New Mine. Bull., v. 8, No. 2, 1984, p. 12.
502. _____. Blackhawk and Southern Pacific Joint Venture Goldfield Project. Bull., v. 8, No. 2, 1984, p. 13.
503. _____. Lacana Becomes Operator of Santa Fe Gold Property Near Luning. Bull., v. 8, No. 2, 1984, p. 15.
504. _____. Gooseberry Mine Modifies Leach Circuit; At Full Production. Bull., v. 8, No. 2, 1984, p. 19.
505. _____. Carlin Gold Mining Co. Tour 1, NV Min. Assoc. Conf., Elko, NV, Sept. 7, 1984, 9 pp.
506. _____. Carlin Gold Mining Co.—Bootstrap. Tour 1, NV Min. Assoc. Conf., Elko, NV, Sept. 7, 1984, 1 p.
507. _____. Carlin Gold Mining Co.—Gold Quarry Process Facilities Tour 1, NV Min. Assoc. Conf. Elko, NV, Sept. 7, 1984, 5 pp.
508. _____. Carlin Gold Mining Co.—Maggie Creek Heap Leach Facilities. Tour 1, NV Min. Assoc. Conf., Elko, NV, Sept. 7, 1984, 15 pp.
509. Nevada State Journal (Reno). Hazards of Mining Carson River Outlined. June 13, 1982, p. 5.
510. Newmont Mining Corp. Annual Report, 1974. 1975, p. 12.
511. _____. Annual Report, 1983. 1984, pp. 9, 22-23.
512. New Mexico Paydirt (Bisbee, AZ). Houston Minerals To Begin Development of Major Open-Pit Gold Mine. No. 45, Feb. 1981, p. 58.
513. _____. Of Mines and Men. No. 75, Aug. 1983, p. 8A.
514. _____. Of Mines and Men. No. 84, May 1984, p. 31A.
515. Nickle, N. L. Geology of the Southern Part of the Buena Vista Hills, Churchill County, Nevada. M.S. Thesis, Univ. CA, Los Angeles, CA, 1968, 84 pp.
516. Noble, L. L., and A. S. Radtke. Geology of the Carlin Disseminated Replacement Gold Deposit, Nevada. Paper in Guidebook to Mineral Deposits of the Central Great Basin. NV Bur. Mines and Geol. Rep. 32, 1978, pp. 40-44.
517. Noble, L. L., J. Valiquett, and C. Ekburg. Geology of the Blue Star Gold Deposit Near Carlin, Nevada. Rep. distributed at Pacific Southwest Miner. Ind. Conf., Stateline, NV, 1977, 11 pp.; available upon request from BuMines Library, Western Field Operations Center, Spokane, WA, 99202.
518. Nolan, T. B. The Eureka District, Nevada. U.S. Geol. Surv. Prof. Paper 406, 1962, 78 pp.
519. _____. The Eureka Mining District, Nevada. Guidebook to Mineral Deposits of the Central Great Basin, Nevada. NV Bur. Mines and Geol. Rep. 32, 1978, pp. 51-54.
520. Nolan, T. B., and R. N. Hunt. The Eureka Mining District, Nevada. Paper in Ore Deposits of the United States, 1933-1967, ed. by J. D. Ridge. AIME, New York, v. 1 (Graton-Sales), 1968, pp. 966-991.
521. Nolan, T. B., C. W. Merriam, and W. V. Steele. The Stratigraphic Section in the Vicinity of Eureka, Nevada. U.S. Geol. Surv. Prof. Paper 276, 1956, 77 pp.
522. Nolan, T. B., C. W. Merriam, and M. C. Blake, Jr. Geologic Map of the Pinto Summit Quadrangle, Eureka and White Pine Counties, Nevada. U.S. Geol. Surv. Map I-793, 1974, scale 1:31,680.
523. North American Gold Mining Industry News (Wilsonville, OR). Recent Lacana, Santa Fe Results. V. 2, Iss. 4, Mar. 15, 1984, p. 4.
524. _____. Pecos Plans $1.5 Million Program at Dexter Mine in Nevada. V. 2, Iss. 4, Mar. 15, 1984, p. 13.
525. _____. Lacana Treating Ore Heaps at Relief Canyon Property. V. 2, Iss. 19, Oct. 12, 1984, p. 13.
526. Northern Miner (Toronto). Oxbow in Production at Nevada Tungsten Mine. Sept. 16, 1976, p. 11.
527. _____. Oxbow Nevada Tungsten Mill Expansion Is in View. Feb. 10, 1977, p. 6.
528. _____. Home Oil, Scurry, and Asamera in U.S. Gold-Silver Mine Deal. Dec. 2, 1982, pp. 1-2.
529. _____. Cordex V Syndicate To Go to Production. Apr. 7, 1983, p. 1.
530. _____. Lacana Increases Profit, Revenue; Cites Activity on Several Fronts. Sept. 1, 1983, p. 5.
531. _____. Pezamerica Makes Bid for Corona. May 17, 1984, pp. A1-A2.
532. _____. Ruskin Plans Drilling Hilltop Gold Property. June 21, 1984, p. A14.
533. _____. Geomex Impressed by Nevada Mine but Bralorne Placed on Standby. July 26, 1984, p. 12.
534. _____. Pecos Resources Concentrates Efforts on Western U.S. Heap Leach Prospect. Oct. 11, 1984, p. 20.
535. Norton, J. J. Lithium, Cesium, and Rubidium—The Rare

Alkali Metals. Ch. in United States Mineral Resources, ed. by D. A. Brobst and W. P. Pratt. U.S. Geol. Surv. Prof. Paper 820, 1973, pp. 365-378.

536. Ohle, E. L. Evaluation of Iron Ore Deposits. Econ. Geol. and Bull. Soc. Econ. Geol., v. 67, No. 7, 1972, pp. 953-964.

537. Oliveira, J. L. Road Log/Trip Guide: Gooseberry Mine. Field Trip Guidebook, Field Trip 12. Paper in Exploration for Ore Deposits in the North American Cordillera, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, p. FT12 1.

538. Olsen, D. R. Geology and Mineralogy of the Delno Mining District and Vicinity, Elko County, Nevada. Ph.D. Diss., Univ. UT, Salt Lake City, UT, 1960, 96 pp.

539. Ott, L. E. Geology and Ore Localization at the Northumberland Gold Mine, Nye County, Nevada. M.S. Thesis, MT College Miner. Sci. Technol., Butte, MT, 1983, 52 pp.

540. Page, B. M. Geology of the Candelaria Mining District, Mineral County, Nevada. NV Bur. Mines and Geol. Bull. 56, 1959, 67 pp.

541. _____. Preliminary Geologic Map of a Part of the Stillwater Range, Churchill County, Nevada. NV Bur. Mines and Geol. Map 28, 1965, scale 1:125,000.

542. Pantea, M. P., and S. Asher-Bolinder. Lithological Log and Lithium Content of Sediments Drilled in Clayton Valley, Esmeralda County, Nevada. U.S. Geol. Surv. OFR 82-415, 1982, 13 pp.

543. Pantea, M. P., S. Asher-Bolinder, and J. D. Vine. Lithology and Lithium Content of Sediments in Basin Surrounding Clayton Valley, Esmeralda and Nye Counties, Nevada. U.S. Geol. Surv. OFR 81-962, 1981, 23 pp.

544. Papke, K. Evaporites and Brines in Nevada Playas. NV Bur. Mines and Geol. Bull. 87, 1976, pp. 29-31.

545. _____. Fluorspar in Nevada. NV Bur. Mines and Geol. Bull. 13, 1979, 77 pp.

546. _____. Barite Deposits in Nevada. NV Bur. Mines and Geol. Bull. 98, 1984, 125 pp.

547. Pardee, J. T., and E. L. Jones, Jr. Deposits of Manganese Ore in Nevada. U.S. Geol. Surv. Bull. 710-F, 1920, pp. 158-248.

548. Parkinson, E. A., and A. L. Mular. Mineral Processing Equipment Costs and Preliminary Capital Cost Estimations. Can. Inst. Min. and Metall. Spec., v. 13, 1972, 140 pp.

549. Parkinson, G. Golden Pilot Plant Points Way to 500,000 TPY Alumina From Alunite Mine and Plant in Utah. Eng. and Min. J., v. 175, No. 8, 1974, pp. 75-78.

550. Parkhurst, D. Carbon Adsorption Method for Processing Gold Ores. Min. Record (Denver), v. 94, No. 29, July 21, 1982, p. 4.

551. _____. More Gold Ore Found at Jerritt Canyon. Min. Record (Denver), v. 95, No. 10, 1983, p. 1.

552. Pastorino, M. Eureka's Windfall Mine Has Rich History. Ely (Nevada) Daily Times. Sept. 5, 1978, p. 3.

553. Pazour, D. A. Union Carbide Increases Tungsten Production With New Nevada Mine. Min. World, v. 40, No. 3, 1978, pp. 58-59.

554. Pearce, R. C. Rayrock, Siscoe, Lacana Team Launch Pinson Project in Nevada. Northern Miner (Toronto), v. 67, No. 11, 1981, pp. 1, A28-A29.

555. _____. Rich Rewards From Nevada Gold for Rayrock, Dome, and Lacana. Northern Miner (Toronto), v. 69, No. 12, 1983, pp. 1, 6.

556. Pennebaker, E. N. Geology of the Robinson (Ely) Mining District in Nevada. Min. and Met., v. 13, No. 304, 1932, pp. 163-168.

557. Peters, W. C. The Geologic Environment of Fluorspar Deposits in the Western United States. Ph.D. Diss., Univ. CO, Boulder, CO, 1956, 113 pp.

558. _____. Some Geological Comparisons—Recent Porphyry Copper Discoveries. Min. Congr. J., v. 56, No. 10, 1970, pp. 29-31.

559. Peterson, E. C. Iron Ore. Ch. in Mineral Facts and Problems, 1980 Edition. BuMines B 671, 1981, pp. 433-453.

560. Pinson Mining Co. Pinson Mining Company, Field Trip 1, Sediment-Hosted Gold Deposits. Paper in Exploration for Gold Deposits of the North American Cordillera, Field Trip Guidebook, ed. by J. L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, pp. FT1 11-15.

561. _____. Company Brochure on Pinson Mine. Pres. at Open House, May 12, 1981, 7 pp.; available at Pinson Min. Co., Winnemucca, NV.

562. Pizarro, R., J. D. McBeth, and G. M. Potter. Heap Leaching Practice at the Carlin Gold Mining Company, Carlin, Nevada. Paper in Solution Mining Symposium, 1974 (Proc., 103d AIME Annu. Meeting, Dallas, TX, Feb. 25-27, 1974). AIME, 1974, pp. 253-267.

563. Placer Development Ltd. Annual Report, 1980. 1981, pp. 9-10, 19.

564. _____. Annual Report, Form 10-K, Fiscal Year Ended December 31, 1982. Securities and Exchange Commission, 1983, 67 pp.

565. Poole, F. G. Flysch Deposits of Antler Foreland Basin, Western United States. Paper in Tectonics and Sedimentation, ed. by W. R. Dickson. Soc. Econ. Paleontologists and Mineral., Spec. Publ. No. 22, 1974, pp. 58-82.

566. Powers, S. L. Jasperiod and Disseminated Gold at the Ogee-Pinson Mine, Humboldt County, Nevada. M.S. Thesis, Univ. NV, Reno, NV, 1978, 88 pp.

567. Proffett, J. M., and J. H. Dilles. Geologic Map of the Yerington District, Nevada. NV Bur. Mines and Geol., Univ. of NV, Reno, Map 77, 1984.

568. Radtke, A. S. Geology and Mineralogy of the Buena Vista Iron Ores, Churchill County, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 59, No. 2, 1964, pp. 279-290.

569. _____. Preliminary Geologic Map of the Carlin Gold Mine, Eureka County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF-537, 1973, scale 1:3,600.

570. _____. Preliminary Geologic Map of the Area of the Carlin and Blue Star Gold Deposits, Eureka County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF-552, 1974, scale 1:12,000.

571. _____. Geology of the Carlin Gold Deposit, Nevada. U.S. Geol. Surv. OFR 81-97, 1981, 154 pp.

572. Radtke, A. S., R. O. Rye, and F. W. Dickson. Geology and Stable Isotope Studies of the Carlin Gold Deposit, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., No. 5, 1980, pp. 641-672.

573. Radtke, A. S., and B. J. Scheiner. Studies of Hydrothermal Gold Deposition (I). Carlin Gold Deposit, Nevada: The Role of Carbonaceous Materials in Gold Deposition. Econ. Geol. and Bull. Soc. Econ. Geol., v. 65, No. 2, 1970, pp. 87-102.

574. Ramsey, R. H. Weed Heights: Anaconda's Nevada Project—New Approach to Copper Mining. Eng. and Min. J., v. 155, No. 8, 1954, pp. 74-93.

575. Ransome, F. L. The Yerington Copper District, Nevada. Paper in Contributions to Economic Geology, 1908, pt. 1, ed. by C. W. Hayes and W. Lindgren. U.S. Geol. Surv. Bull. 380, 1909, pp. 99-119.

576. _____. Geology and Ore Deposits of Goldfield, Nevada. U.S. Geol. Surv. Prof. Paper 66, 1909, 258 pp.

577. Ravenscroft, A. W. The Geology of the Big Bald Mountain, White Pine County, Nevada. M.S. Thesis, San Diego State Univ., San Diego, CA, 1974, 90 pp.

578. Reeves, L. Pinson/Preble. Geology and Exploration Aspects of Fine-Grained, Carlin-Type Gold Deposits. Pres. at Geol. Soc. NV and Mackay School of Mines Symp., Reno, NV, Mar. 26, 1976, 14 pp.; available upon request from Mackay School of Mines Library, Univ. NV, Reno, NV.

579. Reeves, R. G., and V. E. Kral. Iron Ore Deposits of Nevada. Part A, Geology and Iron Ore Deposits of the Buena Vista Hills, Churchill and Pershing Counties, Nevada. NV Bur. Mines and Geol. Bull. 53A, 1955, 32 pp.

580. Reeves, R. G., F. R. Shawe, and V. E. Kral. Iron Ore Deposits of Nevada. Part B, Iron Ore Deposits of West-Central Nevada. NV Bur. Mines and Geol. Bull. 53, 1958, 97 pp.

581. Regnier, J. P. M. Cenozoic Geology in the Vicinity of Carlin, Nevada. Geol. Soc. Am. Bull., v. 71, 1960, p. 1189.

582. Reno (NV) Gazette Journal. Silver King Plans to Reopen Ely Mine. Aug. 28, 1982, p. 9.

583. Reno, H. T., and F. E. Brantley. Iron—A Materials Survey. BuMines IC 8574, 1973, 177 pp.

584. Rice, C. T. The Manhattan Mining District, Nevada. Eng. and Min. J., v. 22, No. 13, 1906, pp. 581-583.

585. Richins, R. T. Mercury Content of Aquatic Organisms in the Carson River Drainage System. M.S. Thesis, Univ. NV, Reno, NV, 1973, 82 pp.

586. Richins, R. T., and A. C. Risser, Jr. Total Mercury in Water, Sediment, and Selected Aquatic Organisms, Carson River, Nevada—1972. U.S. Environ. Protection Agency Pesticides Monitoring J., v. 9, No. 1, June 1975, pp. 44-54.

587. Rigby, J. K. Geology of the Buck Mountain-Bald Mountain Area, Southern Ruby Mountains, White Pine County, Nevada. Intermountain Assoc. Petrol. Geol. Guidebook to the Geology of East Central Nevada, 11th Annu. Field Conf., UT Geol. Assoc., Salt Lake City, UT, 1960, pp. 173-180, fig. 4, scale 1:125,000; fig. 5, scale 1:125,000.

588. Roberts, R. J. Antler Peak Quadrangle, Nevada. U.S. Geol. Surv. Geol. Quad. Map GQ-10, 1951, scale 1:62,500.

589. _____. Alignment of Mining Districts in North-Central Nevada. Paper in Short Papers in the Geological Sciences. U.S. Geol. Surv. Prof. Paper 400-B, 1960, pp. B17-B19.

590. _____. Stratigraphy and Structure of the Antler Peak Quadrangle, Humboldt and Lander Counties, Nevada. U.S. Geol. Surv. Prof. Paper 459-A, 1964, pp. A1-A93.

591. Roberts, R. J., and D. C. Arnold. Ore Deposits in the Antler Peak Quadrangle, Humboldt and Lander Counties, Nevada. U.S. Geol. Surv. Prof. Paper 459-B, 1965, pp. B1-B94.

592. Roberts, R.J., P.E. Hotz, J. Gilluly, and H.G. Ferguson. Paleozoic Rocks in North Central Nevada. AAPG Bull., v. 42, No. 12, 1958, pp. 2813-2857.

593. Roberts, R.J., K.M. Montgomery, and R.E. Lehner. Geology and Mineral Resources of Eureka County, Nevada. NV Bur. Mines and Geol. Bull. 64, 1967, 152 pp.

594. Roberts, R.J., A.S. Radtke, R.R. Coats, M.L. Silberman, and E.H. McKee. Gold Bearing Deposits in North-Central Nevada and Southwestern Idaho. Econ. Geol. and Bull. Soc. Econ. Geol., v. 66, No. 1, 1971, pp. 14-33.

595. Robinson, P.T., E.H. McKee, and R.J. Moiola. Cenozoic Volcanism and Sedimentation, Silver Peak Region, Western Nevada and Adjacent California. Ch. in Studies in Volcanology—A Memoir in Honor of Howel Williams. Geol. Soc. Am. Memoir 116, 1968, pp. 577-611.

596. Roper, M.W. Hot Springs Mercury Deposition at McDermitt Mine, Humboldt County, Nevada. Trans. Soc. Min. Eng. AIME, v. 260, June 1976, pp. 192-195.

597. Rose, R.L. Geology of Parts of the Wadsworth and Churchill Butte Quadrangles, Nevada. NV Bur. Mines and Geol. Bull. 71, 1969, 29 pp.

598. Ross, D.C. Geology and Mineral Deposits of Mineral County, Nevada. NV Bur. Mines and Geol. Bull. 58, 1961, 98 pp.

599. Ross, D.M. Environmental Pitfalls of Hard-Rock Mining in the West. Pres. at a Symposium on Gold (Apr. 21-24, 1980), 6 pp.; available from Mackay School of Mines, Univ. NV, Reno, NV.

600. Roylance, J.G. The Dayton Iron Deposits, Lyon and Storey Counties, Nevada. Paper in Papers Pres. at Soc. Min. Eng. AIME Pacific Southwest Mineral Industry Conf., Sparks, NV, May 5-7, 1965. NV Bur. Mines and Geol. Rep. 13, pt. A, 1966, pp. 125-142.

601. Rye, R.O., D.R. Shawe, and F.G. Poole. Stable Isotope Studies of Bedded Barite at East Northumberland Canyon in Toquima Range, Central Nevada. U.S. Geol. Surv. J. Res., v. 6, No. 2, 1978, pp. 221-229.

602. Rytuba, J.J., and R.K. Glanzman. Relation of Mercury, Uranium, and Lithium Deposits to the McDermitt Caldera Complex, Nevada-Oregon. Paper in Papers on Mineral Deposits of Western North America. NV Bur. Mines and Geol. Rep. 33, 1979, pp. 109-117.

603. Rytuba, J.J., R.K. Glanzman, and W.K. Conrad. Uranium, Thorium, and Mercury Distribution Through the Evolution of the McDermitt Caldera Complex. Paper in Proceedings of Rocky Mountain Association of Geologists/Utah Geological Association Basin and Range Symposium and Great Basin Field Conference (Las Vegas, NV, Oct. 7-11, 1979), ed. by G.W. Newman and H.D. Goode. RMAG, 1979, pp. 405-412.

604. Sainsbury, C.L., and F.J. Kleinhampl. Fluorite Deposits of the Quinn Canyon Range, Nevada. Paper in Contributions to Economic Geology. U.S. Geol. Surv. Bull. 1272-C, 1969, 22 pp.

605. Sayers, R.W., M.C. Tippet, and E.D. Fields. The Ore Deposits at Copper Canyon and Copper Basin, Lander County, Nevada. Trans. Soc. Min. Eng. AIME, v. 244, No. 3, 1967, pp. 320-331.

606. _____. Duval's New Copper Mines Show Complex Geologic History. Min. Eng., v. 20, No. 3, 1968, pp. 55-62.

607. Schafer, R.W. The Mineralogy, Structure, and Alteration Pattern of the Gooseberry Mine, Storey County, Nevada. M.S. Thesis, Miami Univ., Oxford, OH, 1976, 79 pp.

608. Schilling, J.H. An Inventory of Molybdenum Occurrences in Nevada. NV Bur. Mines and Geol. Rep. 2, 1962, 48 pp.

609. _____. The Gabbs Magnesite-Brucite Deposit, Nye County, Nevada. Ch. 77 in Ore Deposits of the United States, 1933-1967, ed. by J.D. Ridge. AIME, v. II (Graton-Sales), 1968, pp. 1607-1622.

610. _____. Molybdenum Deposits and Occurrences in Nevada. NV Bur. Mines and Geol. Map 66, 1980, scale 1:1,000,000.

611. _____. The Nevada Mineral Industry. NV Bur. Mines and Geol. Spec. Publ. MI-1983, 1984, 40 pp.

612. Schilling, J.H., and J. Hall. The Nevada Mineral Industry. NV Bur. Mines and Geol. Spec. Publ. MI-1980, 1981, 41 pp.

613. Schrader, F.C. The Rochester Mining District, Nevada. U.S. Geol. Surv. Bull. 580-M, 1914, pp. 325-372.

614. Schreck, A.E. Lithium: A Materials Survey. BuMines IC 8053, 1961, 80 pp.

615. Scott, M. Half of Nation's Mercury Comes From McDermitt. NV State J. (Reno), Feb. 5, 1979, p. 28.

616. Shanley, F.E. A Geologic and Economic Analysis of the Disseminated Gold Investment Alternative. M.S. Thesis, Stanford Univ., Stanford, CA, 1977, 149 pp.

617. Sharp, L.E., and B.L. Myerson. Preliminary Report on a Uranium Occurrence in the Atlanta Area, Lincoln County, Nevada. U.S. Atomic Energy Commission, Div. Raw Mater., Salt Lake Area Office, RME-2048 (rev.), 1956, 18 pp.

618. Sharp, R.P. Stratigraphy and Structure of the Southern Ruby Mountains, Nevada. Geol. Soc. Am. Bull., v. 53, 1942, pp. 681-684.

619. Shaver, S.A. Elemental Dispersion at the Hall (Nevada Moly) Porphyry Molybdenum Deposit, Nye County, Nevada, and Its Relationship to Features of Alteration and Mineralization. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, p. 28.

620. Shawe, D.R. Mineral Resources Potential of the Round Mountain Quadrangle, Nevada. U.S. Geol. Surv. Field Studies Map MF-834, 1977, scale 1:24,000.

621. _____. Geologic Map of the Round Mountain Quadrangle, Nye County, Nevada. U.S. Geol. Surv. OFR 81-515, 1981, 42 pp.

622. _____. Gold and Silver Potential of the Round Mountain and Manhattan Quadrangles, Nye County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF-1467, 1982, scale 1:24,000.

623. Shawe, D.R., F.G. Poole, and D.A. Brobst. Bedded Barite in East Northumberland Canyon, Nye County, Nevada. U.S. Geol. Surv. Circ. 555, 1967, 8 pp.

624. _____. Newly Discovered Bedded Barite Deposits in East Northumberland Canyon, Nye County, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 64, No. 3, 1969, pp. 245-254.

625. Shawe, F.R., R.G. Reeves, and V.E. Kral. Iron Ore Deposits of Nevada. NV Bur. Mines and Geol. Bull. 53-C, 1962, pp. 82-125.

626. Silberling, N.J. Pre-Tertiary Stratigraphy and Upper Triassic Paleontology of the Union District, Shoshone Mountains, Nevada. U.S. Geol. Surv. Prof. Paper 322, 1959, 67 pp.

627. Silberman, M.L., and R.P. Ashley. Age of Ore Deposition at Goldfield, Nevada, From Potassium-Argon Dating of Alunite. Econ. Geol. and Bull. Soc. Econ. Geol., v. 65, No. 3, 1970, pp. 352-354.

628. Silberman, M.L., B.R. Berger, and R.A. Koski. K-Ar Age Relations of Granodiorite Emplacement and Tungsten and Gold Mineralization Near the Getchell Mine, Humboldt County, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 69, No. 5, 1974, pp. 646-656.

629. Silberman, M.L., H.F. Bonham, Jr., L.J. Garside, and R.P. Ashley. Timing of Hydrothermal Alteration-Mineralization and Igneous Activity in the Tonopah Mining District and Vicinity, Nye and Esmeralda Counties, Nevada. Paper in Papers on Mineral

Deposits of Western North America. NV Bur. Mines and Geol. Rep. 33, 1979, pp. 119-126.

630. Silberman, M.L., and E.H. McKee. K-Ar Ages of Granitic Plutons in North-Central Nevada. Isochron/West, No. 71-1, 1971, pp. 15-32.

631. _____. Ages of Tertiary Volcanic Rocks and Hydrothermal Precious-Metal Deposits in Central and Western Nevada. NV Bur. Mines and Geol. Rep. 19, 1974, pp. 67-72.

632. Silberman, M.L., J.H. Stewart, and E.H. McKee. Igneous Activity, Tectonics, and Hydrothermal Precious-Metal Mineralization in the Great Basin During Cenozoic Time. Pres. at Soc. Min. Eng. AIME Annu. Meeting, Las Vegas NV, Feb. 22-26, 1976. Soc. Min. Eng. preprint 76-1102, 18 pp.

633. Silver King Mines, Inc. (Salt Lake City, UT). Annual Report, Year Ended Apr. 30, 1976. Pp. 2, 7-9.

634. _____. Annual Report, Year Ended Apr. 30, 1978. 12 pp.

635. _____. Annual Report, Year Ended Mar. 31, 1980. 12 pp.

636. _____. Annual Report, Year Ended Mar. 31, 1981. 14 pp.

637. _____. Annual Report, Year Ended Mar. 31, 1983. 16 pp.

638. Singleton, R.H. Lithium. BuMines Mineral Commodity Profile, 1979, 25 pp.

639. Sisselman, R. New McDermitt Mine Joint Venture Emerges as Dominant Force in U.S. Mercury Production. Eng. and Min. J., v. 176, No. 12, 1975, pp. 72-77.

640. Skillings, D.N., Jr. Pinson Mining Company Marking First Full Year of Gold Production. Skillings' Min. Rev., v. 71, No. 28, 1982, pp. 8-12.

641. Skillings' Mining Review. Duval Starts Up Battle Mountain, Nevada Property. V. 56, No. 20, 1967, p. 14.

642. _____. Placer Amex's New McDermitt Mercury Mine: Plant in Northern Nevada With Annual Capacity of 20,000 Flasks. V. 64, No. 52, 1975, pp. 1, 6-7.

643. _____. McDermitt Mercury Mine at Designed Capacity of 20,000 Flasks Annually. V. 65, No. 26, 1976, p. 18.

644. _____. Silver King Acquires Ward Property: Option on Taylor Mine. V. 66, No. 35, 1977, p. 22.

645. _____. Gulf Oil Acquires 51 Percent of Silver King's Nevada Properties. V. 67, No. 7, 1978, p. 16.

646. _____. News (& Rumor) From the Bush. V. 68, No. 3, 1979, p. 27.

647. _____. Denison Acquires Option on the Taylor Silver Property. V. 68, No. 15, 1979, p. 5.

648. _____. Duval Starts Copper Facility at Battle Mountain, Nevada. V. 68, No. 26, 1979, p. 8.

649. _____. First Silver Poured at Candelaria Mine in Nevada. V. 70, No. 7, 1981, p. 23.

650. _____. Ventures West Option for Brican Resources Santa Fe Claims. V. 70, No. 26, 1981, p. 16.

651. _____. Borealis Gold/Silver Mine of Tenneco Begins Output. V. 70, No. 52, 1981, p. 18.

652. _____. Ore Processing Operations at Silver King's Taylor Mine. V. 71, No. 13, 1982, p. 5.

653. _____. Sunshine Dedicates 16-to-1 Silver Project in Nevada. V. 71, No. 20, 1982, p. 6.

654. _____. Silver Production Resumes at Taylor Open Pit Mine. V. 71, No. 40, 1982, p. 6.

655. _____. NERCO Agrees To Acquire Oxymin From Occidental Petroleum. V. 72, No. 1, 1983, p. 7.

656. _____. News (& Rumor) From the Bush. V. 72, No. 37, 1983, p. 10.

657. _____. Westley/Lacana Agreement To Fund Santa Fe Project in Nevada. V. 72, No. 52, 1983, p. 4.

658. _____. Lacana To Proceed With Relief Canyon Gold Project in Nevada: Heap Leaching To Begin in October at Deposit Near Lovelock, Nev. V. 73, No. 19, 1984, p. 21.

659. _____. Dee Open Pit Gold Mine and Mill in Nevada for September Start Up. V. 73, No. 21, 1984, p. 25.

660. _____. Atlas Corp. Announces Discovery of Gold Bar Deposit in Nevada. V. 73, No. 37, 1984, p. 8.

661. Slack, J. Structure, Petrology and Ore Deposits of the Indian Springs (Delano Mountains) Region, Elko County, Nevada. M.S. Thesis, Miami Univ., Oxford, OH, 1972, 159 pp.

662. Slavik, G. (ed.). Pinson Mine, Florida Canyon Deposit, Rochester District, and Relief Canyon Deposit. Geol. Soc. NV 1984 Meeting, Field Trip, and Road Log, Sept. 21-23, 1984, Reno, NV, 68 pp.

663. Smith, J.F., Jr., and K.B. Ketner. Generalized Geologic Map of the Carlin, Dixie Flats, Pine Valley, and Robinson Mountain Quadrangles, Elko and Eureka Counties, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF-481, 1972, scale 1:125,000.

664. _____. Stratigraphy of Paleozoic Rocks in the Carlin-Pinon Range Area, Nevada. U.S. Geol. Surv. Prof. Paper 867-A, 1975, pp. A1-A87.

665. _____. Geologic Map of the Carlin-Pinon Range Area, Elko and Eureka Counties, Nevada. U.S. Geol. Surv. Map I-1028, 1978, scale 1:62,500.

666. Smith, M.C. Methods and Operations at the Yerington Copper Mine and Plant of the Anaconda Company, Weed Heights, Nevada. BuMines IC 7848, 1958, 37 pp.

667. Smith, M.E., and W.B. Craft. Pilot Scale Heap Leaching at the Pinson Mine, Humboldt County, Nevada. Pres. at Soc. Min. Eng. AIME Fall Meeting, Salt Lake City, UT, Oct. 19-21, 1983. Soc. Min. Eng. AIME preprint 83-343, 7 pp.

668. Smith, M.R. The Pumpkin Hollow Magnesian Iron-Copper Skarn, Field Trip 10, Skarn Deposits. Exploration for Ore Deposits of the North American Cordillera Field Trip Guidebook, ed. by J.L. Johnson. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, pp. 41-42.

669. Smith, R.M. Mineral Resources of Elko County, Nevada. U.S. Geol. Surv. OFR 76-56, 1976, 194 pp.

670. Smoky Valley Memo. Special Edition. Smoky Valley Min. Div., Round Mountain, NV, v. 3, No. 18-A, Sept. 22, 1983, 6 pp.; available from Smoky Valley Min. Div., Round Mountain, NV.

671. Speed, R.C. Geologic Map of the Humboldt Lopolith and Surrounding Terrain, Nevada. Geol. Soc. Am. Map and Chart Series MC-14, 1976, scale 1:81,000.

672. Speed, R.C., and T.A. Jones. Synorogenic Quartz Sandstone in the Jurassic Mobile Belt of Western Nevada, Boyer Ranch Formation. Geol. Soc. Am. Bull., v. 80, No. 12, 1969, pp. 2551-2584.

673. Speer, W.E. Geology of the McDermitt Mine Area. M.S. Thesis, Univ. AZ, Tucson, AZ, 1977, 65 pp.

674. Spencer, A.C. Geology and Ore Deposits of Ely, Nevada. U.S. Geol. Surv. Prof. Paper 96, 1917, 189 pp.

675. Spokane (WA) Daily Chronicle. Cominco To Develop Mine. Sept. 9, 1983, p. D16.

676. Spokesman-Review (Spokane, WA). Nerco Buys Half of Taylor Mine. Apr. 3, 1984, p. C5.

677. Spurr, J.E. Ore Deposits of the Silver Peak Quadrangle, Nevada. U.S. Geol. Surv. Prof. Paper 55, 1906, 174 pp.

678. Staatz, M.H., and D.H. Johnson. Atlanta Mine. Paper in Radioactive Deposits of Nevada, ed. by T.G. Lovering. U.S. Geol. Surv. Bull. 1009-C, 1954, pp. 81-84.

679. Stager, H.K. A New Beryllium Deposit at the Mount Wheeler Mine, White Pine County, Nevada. Ch. 33 in Short Papers in the Geological Sciences. U.S. Geol. Surv. Prof. Paper 400-B, 1960, pp. B70-B71.

680. Standard Slag Co. Welcome to Standard Slag Company (Atlanta Mine). Min. District File No. 164, item 6, 1982, 2 pp.; available at NV Bur. Mines and Geol., Reno, NV.

681. Stanford, W.D. Alligator Ridge: From a Lone Prospector's Discovery to an Operating Gold Mine. Min. Eng. (NY), v. 36, No. 6, June 1984, pp. 593-598.

682. State of Nevada. Water for Nevada—Nevada's Water Resources. Dep. Conserv. and Nat. Resourc., Office of the State Engineer, Rep. 3, 1971, 126 pp.

683. _____. Directory of Nevada Mine Operations Active During Calendar Year 1975. Dep. Ind. Relations, Div. of Mine Insp., 1976, 70 pp.

684. _____. Nevada Water Facts. Dep. Conserv. and Nat. Resourc., Div. of Water Planning, 1980, 74 pp.

685. _____. Directory of Nevada Mine Operations Active During Calendar Year 1980. Dep. Ind. Relations, Div. Mine Insp., 1981, pp. 60, 62, 63.

686. _____. Final Report—1982 Update—Nevada State Rail Plan. Dep. Transportation, 1982, 202 pp.

687. _____. Nevada Statewide Profile, 1982-1983. Office of Community Services, 1982, 101 pp.

688. _____. Directory of Nevada Mine Operations Active Dur-

ing Calendar Year 1982. Dep. Ind. Relations, Div. Mine Insp., 1983, 60 pp.

689. _____. Transmission Pipelines, Hazardous Materials, Pipelines Locating Atlas. Public Service Commission, 1983, 135 pp.

690. Stearns, S.W. Disseminated Epithermal Precious Metals in the Santa Fe District, Mineral County, Nevada. M.S. Thesis, Stanford Univ., Stanford, CA, 1982, 109 pp.

691. Steele, G.L. Candelaria: Famous Silver Producer Reactivated After 100 Years. Min. Eng. (NY), v. 33, No. 6, 1981, pp. 658-660.

692. Stevens, D.L., and R.B. Hawkins. A Comparison of the Gold Mineralization at Jerritt Canyon, Nevada, With Other Disseminated Gold Deposits of the Basin and Range Region. Pres. at AIME Circumpacific Energy and Miner. Resour. Conf., Honolulu, HI, Aug. 1982, 13 pp.

693. Stewart, J.H., E.H. McKee, and H.K. Stager. Geology and Mineral Deposits of Lander County, Nevada. NV Bur. Mines and Geol. Bull. 88, 1977, 106 pp.

694. Stewart, J.H., P.T. Robinson, J.P. Albers, and D.F. Crowder. Geologic Map of the Piper Peak Quadrangle, Nevada-California. U.S. Geol. Surv. Geol. Quad. Map GQ-1186, 1974, scale 1:62,500.

695. Stoddard, C., and J.A. Carpenter. Mineral Resources of Storey and Lyon Counties, Nevada. NV Bur. Mines and Geol. Bull. 49, 1950, p. 89.

696. Strachen, D.G., P.M. Pettit, and R.F. Reid. The Geology of the Borealis Gold Deposit, Mineral County, Nevada. Geol. Soc. Am. Abstr. With Programs, Annu. Meeting, New Orleans, LA, 1982, p. 684.

697. Stuart, W.T. Pumping Test Evaluates Water Problem at Eureka, Nevada. Min. Eng. (NY), v. 7, No. 2, 1955, pp. 148-156.

698. Sunshine Mining Co. Annual Report, 1982. 1983, p. 6.

699. _____. Annual Report, Form 10-K, for Year Ended December 31, 1983. Securities and Exchange Commission, 1984, pp. 10-12.

700. _____. Annual Report, 1983. 1984, p. 8.

701. Sutulov, A. Intermet Molybdenum Yearbook. Alexander Sutulov/Intermet Publ., Santiago, Chile, 1982, p. 28.

702. Taylor, B.E., and J.R. O'Neil. Stable Isotope Studies of Metasomatic Ca-Fe-Al-Si Skarns and Associated Metamorphic and Igneous Rocks, Osgood Mountains, Nevada. Contributions to Mineral. and Petrology, Springer-Verlag, v. 63, 1977, pp. 1-49.

703. Taylor, H.P. O^{18}/O^{16} Evidence for Meteoric-Hydrothermal Alteration and Ore Deposition in the Tonopah, Comstock Lode, and Goldfield Mining Districts, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 68, No. 6, 1973, pp. 747-764.

704. Taylor, J.K. Geology of the Nevada Scheelite Mine, Mineral County, Nevada. M.S. Thesis, Univ. NV, Reno, NV, 1982, 94 pp.

705. Theodore, T.G., and J.N. Batchelder. Stable Isotopes and Geology of the Copper Canyon Porphyry Copper Deposits. Econ. Geol. and Bull. Soc. Econ. Geol., v. 71, No. 3, 1976, p. 703.

706. Theodore, T.G., and D.B. Blake. Geology and Geochemistry of the Copper Canyon Porphyry Copper Deposit and Surrounding Area, Lander County, Nevada. U.S. Geol. Surv. Prof. Paper 798-B, 1975, pp. B81-B86.

707. _____. Geology and Geochemistry of the West Ore Body and Associated Skarns, Copper Canyon Porphyry Copper Deposits, Lander County, Nevada. U.S. Geol. Surv. Prof. Paper 798-C, 1978, 85 pp.

708. Theodore, T.G., D.W. Blake, and E.L. Krechmer. Geology of the Copper Canyon Deposits, Lander County, Nevada. Paper in Advances in Geology of the Porphyry Copper Deposits, Southwestern North America, ed. by S.R. Titley. Univ. AZ Press, Tucson, AZ, 1982, pp. 543-550.

709. Theodore, T.G. and S.S. Howe. Geochemical and Fluid Zonation in the Skarn Environment at the Tomboy-Minnie Gold Deposits, Lander County, Nevada. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, p. 29.

710. Theodore, T.G., and W.D. Menzie. Fluorine-Deficient Porphyry Molybdenum Deposits in the Cordillera of North America. Paper in Proc. of the 6th Quadrennial I.A.G.O.D. Symp. (Tblisi, Georgian S.S.R., Aug. 1982), 1984, 673 pp.; available upon request from T.G. Turner, USGS, Menlo Park, CA.

711. Theodore, T.G., and J.T. Nash. Scientific Communication: Geochemical and Fluid Zonation at Copper Canyon, Lander County, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 68, No. 4, 1973, pp. 65-70.

712. Theodore, T.G., M.L. Silberman, and D.W. Blake. Geochemistry and Potassium-Argon Ages of Plutonic Rocks in the Battle Mountain Mining District, Lander County, Nevada. U.S. Geol. Surv. Prof. Paper 798-A, 1973, pp. A1-A24.

713. Thorndycraft, R.B. Pinson Mining Company—Mill Design. Pres. at Soc. Min. Eng. AIME Annu. Meeting, Dallas, TX, Feb. 14-18, 1982. Soc. Min. Eng. AIME preprint 82-162, 10 pp.

714. Thurston, W.R., and G.L. Bell. Daisy Fluorspar Deposit Near Beatty, Nye County, Nevada. U.S. Geol. Surv. OFR 3-209, 1949, 10 pp.

715. Tingley, J.V. Guides to Exploration in the Sierra Nevada Tungsten Province. M.S. Thesis, Mackay School of Mines, Univ. NV, Reno, NV, 1963, pp. 1, 47, fig. 15.

716. _____. Summary Report, Mineral Industry of the Wells Resource Area, Elko County, Nevada (BLM contract YA-512-CT9-156). NV Bur. Mines and Geol. OFR 81-4, 1981, 46 pp.

717. Tippett, M.C. The Geology of the Copper Basin Ore Deposits, Lander County, Nevada. M.S. Thesis, Univ. NV, Reno, NV, 1967, 30 pp.

718. Tishler, M.S., H.F. Bonham, Jr., and W.A. Oesterling. Minerals for Industry, Northern Nevada and Northwestern Utah. Sum. of Geol. Surv. of 1955-1961, Southern Pacific Co., San Francisco, CA, v. 1, 1964, 188 pp.

719. Tonopah (NV) Times-Bonanza. Houston Plans are Moving Ahead. June 16, 1983, pp. 1-10.

720. Trengove, R.R. Investigation of Comet Coalition Lead-Zinc Deposit, Lincoln County, Nevada. BuMines RI 4541, 1949, 6 pp.

721. _____. Reconnaissance of Nevada Manganese Deposits. BuMines RI 5446, 1959, 40 pp.

722. Trengove, R.R., and A.C. Johnson. Sampling Deep Ore Deposits by Rotary Drilling and Methods of Surveying and Controlling the Direction of Drill Holes. BuMines IC 7768, 1956, 3 pp.

723. Tschanz, C.M. Geology of Northern Lincoln County. Intermountain Association of Petroleum Geology Guidebook to the Geology of East Central Nevada. 11th Annu. Field Conf., UT Geol. Assoc., Salt Lake City, UT, 1960, pp. 198-208.

724. Tschanz, C.M., and E.H. Pampeyan. Geology and Mineral Deposits of Lincoln County, Nevada. NV Bur. Mines and Geol. Bull. 73, 1970, 186 pp.

725. Tunnell, G. Chemical Processes in the Formation of Mercury Ores and Ores of Mercury and Antimony. Geochim. et Cosmochim. Acta, v. 28, No. 7, 1964, pp. 1019-1037.

726. U.S. Bureau of Mines. Materials Survey—Manganese. Mater. Surv. 10 (with USGS), 1952, 538 pp.

727. _____. The Bureau of Mines Minerals Availability System and Resource Classification Manual. BuMines IC 8654, 1974, 214 pp.

728. _____. Minerals Yearbooks, 1978-1983. Ch. on Nevada, Aluminum, Antimony, Barite, Bauxite, and Alumina, Beryllium, Copper, Iron, Fluorspar, Gold, Lead, Lithium, Magnesium, Manganese, Mercury, Molybdenum, Tungsten, and Zinc.

729. _____. Mineral Commodity Summaries, 1978-1984.

730. U.S. Department of Agriculture (Forest Service). Final Environmental Impact Statement; Jerritt Canyon Project Gold Mine and Mill, Elko County, Nevada. Humboldt National Forest, Region 4. Apr. 1980, 105 pp.

731. U.S. Department of the Interior (Geological Survey). Permit Requirements for Development of Energy and Other Selected Natural Resources for the State of Nevada. Prepared for Four Corners Regional Commission and U.S. Geol. Surv., 1981, 57 pp.; available from Four Corners Regional Commission, Albuquerque, NM.

732. U.S. Department of Transportation. United States Transportation Zone Maps. Federal Railroad Administration, Office of Policy and Program Dev., 1975, 12 pp., 490 pl.; GPO, Washington, DC, 050-005-0012-7.

733. U.S. Senate. Mineral and Water Resources of Nevada. 88th Congr., 2d sess., Senate Document 87, July 23, 1964, 314 pp. (Also published as NV Bur. Mines and Geol. Bull. 65.)

734. _____. An Assessment of Factors Affecting Small Mining and Custom Milling Operations in the Western United States. 97th Congr., 2d sess., May 13, 1982, 169 pp.

735. Valcarce, J.S. The Mountain Springs Barite Mine, Lander County, Nevada. Ch. in Guidebook to Mineral Deposits of the Central Great Basin, ed. by D.R. Shawe. NV Bur. Mines and Geol. Rep. 32, 1978, pp. 49-50.

736. Valenti, P.B., C.I. Wilmot, and R.A. Heig. Anaconda Nevada Molybdenum Project. Soc. Min. Eng. AIME preprint 83-141, 1983, 7 pp.

737. Van Denburgh, A.S. Mercury in the Carson and Truckee River Systems, Nevada. U.S. Geol. Surv. OFR 73-0352, 1973, 14 pp.

738. Vanderburg, W.O. Mining and Milling Tungsten Ores. BuMines IC 6852, 1935, 47 pp.

739. _____. Reconnaissance of Mining Districts in Pershing County, Nevada. BuMines IC 6902, 1936, 56 pp.

740. _____. Reconnaissance of Mining Districts in Mineral County, Nevada. BuMines IC 6941, 1937, 79 pp.

741. _____. Reconnaissance of Mining Districts in Eureka County, Nevada. BuMines IC 7022, 1938, 66 pp.

742. _____. Reconnaissance of Mining Districts in Lander County, Nevada. BuMines IC 7043, 1939, 83 pp.

743. Van Gilder, K.L. The Manganese Ore Body at the Three Kids Mines, Clark County, Nevada. M.S. Thesis, Univ. NV, Reno, NV, 1963, 55 pp.

744. Vedensky, D.N. How the SO_2 Process Worked on the Three Kids Manganese Ore. Eng. and Min. J., v. 147, No. 7, July 1946, p. 58.

745. Vikre, P.G. Geology and Silver Mineralization of the Rochester District, Pershing County, Nevada. Ph.D. Diss., Stanford Univ., Stanford, CA, 1978, 404 pp.

746. _____. Silver Mineralization in the Rochester District, Pershing County, Nevada. Econ. Geol. and Bull. Soc. Econ. Geol., v. 76, No. 3, 1981, pp. 580-609.

747. Vine, J.D. Lithium in Sediments and Brines—How, Why, and Where to Search. Pres. at WY Geol. Assoc., Casper, WY, Jan. 3, 1975. U.S. Geol. Surv. OFR 75-86, 1975, 14 pp.

748. Vine, J.D. (ed.) Lithium Resources and Requirements by the Year 2000. U.S. Geol. Surv. Prof. Paper 1005, 1976, 162 pp.

749. Vitaliano, C.J., and E. Callaghan. Geologic Map of the Gabbs Magnesite and Brucite Deposit, Nye County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map MF-35, 1956, scale 1:24,000.

750. _____. Geology of the Paradise Peak Quadrangle, Nevada. U.S. Geol. Surv. Quad. Map GQ-250, 1963, scale 1:62,000.

751. Voskuil, W.H. Economic Aspects of the Iron Ore Industry in Nevada. NV Bur. Mines and Geol. Rep. 13, pt. A, 1966, pp. 5-14.

752. Walker, P. Canfield: U.S. Gold Production Will Hit 2M Ounces/New Mines Opening, Old Ones Expanding; Nevada Leads in Output Ahead of South Dakota, Utah. Am. Met. Market, Mar. 11, 1983, pp. 3, 7.

753. Walker, W.W., and D.N. Stevens. The Earth Sciences-National Southwire Alunite-to-Alumina Project. Paper in Light Metals, ed. by Forberg and Helge. AIME, v. 3, 1974, pp. 683-688.

754. Wallace, A.B., and F.W. Bergwall. Geology and Gold Mineralization at the Dee Mine, Elko County, Nevada. Abstr. No. 33,390 in Abstracts With Programs, 1984. 97th Annu. Meeting, Geol. Soc. Am., Nov. 5-8, 1984, Reno, NV, p. 686.

755. Wallace, R.E., N.J. Silberling, W.P. Irwin, and D.B. Tatlock. Geologic Map of the Buffalo Mountain Quadrangle, Pershing and Churchill Counties, Nevada. U.S. Geol. Surv. Quad. Map GQ-821, 1969, scale 1:62,500.

756. Wallace, R.E., D.B. Tatlock, N.J. Siberling, and W.P. Irwin. Geologic Map of the Unionville Quadrangle, Pershing County, Nevada. U.S. Geol. Surv. Quad. Map GQ-820, 1969, scale 1:62,500.

757. Wallace (ID) Miner. Gulf Oil To Develop Ward Mountain Mine. June 8, 1978, p. 2.

758. _____. Molybdenum Found in Nye County, Nevada. Jan. 4, 1979, p. 2.

759. _____. Development of Big Moly Mine in Nevada Nears Reality. July 12, 1979, p. 1.

760. _____. Silver King Sells Interest in Claims. Aug. 30, 1979, p. 2.

761. _____. Cyprus Files Plan of Operation in Nevada. Aug. 28, 1980, p. 4.

762. _____. Nevada's Mohawk Mine Producing. Dec. 11, 1980, p. 2.

763. _____. Oxymin Shuts Down Candelaria. June 24, 1982, p. 4.

764. _____. Oxymin Shuts Down Candelaria Mine as Silver Drops Below $6. July 22, 1982, p. 2.

765. _____. Profit Predicted for 16-to-1 Mine. Sept. 9, 1982, p. 5.

766. _____. Ore Body Found at Borealis. Jan. 6, 1983, p. 3.

767. _____. Round Mountain Gold Mine for Sale. Apr. 21, 1983, p. 3.

768. _____. Houston Reopens Gold Mine. July 28, 1983, p. 2.

769. _____. Cominco Will Work Buckhorn Gold Deposit. Sept. 22, 1983, p. 3.

770. _____. Pinson Pegs Fall Opening. Aug. 30, 1984, p. 1.

771. Wall Street Journal (New York). U.S. Steel Confirms Iron and Copper Finds in Nevada, Sees Steel Price Rise in 1970. Dec. 19, 1969, p. 6.

772. _____. FMC Finds Deposits of Gold and Silver Ore. Jan. 17, 1984, p. 39.

773. Wargo, J.G. The Next Exploration Stage for Carlin-Type Gold Deposits. Min. Eng. (NY), v. 31, No. 9, 1979, pp. 1321-1323.

774. Warner, L.A., W.T. Holser, V.R. Wilmarth, and E.N. Cameron. Localities in Nevada. Ch. in Occurrence of Nonpegmatite Beryllium in the United States. U.S. Geol. Surv. Prof. Paper 318, 1959, pp. 63-85.

775. Warren, R.E. Mine Closures Signal Dramatic Turn-Down in Mining Industry. NV Min. Assoc. Bull., v. 6, No. 3, 1982, pp. 1-3, 20.

776. Watson, B.N. Large Low Grade Silver Deposits in N. America. World Min., v. 30, No. 3, 1977, pp. 44-49.

777. _____. Bulk Tonnage, Low-Grade Silver Deposits—Update 1980. NV Bur. Mines and Geol. Rep. 36, 1983, pp. 36-41.

778. Watson, I. Barytes—U.S. Drilling Downturn Weighs Heavily on the Market. Ind. Min. (London), No. 183, 1982, pp. 21-57.

779. Wells, J.D., and J.E. Elliott. Preliminary Geologic and Geochemical Maps of the Buckhorn Mine Area, Eureka County, Nevada. U.S. Geol. Surv. OFR 69-315, 1969, 43 pp.

780. _____. Geochemical Reconnaissance of the Cortez-Buckhorn Area, Southern Cortez Mountains, Nevada. U.S. Geol. Surv. Bull. 1312P, 1971, 18 pp.

781. Wells, J.D., J.E. Elliott, and J.D. Obradovich. Age of the Igneous Rocks Associated With Ore Deposits, Cortez-Buckhorn Area, Nevada. U.S. Geol. Surv. Prof. Paper 750-C, 1971, pp. C127-C135.

782. Wells, J.D., and M.L. Silberman. K-Ar Age of Mineralization at Buckhorn, Eureka County, Nevada. Isochron/West, No. 8, 1973, p. 37.

783. Wenatchee (WA) World. Asamera Mining To Call for Bids for Gold Mining Shafts, Tunnels. June 16, 1983, p. 14.

784. _____. Gold in Nevada. Sept. 9, 1983, p. 17.

785. Western Miner (Vancouver, BC). Alive in the West: Canadian Exploration and Mining; Wide-Ranging Interests of Placer Development. V. 57, No. 4, Apr. 1984, pp. 9-12.

786. _____. Lacana Mining Active in Precious Metals. V. 57, No. 4, Apr., 1985, pp. 24-25.

787. Western Mining Letter (Bisbee, AZ). Cominco's Buckhorn Gold Mine Set to Come on Line in Early 1984. No. 12, Nov. 7, 1982, p. 3.

788. Western Mining News (Spokane, WA). Day Acquires Victoria Mine. May 25, 1979, p. 1.

789. _____. Silver King Gets $1 Million in Asset Sales. Aug. 24, 1979, p. 1.

790. _____. Silver King Mines' New Production Puts Them in Top 10 in Silver. June 12, 1981, p. 1.

791. Westgate, L.G., and A. Knopf. Geology and Ore Deposits of the Pioche District, Nevada. U.S. Geol. Surv. Prof. Paper 171, 1932, 75 pp.

792. Westra, G. Porphyry Copper Genesis at Ely, Nevada in Papers on Mineral Deposits of Western North America. NV Bur. Mines and Geol. Rep. 33, 1979, pp. 127-140.

793. _____. The Use of Geochemistry in the Search for Molybdenum Deposits. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, p. 28.

794. Westra, G., and S.B. Keith. Classification and Genesis of

Stockwork Molybdenum Deposits. Econ. Geol. and Bull. Soc. Econ. Geol., v. 76, No. 4, 1981, pp. 844-873.

795. White, L. Heap Leaching Will Produce 85,000 oz/yr of Dore Bullion for Smoky Valley Mining. Eng. and Min. J., v. 178, No. 7, 1977, pp. 70-72.

796. _____. Nevada Barite Output Up Sharply in '70's. Paper in Engineering and Mining Journal Operating Handbook of Mineral Surface Mining and Exploration, ed. by R. Hoppe. McGraw-Hill, v. 2, 1978, pp. 444-445.

797. Whitebread, D.H. Geologic Map of the Wheeler Peak and Highland Ridge Further Planning Areas, White Pine County, Nevada. U.S. Geol. Surv. Misc. Field Studies Map, MF 1343-A, 1982, scale 1:62,500.

798. Whitebread, D.H., and D.E. Lee. Geology of the Mount Wheeler Mine Area, White Pine County, Nevada. Ch. 193 in Short Papers in the Geologic and Hydrologic Sciences, Articles 147-292. U.S. Geol. Surv. Prof. Paper 424-C, 1961, pp. C120-C122.

799. Whittemore, R.N. Geology and Geochemistry of the Quito Prospect. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, p. 32.

800. Wiegand, J. Variation in Composition of Three Granitic Stocks Associated With Ore Deposits, Lincoln County, Nevada. M.S. Thesis, Columbia Univ., New York, NY, 1961, 104 pp.

801. Willden, R. Geology and Mineral Deposits of Humboldt County, Nevada. NV Bur. Mines and Geol. Bull. 59, 1964, 154 pp.

802. Willden, R., and R.C. Speed. Geology and Mineral Deposits of Churchill County, Nevada. NV Bur. Mines and Geol. Bull. 83, 1974, 95 pp.

803. Wilson, B.R., and S.W. Laule. Tectonics and Sedimentation Along the Antler Orogenic Belt of Central Nevada. Paper in Proceedings of Rocky Mountain Association of Geologists/Utah Geological Association Basin and Range Symposium and Great Basin Field Conference (Las Vegas, NV, Oct. 7-11, 1979), ed. by G.W. Newman and H.D. Goode. RMAG, 1979, pp. 81-92.

804. Wilson, C.W. Bouguer Gravity Map of Clayton Valley, Nevada. U.S. Geol. Surv. OFR 75-333, 1975, scale 1:62,500.

805. Wilson, W.L. Heap Leaching Gold Ore, Eureka Windfall Gold Mine, Eureka, Nevada. Paper in Proceedings From a Symposium on Gold (Reno, NV, Apr. 21-24, 1980). Univ. NV, Reno, NV, 1980, 10 pp.

806. Wilson, W.R. Geology of the Robinson Mining District, Nevada. Guidebook to Mineral Deposits of the Central Great Basin, Nevada. NV Bur. Mines and Geol. Rep. 32, 1978, pp. 55-61.

807. Wise, F. Roasting Improves Gold Recovery at Getchell Mine. Min. Congr. J., v. 28, No. 4, 1942, pp. 48-51.

808. Wise, F., and C.W. Work. Metallurgy and Milling Practice at Getchell Mine. Am. Inst. of Min. and Metall. Eng., Tech. Pub. No. 1260, 1940, 9 pp.

809. Wisser, E. Relation of Ore Deposition to Doming in the North American Cordillera. Geol. Soc. Am. Memoir 77, 1960, 117 pp.

810. Wittkopp, R.W., R.L. Parrat, and W.R. Bruce. Geology and Mineralization at the Relief Canyon Gold Deposit, Pershing County, Nevada. Abstr. in Exploration for Ore Deposits of the North American Cordillera. Symp. of Assoc. Expl. Geochem., Reno, NV, Mar. 25-28, 1984, p. 46.

811. Wood, H.B. Fluorspar. Eng. and Min. J., v. 173, No. 3, 1972, pp. 151-153.

812. _____. Fluorspar Briquetters Expanding Output. Eng. and Min. J., v. 179, No. 7, 1978, pp. 81-83.

813. Woodcock, J.R. Molybdenum—A Guide to North American Resources and Ongoing Plans for Development. Eng. and Min. J., v. 180, No. 8, 1979, pp. 86-89.

814. Woolf, J.A., and A.P. Towne. Ore-Testing Studies on Gold and Gold-Silver Deposits. BuMines RI 3765, 1944, 63 pp.

815. Worl, R.G., R.E. Van Alstine, and A.V. Heyl. Fluorite in the United States (Exclusive of Hawaii). U.S. Geol. Surv. Map MR-60, 1974, scale 1:3,168,000.

816. Worl, R.G., R.E. Van Alstine, and D.R. Shawe. Fluorine. Ch. in United States Mineral Resources, ed. by D.A. Brobst, and W.P. Pratt. U.S. Geol. Surv. Prof. Paper 820, 1973, pp. 223-235.

817. World Mining (San Francisco). Esperanza and Ithaca Peak Ore Grades, Reserves, and Costs. V. 5, No. 3, 1969, pp. 51-52.

818. _____. What's Going on in World Mining—United States: Nevada; Duval Corporation, Battle Mountain Production and Costs. V. 8, No. 7, 1972, p. 41.

819. _____. Short Tons of Ore Mined and Waste Stripped at Key United States Open Pit Mines in 1968, 1969, 1970, and 1971. V. 8, No. 7, 1972, p. 144.

820. _____. Short Tons of Ore Mined and Waste Stripped at Key United States Open Pit Mines in 1970, 1971, 1972, and 1973. V. 27, No. 7, 1974, pp. 198-199.

821. _____. Short Tons of Ore Mined and Waste Stripped at Key United States Open Pit Mines in 1971, 1972, 1973, and 1974. V. 28, No. 7, 1975, p. 204.

822. _____. What's Going on in World Mining—United States: Nevada; Yerington District Will be a Major Future Porphyry Copper Producer. V. 29, No. 3, 1976, p. 82.

823. _____. What's Going on in World Mining—United States: Nevada; Tenneco Drops Out, Asarco Makes Higher Bid for Shares To Control Anaconda. V. 29, No. 5, 1976, pp. 97-98.

824. _____. Oil Company, ARCO, Purchases Copper Company. V. 30, No. 2, 1977, pp. 64-68.

825. _____. Short Tons of Ore Mined and Waste Stripped at Key United States Open Pit Mines in 1973, 1974, 1975, and 1976. Table in 1976 Review and Summary of United States Underground, Open Pit Mines. V. 30, No. 8, 1977, pp. 54-61.

826. _____. Short Tons of Ore Mined and Waste Stripped at Key United States Open Pit Mines in 1974, 1975, 1976, and 1977. In 1977 Review and Summary of United States Open Pit, Underground Mines. V. 31, No. 8, 1978, pp. 54-60.

827. _____. U.V. Industries Drills MoS_2 Deposit. V. 31, No. 8, 1978, p. 69.

828. _____. What's Going on in World Mining—United States: Nevada. V. 31, No. 10, 1978, p. 187.

829. _____. Anaconda—Atlantic Richfield Must Divest Cu Reserves. V. 32. No. 5, 1979, p. 65.

830. _____. What's Going on in World Mining—United States: Nevada; Utah Announces Plans to Reopen Springer Mine. V. 32, No. 13, 1979, p. 82.

831. _____. What's Going on in World Mining—United States: Nevada; Cyprus Studies Au Pit at Northumberland. V. 33, No. 5, 1980, p. 86.

832. _____. Newmont Will Increase Gold Production With Maggie Creek Ore. V. 34, No. 1, 1981, pp. 47-48.

833. _____. What's Going on in World Mining—United States: Nevada. V. 34, No. 5, 1981, p. 92.

834. _____. What's Going on in World Mining—United States: Nevada; Newmont Raises Reserves Estimates for Gold Quarry. V. 34, No. 6, 1981, pp. 147, 150.

835. _____. What's Going on in World Mining—United States: Nevada; Nevada's Alligator Ridge Gold Mine Comes on Stream. V. 34, No. 8, 1981, p. 65.

836. _____. Victoria Copper Mine Shut Down by Day Mines. V. 34, No. 10, 1981, p. 76.

837. _____. What's Going on in World Mining—United States: Nevada; Nevada May be the Next Big Molybdenum Producer. V. 34, No. 12, 1981, p. 77.

838. _____. What's Going on in World Mining—United States: Nevada; Duval Discovers Silver and Gold Near Battle Mountain. V. 35, No. 1, 1982, p. 35.

839. _____. What's Going on in World Mining—United States: Nevada, V. 35, No. 6, 1982, p. 105.

840. Worthington, J.E. Bulk Tonnage Gold Deposits in Volcanic Environments. Paper in Relations of Tectonics to Ore Deposits in the Southern Cordillera. AZ Geol. Soc. Digest, v. 14, 1981, pp. 263-270.

841. Wright, L.B. Southern Pacific's Geologists Find 132,000 Tons Low Grade Iron Ore. Min. World, Mar. 1960, pp. 26-31.

842. Wright, W.A. Molybdenite Mineralization at the Hall Property, Nye County, Nevada. Geol. Soc. Am. Abstr., v. 8, No. 6, 1976, pp. 1176-1177.

843. Wyant, D.G., and D.M. Lemmon. Tungsten Deposits in the

Tem Piute District, Lincoln County, Nevada. U.S. Geol. Surv. OFR 51-89, 1951, 12 pp.

844. Wyman, W.F., and S.F. Ravitz. Sulfur Dioxide Leaching Tests on Various Western Manganese Ores. BuMines RI 4077, 1947, 12 pp.

845. Yates, R.G. Quicksilver Deposits of the Opalite District, Malheur County, Oregon and Humboldt County, Nevada. U.S. Geol. Surv. Bull. 931-N, 1942, pp. 319-348.

846. Yih, S.W.H., and C.T. Wang. Tungsten—Sources, Metallurgy, Properties, and Applications. Plenum Press, New York and London, 1980, pp. 32-34.

847. Young, A.R. The 16 to 1 Mine, Sunshine Mining Company, Silver Peak, Nevada. Section in an In-Depth Study of 5 New Silver and Gold Mines. 1983, 16 pp.; available from Northwest Min. Assoc., 636 Peyton Bldg., Spokane, WA, 99201.

848. Zadra, J.B. Milling and Processing Tungsten. BuMines IC 7912, 1959, 120 pp.

APPENDIX A.—LIST OF ABBREVIATIONS

CHEMICAL SYMBOLS

Ag	Silver.
Al	Aluminum.
Al_2O_3	Alumina.
APT	Ammonium paratungstate.
Au	Gold.
Ba	Barium.
$BaSO_4$	Barium sulfate, barite.
Be	Beryllium.
Ca	Calcium.
CaF_2	Fluorite, fluorspar.
CaO	Calcium oxide.
Co	Cobalt.
Cu	Copper.
F	Fluorine.
Fe	Iron.
Hg	Mercury.
Li	Lithium.
LiO_2	Lithia.
Li_2CO_3	Lithium carbonate.
Mg	Magnesium.
MgO	Magnesia.
Mn	Manganese.
Mo	Molybdenum.
MoS_2	Molybdenite, molybdenum sulfide.
Ni	Nickel.
Pb	Lead.
S	Sulfur.
Sb	Antimony.
Se	Selenium.
V	Vanadium.
V_2O_5	Vanadium pentoxide.
W	Tungsten.
WO_3	Tungsten trioxide.
Zn	Zinc.

MISCELLANEOUS ABBREVIATIONS AND SYMBOLS

BLM	(U.S.) Bureau of Land Management.
CCD	Countercurrent decantation.
Insol.	Insoluble.
MRDS	Mineral Resources Data System.
ppt	Precipitation.
quad	Quadrangle.
R	Range.
Sec.	Section.
T	Township.
USBM	(U.S.) Bureau of Mines.
USGS	U.S. Geological Survey.
°	Degree.
′	Minute of arc (plane angle).
″	Second of arc (plane angle).

APPENDIX B.—COMMON CONVERSION FACTORS[1]

To convert to *kilograms* (*kg*) from—	Multiply by—
Grams	**0.001**
Troy ounces	.0311035
Pounds (avoirdupois)	.453592
Short tons	907.185
Metric tons	1,000.0

To convert to *metric tons* (*t*) from—	Multiply by—
Grams	0.000001
Pounds (avoirdupois)	.000453592
Kilograms	**.001**
Short tons	.907185

To convert to *troy ounces* (*tr oz*) from—	Multiply by—
Grams	0.0321507
Pennyweights	**.05**
Pounds (avoirdupois)	14.5833
Kilograms	32.1507
Short tons	29,166.7
Metric tons	32,150.7

To convert to *pounds* (*lb*) from—	Multiply by—
Grams	0.00220462
Troy ounces	.0685714
Kilograms	2.20462
Short tons	**2,000.0**
Metric tons	2,204.62

To convert to *short tons* (*ton*) from—	Multiply by—
Grams	0.00000110231
Pounds (avoirdupois)	**.0005**
Kilograms	.00110231
Metric tons	1.10231

To convert to *76-lb flasks* from—	Multiply by—
Grams	0.0000290082
Pounds (avoirdupois)	.0131579
Kilograms	0.0290082
Short tons	26.3158
Metric tons	29.0082

To convert to *grams per metric ton* from—	Multiply by—
Troy ounces per short ton	34.2857

To convert to *troy ounces per short ton* from—	Multiply by—
Grams per metric ton	0.0291667

To convert to *cubic meters* (m^3) from—	Multiply by—
Acre feet	1,233.6192

[1]Except for cubic meter conversion to acre feet, conversion factors are from BuMines Statistical Standard 1–83, June 6, 1983.

Note: Boldface conversion factors are exact.

☆U.S. GOVERNMENT PRINTING OFFICE: 1985 484 876 32870

M 74

THE LIBRARY OF CONGRESS

WERT
BOOKBINDING
Grantville, Pa.
Jan — Feb 1986
We're Quality Bound

LIBRARY OF CONGRESS
0 002 955 977 6